# McMullin Area Groundwater Sustainability Agency Water Banking Feasibility Study

Fresno County June 2022

> Prepared for: McMullin Area Groundwater Sustainability Agency Fresno County

> > Prepared by: Provost & Pritchard Consulting Group 455 W Fir Ave, Clovis, California 93611

### COPYRIGHT 2021 by PROVOST & PRITCHARD CONSULTING GROUP ALL RIGHTS RESERVED

Provost & Pritchard Consulting Group expressly reserves its common law copyright and other applicable property rights to this document. This document is not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to a third party without first obtaining the written permission and consent of Provost & Pritchard Consulting Group In the event of unauthorized reuse of the information contained herein by a third party, the third party shall hold the firm of Provost & Pritchard Consulting Group harmless, and shall bear the cost of Provost & Pritchard Consulting Group's legal fees associated with defending and enforcing these rights.

### **Report Prepared for:**

### McMullin Area Groundwater Sustainability Agency

275 S. Madera Avenue, Suite 301 Kerman, CA 93630

Contact: Matt Hurley (559) 515-3339

### **Report Prepared by:**

### **Provost & Pritchard Consulting Group**

Randy Hopkins Terry Erlewine Lynn Groundwater Moeller

Contact: Randy Hopkins (559) 449-2700

# Table of Contents

Exe	cutive	Summa	ry	1				
1	Intro	oduction	1	1-1				
2	Geo	logic Ex	ploration & Site Identification	2-1				
	2.1	Geolog	gic and Hydrogeologic Information	2-1				
	2.2	Soil Bo	orings	2-8				
		2.2.1	Site Locations	2-8				
		2.2.2	Soil Boring Data	2-8				
		2.2.3	Summary of Geologic Findings					
3	Ope	rations I	Evaluation	3-1				
	3.1	Opera	tions	3-1				
	3.2	Water	Quality					
		3.2.1	Exchange and/or Recharge Surface Water Quality					
		3.2.2	Groundwater Quality					
4	Infra	astructur	re Requirements	4-1				
	4.1	General Description						
	4.2	Design Considerations						
	4.3	Faciliti	ies	4-3				
	4.4	Projec	t Costs	4-4				
5	Regi	ulatory C	Considerations	5-1				
	5.1	Permit	ts and Approvals	5-1				
	5.2	Enviro	onmental	5-3				
6	Part	icipant I	nvolvement	6-1				
	6.1	Physic	cal Aspects of Aquaterra Groundwater Bank	6-1				
	6.2	Financ	cial Aspects of Aquaterra Groundwater Bank	6-2				
7	Con	clusions	and Recommendations	7-1				
	7.1	Summ	ary of Findings	7-1				
		7.1.1	Geology and Soils	7-1				
		7.1.2	Groundwater Quality	7-1				
		7.1.3	Project Operations	7-1				
		7.1.4	Infrastructure Refinement	7-2				
		7.1.5	Regulatory Considerations	7-2				
		7.1.6	Participant Involvement					

	7.2	Recommended Next Steps	.7-3	3
8	Bibli	ography/References	.8-2	1

# List of Figures

Figure ES-1 Project Location	ES-4
Figure 2-1 Soils and Near Surface Features - Geologic Facies	2-2
Figure 2-2 Soils and Near Surface Features- Geologic Deposits	2-3
Figure 2-3 Initially-Selected Regions of MAGSA Potentially Suitable for Groundwater Recharge	2-6
Figure 2-4 Groundwater Elevation Contours	2-7
Figure 2-5 Soil Boring Locations	2-10
Figure 3-1 Recharge Deliveries	3-4
Figure 3-2 Extraction Facilities	3-5
Figure 3-3 Mendota Pool Diversions/Delta-Mendota Canal Capacity	3-6
Figure 3-4 Mendota Pool Diversions/Delta-Mendota Canal Capacity- Historical Period	3-7
Figure 3-5 Lower Delta-Mendota Canal with Aquaterra Groundwater Bank Typical Recharge Year Pu Pattern	
Figure 3-6 Lower Delta-Mendota Canal with Aquaterra Groundwater Bank Typical Extraction Year T Pattern	
Figure 3-7 Delta-Mendota Canal Inflow to Mendota Pool Salinity	3-13
Figure 3-8 Historical Total Dissolved Solids in Groundwater	3-15
Figure 3-9 MAGSA Water Bank WQ Tests	3-18
Figure 4-1 Project Map	4-2
Figure 5-1 CNDDB	5-6
Figure 5-2 CPAD Protected Areas	5-7
Figure 5-3 Critical Habitat	5-8
Figure 5-4 Vegetation	5-9
Figure 5-5 Waterbody and Wetlands	5-10
Figure 6-1 Preliminary Schedule	6-1

# List of Tables

Table ES-1 Total Capital Project Costs	ES-2
Table 2-1 Soil Samples Submitted for Sieve Analysis	2-9

### McMullin Area Groundwater Sustainability Agency Water Bank Feasibility Study

Table 2-2 Soil Boring Ranking Based on Field Estimated Percentages of Permeable Material	2-11
Table 3-1 CALSIM SWP DCR Study	3-2
Table 3-2 Computed DMC Inflows to Mendota Pool	3-8
Table 3-3 Aquaterra Groundwater Bank Program Characteristics	3-9
Table 3-4 MAGSA Water Bank Recharge/Extraction Area Representative Groundwater Chemical An 17	alyses 3-
Table 3-5 Surface Water Quality Thresholds (Metals)	3-19
Table 3-6 Surface Water Quality Thresholds (Salinity)	3-19
Table 4-1 Summary of Capital Costs	4-4
Table 4-2 Cost of Storage Capacity	4-4
Table 4-3 Baseline Annual Costs	
Table 4-4 Recharge Costs	4-5
Table 4-5 Recovery Costs	4-5
Table 5-1 Permits and Approvals	5-1
Table 1 Aquaterra Groundwater Bank Program Characteristics	

## List of Appendices

Appendix A – Kenneth D. Schmidt & Associates Memorandum

Appendix B – Soil Boring Logs

Appendix C – Historical Mendota Pool Diversion Data

Appendix D – Analysis of Water Needs for Potential Project Participants

Appendix E – Jensen Canal Concept Designs

Appendix F – East-Side Canal Concept Designs

Appendix G – Project Capital Costs

Appendix H – Special Status Plant and Animal Species List Appendix I – California Natural Diversity Database Data

Appendix J – California Historical Resources Information System Search 20-139

Appendix K – Detailed Preliminary Schedule

## Abbreviations

AF	acre-feet
CCID	Central California Irrigation District
CDFW	California Department of Fish and Wildlife
CEQA	
cfs	
CHRIS	California Historical Resources Information System
CL	
CNDDB	
CNPS	California Native Plant Society
County	
CPAD	
CSLC	California State Lands Commission
CVFPB	Central Valley Flood Protection Board
CVP	Central Valley Project
DCP	Dust Control Plan
DMC	Delta-Mendota Canal
EC	Electrical Conductivity
EIR	Environmental Impact Statement
ESA	Endangered Species Act
GAMA	Groundwater Ambient Monitoring & Assessment Program
gpm	
GSA	Groundwater Sustainability Agency
GSP	Groundwater Sustainability Plan
ICs	
ISR	
ITP	
JID	James Irrigation District
JPA	Joint Powers Authority
KDSA	
Ksat	relative saturated hydraulic conductivity
	Least Environmentally Damaging Practicable Alternative
LSAA	Lake and Streambed Alteration Application

## McMullin Area Groundwater Sustainability Agency Water Bank Feasibility Study

MAGSA	McMullin Area Groundwater Sustainability Agency
mg/L	
ML	silts
MOs	measurable objectives
MTs	minimum thresholds
NEPA	National Environmental Policy Act
NMFS	National Marine Fisheries Service
NPDES	National Pollution Discharge Elimination System
OHP	
PG&E	Pacific Gas and Electric
Program	Groundwater Banking Program
Provost & Pritchard	Provost & Pritchard Consulting Group
РТО	
RWQCB	
SAGBI	Soil Agricultural Groundwater Banking Index
SHPO	State Historic Preservation Officer
SJVAPCD	
SLDMWA	
SM	silty sands
SP	
SWP	
SWPPP	Stormwater Pollution Prevention Plan
TDS	total dissolved solids
USACE	
USBR	United States Bureau of Reclamation
USDA	
USCS	
USFWS	U.S. Fish and Wildlife Service
WD	
WDR	Waste Discharge Requirements

## **Executive Summary**

This study builds upon the fatal flaws analysis to better understand the feasibility of developing the Aquaterra Groundwater Bank in the McMullin Area Groundwater Sustainability Agency (MAGSA) area with the interested parties. Additionally, work includes a review of the water quality at Mendota Pool and within MAGSA, refinement of project costs, identification of groundwater banking sites, development of an understanding of site-specific hydrogeologic conditions, and a more detailed understanding of issues related to diverting water from and returning water to the Mendota Pool.

### Geologic Exploration and Site Identification

Available published information was used to preliminarily identify portions of the Groundwater Sustainability Agency (GSA) that appear geologically suited for groundwater recharge. Several geologic properties were mapped to evaluate regions within MAGSA that appear better suited for recharge of surface water supplies to groundwater. Geologic properties reviewed in this evaluation include soil texture and saturated hydraulic conductivity, the Soil Agricultural Groundwater Banking Index (SAGBI) rating, geologic facies, geologic deposits, groundwater contours, and presence/absence of regional aquitards. Groundwater recharge regions were identified based the combination of these properties that appear suitable for recharge operations.

Based on the findings discussed in **Section 2.1**, soil borings were drilled in the five regions that were identified as potentially favorable for groundwater recharge (Site 1 through Site 5). The purpose of the soil borings was to collect initial location specific soils information to begin near surface characterization of geologic conditions within the five regions. The collected information will be beneficial in helping the GSA narrow down the list of potential groundwater recharge locations to better focus future efforts, studies, and design of a groundwater banking program.

### **Operations Evaluation**

The Aquaterra Groundwater Bank has been analyzed primarily for use by State Water Project (SWP) contractors and Central Valley Project (CVP) contractors, but can also be made available for MAGSA landowners, Kings River water users and other potential users. Water Bank users would access the groundwater bank through use of available capacity in the Delta-Mendota Canal and Mendota Pool. For SWP contractors, recharge water would be delivered to Mendota Pool from October through April, when existing Delta-Mendota Canal usage would be at low levels based on review of historical records. The limitation of recharge to an October through April period is a design assumption that is intended to be conservative. In actual operation, there are many periods outside of this seven-month period when capacity for recharge would often be available. CVP South of Delta contractors could recharge water on a similar schedule as for SWP contractors. Recovered groundwater would be returned to Mendota Pool for exchange with existing water users by making an equivalent amount available at San Luis Reservoir or within either system generally. As described in this document, the Mendota Pool refers to the reservoir upstream of Mendota Dam, which has hydraulically connected arms on both the Fresno Slough and San Joaquin River channels. Recovery would be limited by the ability to do exchanges with Mendota Pool water users, which (based on review of historical operations) would be feasible from May through September. Other (non-SWP) project participants could have more flexibility with the recharge and recovery operations depending on their specific circumstances. This report does not address multitude of possible agreements between existing Delta-Mendota Canal and Mendota Pool water users that could facilitate exchange of recovered water from the Aquaterra Groundwater Bank.

The storage capacity available for the Aquaterra Groundwater Bank is approximately, and conservatively, estimated to be at least 1.8 million acre-feet. This estimate of available groundwater storage is based on 2016 groundwater levels and data on specific yields in the aquifer, with a limitation on storage being no higher than

30-feet below the land surface. Total storage capacity, physical recharge capacity and physical recovery capacity are not expected to be limiting factors in project development. Based on anticipated participant operational banking needs, the recovery capacity and the ability to exchange recovered water at Mendota Pool during drought periods are the likely limiting factors for overall project capacity.

An initial project formulation was also developed based on 800,000 AF of priority banking storage capacity. This priority project formulation would provide for annual recharge capacity of 208,000 AF with instantaneous capacity of 770 cfs. The recovery capacity for this priority project formulation would be 146,000 AF per year, with instantaneous recovery of 480 cfs.

The project characteristics included here were developed to support facility design and project formulation and are expected to be revised in the course of final design based on a level of participant interest and more specific information on participant operational needs.

### Infrastructure

The Aquaterra Groundwater Bank infrastructure consists of:

- 72 miles of canal conveyance between 300 and 500 cfs in capacity,
- 22 lift pump stations,
- 3,900 acres of recharge basins providing 1,540 acre-feet per day of recharge capacity,
- 87 recovery wells providing 960 AF per day of recovery capacity, and
- 55 monitoring wells.

**Figure ES-0-1** shows the overview layout of the groundwater bank facilities. The water is initially pumped from three connections from the Fresno Slough arm of the Mendota Pool into the Jensen and American Canals. These canals flow east until they intersect the East-Side Canal. The East-Side canal follows the eastern MAGSA boundary north and south of Jensen to deliver water to five recharge site locations. After the water has been recharged and an interested party is ready to recover the water, recovery wells that are spread out among the basins will return the water to the canal. The canals will then return the water to the starting point at the Fresno Slough.

Capital, annual, operations and maintenance costs were analyzed for the project. These costs are summarized in **Table ES-0-1**.

Range of Total Capital Costs	
Low	\$478,250,000
High	\$777,156,000
Range of Capital Costs (\$/AF Storage Capacity)	
Low	\$598
High	\$971
Range of Baseline Annual Costs	
Low	\$26,383,500
High	\$42,873,600
Recovery Costs (\$/AF)	\$164
Recharge Costs (\$/AF)	\$93

#### Table ES-0-1 Total Capital Project Costs

### **Regulatory and Policy Analysis**

Construction and operation of the water bank and conveyance will require coordination, consultation and permits from multiple agencies with jurisdiction for various aspects of the Project. This section looks at permits that may be needed for groundwater banking and conveyance projects. During the environmental review process, the need for the various permits and approvals will be further refined.

### **Participant Involvement**


The MAGSA groundwater banking program has been formulated based on participation of outside water agencies potentially including SWP contractors, Kings River water users, CVP Contractors and other water agencies. MAGSA would develop, construct and operate the facility on behalf of the banking participants. The development, construction and operation would proceed under contracts between MAGSA and banking participants, which would provide for ongoing review of project costs and characteristics by banking participants.

The participant agreements would generally provide for participant payment for the costs of MAGSA groundwater banking program facilities and actual operational costs. Participants would generally have priority access to banking recharge and recovery facilities, with MAGSA having secondary access to those facilities for its own uses on an as-available basis. MAGSA would operate the groundwater bank and maintain banking operations accounts which would reflect physical operational losses, likely as a negotiated percentage included in the project agreements. The participant agreements, including preliminary indication of operational arrangements, are in development and will be finalized in the near future. The general parameters identified above may be refined as agreed to by project participants in the course of program development.

### Recommendations

After discussions with MAGSA, the initial project formulation was developed based on 800,000 AF of banking storage. This project formulation would provide for annual recharge capacity of 208,000 AF with instantaneous capacity of 770 cfs. The recovery capacity for this project formulation would be 146,000 AF per year, with instantaneous recovery of 480 cfs. This alternative has multiple points of diversion from the Fresno Slough arm of the Mendota Pool that allows for flexibility for pumping into the project canals.

Additional storage capacity will likely be available within the water banking facilities, but this study has concentrated on the initial priority offering for the first 800,000 acre-feet of storage only.



4/22/2022 : G:\McMullin GSA-2659\265921004-MAGSA GW Bank\400 GIS\Map\MAGSA\_GroundwaterBank\_Overview.mxd

## 1 Introduction

McMullin Area Groundwater Sustainability Agency (MAGSA) has spoken with many interested parties on both the State Water Project (SWP) and Central Valley Project (CVP) systems about potentially developing a groundwater banking program and facilities. Provost & Pritchard Consulting Group (Provost & Pritchard) recently completed a draft fatal flaws analysis that reviewed the program at a high level to ascertain water supply availability, geologic conditions, environmental constraints, infrastructure needs, and the associated costs. Many of the interested parties have expressed continued interest in the Project.

Conceptually, water from an interested party would be delivered from the O'Neil Forebay through the Delta-Mendota Canal (DMC) and to the Mendota Pool. Once in the Fresno Slough arm of the Mendota Pool, water would then be diverted to MAGSA and conveyed to a dedicated groundwater banking facility, delivered to growers for them to utilize "in-lieu" of pumped groundwater, delivered to growers for them to recharge through an on-farm recharge program, or through a combination of these approaches. For the purposes of this analysis, it is assumed MAGSA will develop dedicated recharge and recovery facilities in order to develop a more conservative opinion of capital costs. Water recovered in dry years would be collected in MAGSA and returned to the Mendota Pool, where it would be exchanged through the DMC for a water supply in the San Luis Reservoir on the California Aqueduct.

This feasibility study builds upon the fatal flaws analysis to better understand the feasibility of building facilities in MAGSA that would facilitate a groundwater banking program with the interested parties. Additionally, work includes a review of water quality at the Mendota Pool and within MAGSA, refinement of project costs, identification of groundwater banking sites, development of an understanding of site-specific hydrogeologic conditions, and a more detailed understanding of issues related to diverting water from and returning water to the Mendota Pool.

## 2 Geologic Exploration & Site Identification


## 2.1 Geologic and Hydrogeologic Information

### <u>Approach</u>


Available published information was used to preliminarily identify portions of the GSA that appear geologically suited for groundwater recharge. Several geologic properties were mapped to evaluate regions within MAGSA that appear better suited for recharge of surface water supplies to groundwater based on the totality of the geologic properties. Geologic properties reviewed in this evaluation include soil texture and saturated hydraulic conductivity, the Soil Agricultural Groundwater Banking Index (SAGBI) rating, geologic facies, geologic deposits, groundwater contours, and presence/absence of regional aquitards.

As shown on **Figure 2-1** and **Figure 2-2**, soils within the MAGSA were grouped and mapped based on soil texture (coarseness) and relative saturated hydraulic conductivity (Ksat). Other features that could positively effect or negatively impact groundwater recharge were then added to the maps. These include:

- Areas of shallow regional aquitards (A-Clay and C-Clay) which could impede percolation of groundwater (**Figure** 2-1 and **Figure** 2-2).
- Extent of the regional E clay (Corcoran clay) aquitard, as generally, recovery of banked groundwater would primarily occur from the portion of the aquifer above it and if the project is in an area underlain by the E clay, recharged water will pre-dominantly reside above the E clay.
- Geologic facies, as mapped by the USGS (Page and LeBlanc 1969), which are relatively conducive to groundwater recharge (*Figure 2-1*).
  - Facies D: 50-66% coarse grained material
  - Facies E: 66-80% coarse grained material
- Geologic deposit types, mapped by Page and LeBlanc in 1969, which provide general indication of relative favorability of surface water percolation to groundwater (*Figure 2-2*).
  - Sand Dune Deposits (relatively favorable for recharge)
  - Younger Alluvium (relatively favorable for recharge)
  - Older Alluvium (relatively favorable for recharge)
  - Flood Basin Deposits (relatively unfavorable for recharge)
- Groundwater surface elevation contours to site possible locations with sufficient storage space, determine directions of groundwater flow as they relate to areas of poor groundwater quality and the likely direction recharged water will flow (Figure 2-1 and Figure 2-2).



4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\McMGSA\_Soils\_GeoFacies.mxd



4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\McMGSA\_Soils\_SurfFeatures.mxd

### **Geologic Findings**

As shown on **Figure 2-1** and **Figure 2-2**, coarse- to moderately coarse-grained soils are predominately located along the northern edge, the western boundary, the eastern edge (from approximately Whitesbridge Avenue to American Avenue) and the south-eastern portion of the MAGSA. The vast majority of the GSA interior is covered by moderately fine (clay loam) type soils.

Large areas of the northwestern, central-west and southwestern MAGSA are underlain by relatively shallow regional aquitards (A-Clay and C-Clay) that are considered limiting factors in groundwater recharge. The vast majority of the MAGSA is underlain by the E-Clay aquitard, however the E-Clay is at such depths that it is not considered a limiting factor to groundwater recharge of the groundwater table.

Geologic deposits (**Figure 2-2**), as mapped by Page and LeBlanc (1969), indicate that the southern third of the MAGSA is comprised of unconsolidated sand dune deposits. Previous experience has shown that the sand dune deposits are generally favorable for recharge. The bulk of the remaining MAGSA area is comprised of unconsolidated younger and older alluvium deposits. Unconsolidated flood basin deposits, which are generally considered unfavorable for groundwater recharge occur along the western margin of the MAGSA.

Page and LeBlanc (1969) mapped the Geologic Facies in the greater Kings Subbasin. These geologic facies were grouped based on the percentage of coarse-grained materials into Facies A through E. Facies D and E are generally considered favorable for groundwater recharge while Facies A through C are generally considered non-favorable for groundwater recharge as they have higher percentages of fine-grained materials. As shown in **Figure 2-1**, Geologic Facies D and E are generally located in the northern and southern ends of the MAGSA. Small areas of Facies D and E are also located along the eastern edge of the GSA.

Groundwater elevation contours showing groundwater flow directions are presented on **Figure 2-1** and **Figure 2-2**. As shown, groundwater typically flows into the GSA from the east in a south-west direction. A large cone of depression can be seen in the southwest portion of the MAGSA as a result of regional groundwater pumping. Groundwater, above the E clay, generally flows towards this depression from surrounding areas.


### Initially Selected Regions of MAGSA Geologically Suitable for Groundwater Recharge

By layering the soils, geologic, and groundwater quality data presented in **Figure 2-1**, **Figure 2-2**, and **Figure 3-8**, several regions within the MAGSA were identified where relative groundwater percolation rates could be higher, where limiting factors such as shallow regional aquitards are not present, and where existing TDS in groundwater appears to be relatively lower. The area near the San Joaquin River along the eastern most boundary of MAGSA also appears to be an area where recharge could be viable. This area is not shown on **Figure 2-1** as the A clay has been mapped in this area north of the San Joaquin River, but due the close proximity of the site to one of the potential sources of water for the project and the apparently favorable geologic conditions for recharge (other than the potential presence of the A clay) this area may warrant further study and consideration.


Based on this initial study, the regions that appear favorable for recharge are generally located along the eastern boundary of the GSA and in the southeastern portion of the GSA. For discussion purposes, these identified regions have been labeled from north to south as Site 1, Site 2, Site 3, Site 4, and Site 5 (Figure 2-3). Initial geologic findings were reviewed by Kenneth D. Schmidt and Associates (KDSA) and the findings are discussed in a memo dated August 14, 2020 (Appendix A). The memo summarizes the number of well logs available for evaluation by site and indicates areas with apparently favorable conditions for recharge for each of the five sites. The memo recommended twenty-eight borings be completed on the five sites. Two soil borings per site were included as part of this scope of work with the understanding more soil borings will be needed as recharge basin locations are identified. As shown in Table 2-2, ten borings were completed on the five sites. Additional borings will be needed during the next steps in project development. Included in the memo are map figures that show the areas of apparently favorable recharge. The memo notes that Site 2 does

not have any well logs that indicate apparently favorable conditions for basin recharge, and soil borings were not recommended at this site. Two soil borings were conducted at Site 2 to collect location specific data on the soil conditions at the site.

The groundwater flow within MAGSA is generally from northeast to southwest towards the cone of depression. The cone of depression is in the southwest portion of MAGSA. **Figure 2-4** shows the unconfined groundwater contours. The contours show the groundwater flows towards the cone of depression. This shows that recharged groundwater will not generally flow outside of the MAGSA boundaries. Groundwater may flow outside of the GSA if the cone of depression moves. This is advantageous for the banking program since it is expected banked water will not migrate out of the region.



3/16/2021 : \\ppeng.com\pzdata\clients\McMullin GSA-2659\2659 On-going\GIS\Map\McMGSA\_Soils\_GeoFacies.mxd



## 2.2 Soil Borings

Based on the findings discussed above (Section 2.1), soil borings were drilled in the five regions that were identified as appearing favorable for groundwater recharge (Site 1 through Site 5). The purpose of the soil borings was to collect initial location specific soils information to begin near surface characterization of geologic conditions within the five regions. The collected information will be beneficial in helping the GSA narrow down the list of potential groundwater recharge locations to better focus future efforts, studies, and design of a groundwater banking program.

### 2.2.1 Site Locations

Soil borings were advanced to approximately 90 to 100 feet below ground in the areas shown on **Figure 2-5**. Soil Borings 1-1 and 1-2 were advanced within Site 1, Borings 2-1 and 2-2 within Site 2, Borings 3-1 and 3-2 within Site 3, Borings 4-1 and 4-2 within Site 4, and Borings 5-1 and 5-2 within Site 5. An additional two soil borings, A-1 and A-2 were drilled near either side of the mapped A-clay boundary to assess the possibility of basin construction within the northern-central MAGSA area.

### 2.2.2 Soil Boring Data

Drilling was performed by a CME-55 drill rig using hollow stem augers and a Continuous Tube Sampler. Continuous-core soil samples were reviewed by a California licensed Professional Geologist during drilling and the results were logged consistent with the Unified Soil Classification System (USCS). Soil boring logs for each soil boring drilled during this assessment are in Appendix B, Part 1. Additionally, KDSA selected 12 soil samples to send to the laboratory for grain-size distribution by ASTM C136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates (Table 2-1, on following page). The samples were sent to the laboratory to provide additional soil texture data and confirm field estimated texture, especially when a material was logged with an intermediate texture, which most of the submitted samples were. Intermediate textured soils on the boring logs have a dual symbol in the USCS Field Classification column. Of note on the boring logs, is that the vast majority of fine-grained materials and the fine-grained fraction of coarse-grained materials were logged mostly as silt and not clay in the field. Hydrometers, generally used to differentiate between the percentages of clay and silt, were not run on the samples submitted to the laboratory. Therefore, because the majority of fine-grained deposits were logged as silt in field, the fine fraction, i.e., finer than the #200 sieve, from the sieve analysis samples is assumed to be silt. Of the 12 samples submitted, 11 of the laboratory results confirmed the field estimated soil texture. The laboratory results are included in Appendix **B**, **Part 2**, and the data can also be found on the soil boring logs (Appendix B, Part 1). The soil classification, as estimated in the field, was not changed on the boring logs based on the laboratory data.


Boring Number	Sample			
Number				
Number	Depth			
1-1	50'			
2-2	10'			
2-2	25'/30'			
2-2	45'			
3-1	45'			
3-2	45'			
4-1	30'/35'			
4-1	55'			
4-2	15'			
4-2	40'/45'			
5-1	5'			
5-2	60'/65'			
	2-2 2-2 3-1 3-2 4-1 4-1 4-2 4-2 4-2 5-1			

### Table 2-1 Soil Samples Submitted for Sieve Analysis

### 2.2.2.1 Soil Boring Log Analysis – Percentage of Permeable Materials

For the purposes of this assessment, materials logged as poorly graded sands (SP) or silty sands (SM) with grain sizes described as fine to coarse-grained were considered relatively permeable. While materials described as silts (ML) or clays (CL) or generally as very fine-grained were considered relatively less permeable. Based on visual classification of the encountered soils, the percentage of relatively permeable materials in the upper 10-feet, 20-feet, 50-feet, and 100-feet were summarized. For each of these depth intervals the soil borings were sub-ranked in numerical order based on the percentage of permeable materials (SP and SM) with a lower sub-ranking number indicating a higher percentage of materials considered relatively permeable. The depth interval rankings were then summed for an overall ranking of each soil boring. Results of the soil boring ranking are summarized in **Table 2-2**.

As shown in **Table 2-2**, the soils borings with the highest overall percentage of more permeable materials were located in Site 1 (Borings 1-1 and 1-2), Site 2 (Boring 2-1), and Site 3 (Borings 3-1 and 3-2). Soil borings with the lowest percentage of permeable materials were located in the area of the A-Clay assessment (Borings A-1 and A-2) and at Site 4 (Borings 4-1 and 4-2) and Site 5 (Borings 5-1 and 5-2). For the purposes of this assessment, it is assumed that boring locations with the highest overall percentage of permeable materials would be relatively more efficient in groundwater recharge.



3/16/2021 : \\ppeng.com\pzdata\clients\McMullin GSA-2659\2659 On-going\GIS\Map\McMGSA\_BoringLocations\_Soils\_SurfFeatures.mxd

### Table 2-2 Soil Boring Ranking Based on Field Estimated Percentages of Permeable Material

Poring 1 1					Total Cooro	Total Banking
Boring 1-1	1.1	11		1.1	Total Score	Total Ranking
Soil Type	1		Upper 50'			
SP & SM Combined	95%	83%	77%	64%		
Ranking Points (%SP/SM)	2	2	2	3	9	1
Boring 1-2					Total Score	Total Ranking
Soil Type	1	Upper 20'	Upper 50'			
SP & SM Combined	80%	75%	78%	75%		
Ranking Points (%SP/SM)	3	4	1	1	9	1
Boring 2-1		1	1	1	Total Score	Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	100%	88%	68%	61%		
Ranking Points (%SP/SM)	1	1	5	5	12	2
Boring 2-2	-			-	Total Score	<b>Total Ranking</b>
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	0%	35%	29%	40%		
Ranking Points (%SP/SM)	7	10	12	9	38	10
					1	
Boring 3-1				·	Total Score	Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	20%	60%	76%	74%		
Ranking Points (%SP/SM)	5	6	3	2	16	4
Boring 3-2					Total Score	Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	100%	68%	75%	62%		
Ranking Points (%SP/SM)	1	5	4	4	14	3
Boring 4-1	4	3	3	4	Total Score	Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	95%	78%	54%	60%		
Ranking Points (%SP/SM)	2	3	8	6	19	5
Boring 4-2	•			-	Total Score	Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	0%	0%	30%	31%		
Ranking Points (%SP/SM)	7	10	11	10	38	10
				-		
Boring 5-1			d		Total Score	Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	10%	56%	67%	49%		
Ranking Points (%SP/SM)	6	7	6	8	27	6
Boring 5-2						Total Ranking
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'		
SP & SM Combined	0%	45%	61%	58%		
Ranking Points (%SP/SM)	7	9	7	7	30	7
	,	5	,	,		,
		l	l.	L.	Total Score	Total Ranking
$ \mathbf{KOring}  \Delta_{-1}$				400	Total Score	
Boring A-1	Unner 10'	Unner 20'	Unner 50'	Unner 100		
Soil Type	Upper 10' 80%	Upper 20'	Upper 50' 47%	Upper 100' 25%		
Soil Type SP & SM Combined	80%	55%	47%	25%		
Soil Type SP & SM Combined Ranking Points (%SP/SM)					  32	
Soil Type SP & SM Combined Ranking Points (%SP/SM) Notes from log:	80%	55%	47%	25%	32	 8
Soil Type SP & SM Combined Ranking Points (%SP/SM) Notes from log: <b>Boring A-2</b>	80% 3	55% 8	47% 9	25% 12		
Soil Type SP & SM Combined Ranking Points (%SP/SM) Notes from log: <b>Boring A-2</b> Soil Type	80% 3 Upper 10'	55% 8 Upper 20'	47% 9 Upper 50'	25% 12 Upper 100'	32 Total Score 	 8 Total Ranking 
Soil Type SP & SM Combined Ranking Points (%SP/SM) Notes from log: <b>Boring A-2</b>	80% 3	55% 8	47% 9	25% 12	32	 8

### 2.2.2.2 Soil Boring Log Analysis – Potential Impediments to Recharge

In addition to the overall percentages of permeable materials in the soil borings, the presence of soil beds that could restrict the vertical movement of recharge water should also be discussed in siting locations for recharge basins.

Hard drilling conditions were encountered in several of the soil borings at depths ranging from approximately 30 feet to 70 feet below ground. These hard drilling conditions often corresponded to partially cemented silt layers in the soil column, of which several had the appearance of hardpan, but at deeper depths than hardpan is typically encountered. These soils were encountered in Boring 2-2 (48'-50'), Boring 3-1 (47'-48'), Boring 3-2 (43'-45'), and Boring 4-1 (67'-68').

These partially cemented silt layers could be interpreted as being related to hardpan and non-hardpan paleosols as described by Cehrs, Soenke, and Bianchi (1980) in USDA Technical Bulletin 1604, including those identified as components of the Riverbank Formation. While these were previously described by Cehrs, Soenke, and Bianchi at relatively shallower depths in the greater Fresno area, given the valley structure, southwestward dipping alluvial deposits and depositional environment in the valley, finding these paleosol-like features at depths deeper than in their study area is reasonable.

These partially cemented silt layers were typically noted as having blocky structure which would appear to be secondary porosity for the material as no appreciable perched water was encountered above. Based only on soil texture, it would be reasonable to assume that these layers would be impediments to groundwater percolation, however the secondary porosity (blocky structure) indicates these layers may not necessarily be an issue in severely limiting groundwater percolation.

Perched groundwater indicating soil layers restrictive of groundwater percolation was not encountered in the soil borings except for Boring 4-1 at approximately 85 feet in poorly graded sand. However due to extremely soft drilling conditions and heaving sands, this soil boring could not be sampled below 95' and the assumed restrictive layer was not reached in the boring. Current water levels in this vicinity are between approximately 165 to 200 feet deep, therefore the perched groundwater encountered in Boring 4-1 does not appear to be related to the regional groundwater table.

Pilot scale percolation tests are the best way to quantify recharge rates and should be performed, if possible, on any parcel before proceeding with project development. Pilot scale percolation tests on one or more parcels would involve temporary basins of about one acre and the installation of piezometers at varying depths corresponding with the depths of possible percolation barriers, such as those discussed above, to assess impediments to groundwater percolation.

Several of the borings have shallow fine-grained material overlying sequences of sands and silty sands, e.g., Boring 3-1. If these shallow fine-grained materials can be removed during basin construction thereby exposing more coarse-grained materials, these locations would most likely have relatively higher recharge rates. As only two locations were assessed at each Site, the location, presence, prevalence, and thickness of the shallower fine-grained materials cannot be confirmed across the Sites until more borings or backhoe pits can be completed. These additional data would be used to refine the nature and extent of surface or near surface fine-grained materials to ascertain if the shallow fine-grained materials are pervasive across the Site. This information would be used to provide recommendations on how deep a given basin will need to be excavated to expose underlying coarse-grained materials.

### 2.2.3 Summary of Geologic Findings

As discussed above and shown in **Table 2-2**, Site 1 has the highest percentage of coarse-grained materials logged in the borings. Followed in descending order with regards to percent coarse grained material by Site 2, Site 3, Site 4 and Site 5. Based on the regional geologic data for geologic facies, SAGBI rating, relative saturated hydraulic conductivity, and geologic deposits, the Site 1 area was not expected to have as permeable materials as Site 5 which is in an area of sand dune deposits with predominately sand and sandy loam topsoils.

KDSA did not recommend additional borings in Site 2 based on their well log review (**Appendix A**). The relatively high ranking of Boring 2-1, ranked second of the ten borings, illustrates that site specific data is needed to confirm the preliminary findings from the regional data. However, Boring 2-2 on Site 2 does appear to confirm KDSA's finding that the southwestern portion of the site does not appear to be favorable for recharge. Based on geologic facies, Site 3 appeared to have a relatively higher percentage of coarse-grained materials with both Facies D and E mapped there. Significant portions of Site 5 are mapped by Page and Leblanc as Facies D however, the two borings conducted there do not appear to be in areas mapped as Facies D. Future borings in the Site 5 area should be advanced in locations mapped as Facies D to evaluate and compare material textures between areas not mapped as Facies D and areas mapped as Facies D. In addition, the 2 borings completed in Site 5 were about 5 miles apart and assessing this large of an area would require addition borings. It is possible, and maybe even likely, that there are areas in Site 5 with soil texture comparable to Site 1, and Boring 2-1.

Based on soil texture data logged in the field, the area around Borings 1-1, 1-2 and 2-1 appears to be relatively better for recharge, however the selection of a site should also consider groundwater quality as, discussed below in **Section 3.2** and available groundwater storage space above local groundwater levels. Considering the variations in soil texture between borings and between sites, additional soil borings should be conducted at sites selected for additional consideration. Furthermore, the information from the borings indicates that if additional lands are identified in the areas near Sites 1 - 5, site specific borings are warranted even if the regional literature may indicate less than favorable conditions for recharge in the area.

## 3 Operations Evaluation

## 3.1 Operations

### Surface Water Deliveries

The proposed Aquaterra Groundwater Bank would be developed to receive surface water from, and deliver water to, the Fresno Slough and the hydraulically connected Mendota Pool in Fresno County. The Aquaterra Groundwater Bank would develop access to water supplies from the Kings River, the San Joaquin River, the CVP DMC, and the SWP (through use of available capacity in the DMC). While the Kings and San Joaquin Rivers are potential surface water sources, this study focuses on water that would be developed with potential partner agencies on the CVP and SWP systems.

<u>Kings River</u> – During years when flood water is released from Pine Flat Dam, the Kings River flows into James Bypass, which terminates in the Mendota Pool. As described in the MAGSA Groundwater Sustainability Plan (GSP), there are occasionally periods when water supplies have historically exceeded local diversion capacity on the Kings River. These supplies occur infrequently under very high flow conditions and may continue to occur at times in the future. The Aquaterra Groundwater Bank diversion and conveyance facilities would be designed to access any available Kings River flows directly from the Mendota Pool, in addition to an existing diversion to MAGSA upstream on James Bypass. The potential quantities available are not identified in this report.

<u>San Joaquin River</u> – The San Joaquin River also flows into the Mendota Pool. During periods of good water supply conditions on the San Joaquin River, there are occasional periods of water supply availability on the San Joaquin River. Recharge of available San Joaquin River flows was described in the MAGSA GSP as a potential project to achieve sustainability. As noted in the GSP, water rights permits would be needed for recharge of available San Joaquin River flows. As with the Kings River, flows available for recharge from the San Joaquin River are not quantified in this report.

<u>Delta-Mendota Canal</u> – The Delta-Mendota Canal would be a direct or indirect water supply source for the Aquaterra Water Bank. The DMC extends in a southerly direction from a location on the Sacramento-San Joaquin Delta near Tracy, ultimately discharging into the Mendota Pool behind the Mendota Dam. The DMC was built to provide water supplies to various CVP water supply contractors, including water rights settlement contractors (San Joaquin River Exchange Contractors). The DMC has a capacity ranging from 4,600 cfs at its head near Tracy to 2,900 cfs at its terminus near Mendota. Over time, groundwater pumping has caused subsidence in portions of the lower DMC downstream of San Luis Reservoir, which has reduced the operational capacity somewhat just west of Mendota Pool.

The DMC is indirectly connected to San Luis Reservoir and the SWP California Aqueduct just west of Los Banos at the O'Neill Forebay. With this connection, the upper reach of the DMC can deliver water to San Luis Reservoir; typically, this occurs in wet years. The O'Neill facilities also provide a connection to the SWP California Aqueduct and SWP contractors.

Recharge to Aquaterra, from either CVP or SWP contractor participants, can be delivered to Mendota Pool through unused DMC capacity during wet periods. **Figure 3-1** shows the location of the DMC and how SWP and CVP contractor supplies can be delivered.

Extractions from the Aquaterra Groundwater Bank, for either CVP or SWP contractor participants, can also be returned to those CVP or SWP contractors by exchange using the DMC. During extraction periods, Aquaterra Groundwater Bank extractions would be provided to CVP and San Joaquin River Exchange Contractors that receive water either directly from the Mendota Pool or through direct connections to their distribution facilities. Extractions that provide for these contractors' use would make equivalent volumes of

CVP water available at upstream locations on the DMC and would allow for water to be returned to San Luis Reservoir or the SWP California Aqueduct. **Figure 3-2** shows how the DMC would be used during extraction periods to provide water at San Luis Reservoir and on the California Aqueduct.

To quantify the potential DMC delivery capability for recharge to and extraction from the Aquaterra Groundwater Bank, two data sources were analyzed: 1) CALSIM model simulation of projected DMC deliveries to Mendota Pool (1922 through 2003) prepared for the State Water Project Delivery Capability Report (2019) and 2) historical records of actual Mendota Pool diversions for the period 1980 through 2018. The CALSIM 1922-2003 study results for DMC deliveries to Mendota Pool are summarized by year type in **Table 3-1**.


		CALSIM	State \	Water P	roject 20	019 Deli	very Cap	ability	Report S	Study		
					al Inflow					-		
						et per se				•		
	October No	ovemberDe	ecember	January	February	March	April	May	June	July	August	September
Aquaterra F	Recharge Yea	ars										
Wet Yea	r Type											
Average	1,163	494	183	139	261	644	734	895	1,379	1,958	2,408	1,665
Minimum	0	0	0	0	0	0	0	0	0	0	1,384	892
Maximum	1,265	545	260	263	595	1,118	1,259	1,711	2,370	2,550	2,457	1,699
Above N	lormal Year	Туре										
Average	1,208	520	226	206	429	856	963	1,387	2,047	2,379	2,434	1,688
Minimum	959	415	0	0	0	0	0	0	147	1,242	2,407	1,676
Maximum	1,265	545	260	263	595	1,113	1,248	1,703	2,359	2,541	2,457	1,699
Aquaterra N	Ion-Operatio	on Years										
Below N	Iormal Year	Туре										
Average	1,236	496	248	195	431	1,000	1,067	1,504	2,241	2,500	2,412	1,678
Minimum	968	41	191	0	0	0	0	0	1,116	2,462	2,377	1,663
Maximum	1,265	545	260	263	595	1,109	1,245	1,695	2,348	2,524	2,434	1,688
Aquaterra E	xtraction Ye	ears										
Dry Yea	r Type											
Average	1,222	526	248	249	550	1,081	1,203	1,647	2,281	2,449	2,363	1,648
Minimum	963	417	201	204	420	871	980	1,328	1,846	1,987	1,908	1,308
Maximum	1,265	545	260	263	595	1,102	1,238	1,689	2,339	2,513	2,424	1,684
Critical	Year Type											
Average	1,180	508	241	242	526	937	1,051	1,423	1,975	2,122	2,042	1,416
Minimum	965	418	202	205	433	854	959	1,298	1,804	1,938	1,863	1,288
Maximum	1,262	543	258	261	584	1,092	1,221	1,651	2,287	2,452	2,368	1,659

#### Table 3-1 CALSIM SWP DCR Study


The historical Mendota Pool diversion data is summarized in **Appendix C**. The Mendota Pool diversions represent the total diversion amount from the Mendota Pool, regardless of water supply source. These diversions are primarily provided with water from the DMC, but also use San Joaquin River flows during wet periods or during extreme dry periods. For purposes of recharge to or extraction from the Aquaterra Groundwater Bank, actual DMC deliveries to the Mendota Pool would have been the ideal data source. During wet periods, the Mendota Pool diversions would often exceed DMC deliveries to the Mendota Pool. For purposes of determining available capacity, this would actually provide a conservative estimate of DMC available capacity. During most normal or dry years, there are typically no other significant sources of supply to Mendota Pool, making the Mendota Pool diversions a reasonable approximation of DMC deliveries.

The estimates of potential unused DMC capacity for Aquaterra Groundwater Bank recharge have been made based on a conservative analysis of historical use of the lower DMC. As other programs are developed for water management programs involving the lower DMC, these programs could theoretically impact available capacity for recharge to Aquaterra. As described below, very conservative assumptions were made for the level of use of the lower DMC that would ensure that additional capacity is available for Aquaterra recharge operations. Since the Aquaterra recharge operations were evaluated based on restrictive estimates of lower DMC available capacity, these estimates allow for potential additional use by other agencies for new or developing water management programs such as recharge to other areas adjacent to the Mendota Pool (such as areas in the Delta-Mendota or Madera Subbasins). The only known water management program involving the DMC is the North Valley Regional Recycling Program (NVRRP), which uses capacity in the upper portion of the DMC located upstream of San Luis Reservoir. This program is relatively small in scale and would not be expected to restrict Aquaterra recharge operations since the Aquaterra Groundwater Bank has been developed based on availability of allocated SWP or CVP water supplies, which would not be constrained by the NVRRP.

While the conservative assumptions for recharge conveyance availability are used for purposes of facility design and operations planning, available conveyance capacity would frequently be available in most non-peak irrigation months (June through August). In actual operation, Aquaterra recharge operations would normally be possible much more frequently than in the restrictive six-month period described below.



4/30/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\McMGSA\_GWBanking\_RechargeDeliveries.mxd



4/30/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\McMGSA\_GWBanking\_ExtractionDeliveries.mxd

Mendota Pool diversions over the 1980-2018 period are summarized in **Figure 3-3**. This figure shows the maximum, minimum, and average monthly diversions for the 1980-2018 period. As represented in the figure, the peak monthly diversion over this period was 179,449 AF in July 2006, which is equivalent to a flow rate of 2,918 cfs. As noted earlier, there has been some subsidence in the lower DMC in recent years, with some reduction in capacity expected. As a more conservative assumption of available capacity in recent years, diversions during the month of August 2018 were used, during a period with sole reliance on DMC deliveries to Mendota Pool diversions. The diversions during July 2018 totaled 140,741 AF, which is equivalent to a flow rate of 2,289 cfs. Using this flow rate, the minimum available capacity available for DMC additional deliveries to Aquaterra Groundwater Bank was computed as the difference between 2,289 cfs and the maximum historical monthly deliveries. This is considered to be a conservative estimate of DMC capacity available for conveyance of recharge supplies to Aquaterra Groundwater Bank. As described below, a refined estimate was developed using a 90-percentile estimate of maximum baseline DMC delivery use. It may be appropriate to refine the estimate of actual and estimated DMC capacity into the Mendota Pool based on current operational experience and potential future subsidence through discussions with the San Luis & Delta-Mendota Water Authority, which operates the DMC.




Figure 3-3 Mendota Pool Diversions/Delta-Mendota Canal Capacity

As shown in **Figure 3-3**, there is capacity available in the DMC for recharge for more than 40,000 AF per month for six months of the year based on the maximum historical use of the DMC. This is likely an overly conservative estimate of available capacity due to extreme anomalies that occasionally occurred in various months in the historical record.

**Figure 3-4** shows a somewhat less extreme, but still very conservative approach to capacity which will be used for project definition. **Figure 3-4** shows the 10-percentile wettest monthly diversions (rather than absolute maximum values) and the 90-percentile driest monthly diversions (rather than the absolute minimum values.) The remaining DMC capacity at the 10-percentile wettest monthly conditions is also shown, as compared to the assumed DMC capacity (actual July 2018 diversions). Based on the 10-percentile wet conditions, this figure shows that there is a minimum of 40,000 acre-feet of recharge conveyance capacity available for seven months (October through April). This figure also shows no recharge conveyance capacity available for the three summer peak irrigation months of June through August. There are moderate, but limited, amounts of recharge conveyance capacity available in May and September.

The CALSIM projections of DMC deliveries to Mendota Pool for 1922 through 2003 corroborate the estimates of available conveyance identified above based on Mendota Pool Deliveries. The DMC deliveries shown in Table 3-1 are no higher than 1,265 cfs for the period October through April, which results in available lower DMC recharge conveyance capability of no less than 1,000 cfs for the proposed recharge period (2,289 cfs less 1,265 cfs), which is well above the 40,000 acre-feet available recharge conveyance capacity identified based on the Mendota Pool diversion data.

In addition to identifying capacity available for recharge through the lower DMC, the analysis above also indicates periods when recharge capacity would be available for local water users for surplus flows on the San Joaquin and Kings River. This analysis indicates that the months of June through August would be a period when allocated imported water would generally not be conveyed through the lower DMC. Because of the limited available lower DMC capacity during the June through August period, Aquaterra recharge capacity during those periods would be available for local San Joaquin River and Kings River flows.




Figure 3-4 Mendota Pool Diversions/Delta-Mendota Canal Capacity- Historical Period

During extraction operations, Aquaterra pumping would return groundwater to the Mendota Pool where it would need to be exchanged for lower DMC deliveries, which would return water to O'Neill Reservoir and the California Aqueduct. The limiting factors for these extraction exchanges is the amount of DMC deliveries to the Mendota Pool. While Aquaterra recharge would rely on unused DMC capacity (primarily in nonirrigation months), exchanges of extracted Aquaterra groundwater would rely on deliveries of CVP water through the lower DMC to Mendota Pool waters users. The potential extraction conveyance capacity is interpreted from this figure as the 90-percentile driest delivery amounts. This would represent the amounts of DMC water delivered to the Mendota Pool during the 90-percentile conditions and would be an upper limit to the amount of potential Aquaterra Groundwater Bank extractions that could be delivered by exchange back to San Luis Reservoir or the California Aqueduct. This figure indicates that monthly extractions of up to 40,000 acre-feet per month (approximately 667 cfs) could potentially be pumped into Mendota Pool for five months (May through September). The ability to exchange for Aquaterra extractions is supported by the CALSIM projections in Table 3-1, which indicate that projected DMC deliveries to the Mendota Pool during Aquaterra extraction years (normally Dry and Critical Years) fall no lower than 1,298 cfs during the proposed five-month extraction period (May through September.) Extractions during other months would be more limited. In practice, there are potential water quality blending restrictions that might also limit the potential conveyance (by exchange) of extractions in dry years, which are discussed later.

While the CALSIM projections and Mendota Pool diversion data indicate that there would be adequate DMC deliveries to the Mendota Pool to support exchanges of Aquaterra extractions, estimates of the extreme dry conditions for recent actual years indicate that there could be some additional constraints that may affect potential exchanges. As shown in **Table 3-2**, computed DMC deliveries to Mendota Pool during 2014, 2015 and 2021 were lower than projected by CALSIM or experienced in prior dry years. The outlined periods indicate when Aquaterra Groundwater Bank extractions would have been likely. Based on this review of recent operations, there would have been five months during 2014 and 2015 when actual DMC deliveries to the Mendota Pool dropped below the 40,000 acre-feet per month target extraction exchange capacity. Based on the recent 2014-2015 period, it appears that the Aquaterra extraction period might need to be extended to earlier or later in the season, when DMC water is being delivered that could be exchanged. Additionally, extraction exchanges of a high proportion of the DMC flows could be a concern for Mendota Pool divertors which could have water quality concerns that need to be addressed. Finally, potential options for physical return of some portion of Aquaterra extractions could be explored by MAGSA together with project participants to provide a higher level of assurance that dry year extractions can be exchanged back to the California Aqueduct.

#### Table 3-2 Computed DMC Inflows to Mendota Pool

### Computed DMC Inflow to Mendota Pool

Delta Mendota Canal

(acre-feet)													
Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
2014	6,040	24,125	12,128	25,944	46,814	33,840	51,813	38,724	19,661	68,907	50,310	242,157	620,463
2015	6,770	40,000	26,839	19,570	38,859	88,256	75,053	17,564	41,888	55,246	32,226	23,077	465,348
2016	4,498	35,321	33,958	37,845	74,954	126,365	121,375	89 <i>,</i> 828	80,817	67,469	29,340	1,348	703,118
2017	3,608	6,547	3,347	3,249	10,004	12,955	84,220	131,976	97,312	84,370	45,522	34,076	517,186
2018	22,732	72,466	19,034	26,199	56,767	110,966	145,932	117,790	85,262	76,092	48,746	13,355	795,341
2019	13,783	23,019	23,670	57,844	44,843	29,783	124,202	139,040	28,506	80,333	59,135	20,201	644,359
2020	23,330	68,396	32,218	33,355	70,146	114,868	127,916	111,602	85,348	80,631	44,888	20,996	813,694
2021	8,507	24,315	26,552	36,089	67,109	87,912	104,328	75,399	47,428	0	0	0	477,639

Potential Aquaterra Extraction Period

Potential Aquaterra Extraction Period with low DMC inflows

The potential recharge and extraction conveyance capacities identified above were used as the basis for developing the Aquaterra Groundwater Bank operations. The capacities described above were used as constraints on potential conveyance in evaluating project operations.

### **Banking Operations and Project Yield**

As described previously, the Aquaterra Groundwater Bank could be available for use by a wide variety of potential water agencies, subject to provisions that are defined in banking program framework agreements. In the analysis presented here, potential needs for possible SWP contractor participants have been used as the basis for identifying program design capacities. The use of SWP contractors as target Water Bank participants is for purposes of defining potential project facility capacities and does not preclude other water agency groups from participants are expected to have major water supply sources from Central Valley Watersheds (e.g., SWP, Central Valley Project Export Contractors, San Joaquin Valley Water Users), their general water supply needs are expected to be similar to the needs of SWP contractors. In great part, they have the same patterns of dry water supply periods and wet water supply periods, although the specific quantities are likely to differ. The project operations described here are a first level analysis and will be refined in the future as specific water users are identified for potential project participants is presented in **Appendix D**.

**Table 3-3** shows assumed water bank operations for Aquaterra Groundwater Bank participants for purposes of facility design and cost estimation. This shows total project storage of 800,000 acre-feet, with recharge rates of 770 cfs (about 45,800 acre-feet per month) and extraction rates of 480 cfs (about 28,600 acre-feet per month).

	Design Characteristics
Recharge	
Capacity (cfs)	770
Monthly Recharge (TAF)	45.8
Extraction	
Capacity (cfs)**	480
Monthly Extraction (TAF)	28.6
Maximum Storage (TAF)	800

#### Table 3-3 Aquaterra Groundwater Bank Program Characteristics

\*Only water that has been recharged may be extracted.

As described in the later discussion of facility configuration, one or more new conveyance facilities would be built from Mendota Pool to identified recharge basin locations, which would have a total capacity of 770 cfs. Recharge basins would be identified based on the 770 cfs design recharge rate. Groundwater pumps would be located, and their costs estimated for 480 cfs. The recharge conveyance facilities would be used to return extractions back to the Fresno Slough arm of Mendota Pool for exchange with DMC flows. Assumed annual recharge operations for the Aquaterra Groundwater Bank are shown in **Figure 3-5**. This figure, based on typical Delta export water supply availability, shows that two different periods of recharge are possible in years when water is available: February-March for Temporary Water (SWP Article 21 Water, CVP Section 215 Water and Carryover Water from both SWP and CVP) and October-December for allocated SWP and CVP water that exceeds annual demands needs for participants. These two periods were selected as a very conservative potential operation based on a very wet flow scenario on the DMC. In actual operation, it would frequently be possible to recharge for extended periods based on actual unused capacity in the lower DMC.




Figure 3-5 Lower Delta-Mendota Canal with Aquaterra Groundwater Bank Typical Recharge Year Put Pattern

Extraction operations for the Aquaterra Groundwater Bank for a typical drought year are shown in **Figure 3-6** for project participants. This shows pumping of 28,600 acre-feet per month for the period May through September, with total pumping for the year of 146,000 acre-feet. **Figure 3-6** compares the amount of extractions to lower DMC deliveries in dry years (using 90<sup>th</sup> percentile as criteria for dry conditions), which would be the maximum amounts that could physically be extracted while providing the ability to exchange with DMC flows upstream at O'Neill Forebay. As with recharge, this is a generally conservative proposed operation and, in actual operation, extractions could frequently be started earlier in the year than April and extended later in the year past September to provide increased extractions. If greater annual extractions were required, additional pumping capacity could also be added during the peak DMC flow months of June through August. As noted in the discussion of water quality below, there may be additional restrictions due to salinity based on sensitivity to water quality of existing Mendota Pool water users.




Figure 3-6 Lower Delta-Mendota Canal with Aquaterra Groundwater Bank Typical Extraction Year Take Pattern

The typical recharge and extraction operations presented in this chapter are for the purposes of identifying design capacities for facilities. Depending on the operational needs of individual water bank participants, other project recharge or extraction capacities could be more optimal than the design capacities identified here, and the project could be modified as appropriate. In general, the design assumptions made here are expected to be very conservative estimates of the capacity needed, and any refinement of those capacities is expected to result in reduced construction costs, for example from a smaller acreage of recharge basins.

## 3.2 Water Quality

Planning for the Aquaterra Groundwater Bank requires consideration of groundwater quality for both recharge and extraction operations.

## 3.2.1 Exchange and/or Recharge Surface Water Quality

For recharge operations, water quality information was retrieved from the California Data Exchange Center for Station DM3, located at Check 21 on the Delta-Mendota Canal. This location is near the Delta-Mendota Canal's discharge to Mendota Pool and is an appropriate representation of the quality of water that would be available for recharge or would be exchanged through extractions. The values were downloaded as daily values and averaged for monthly and annual amounts, with interpolation to fill-in missing data and corrections for occasional anomalous data values.

**Figure 3-7** shows average concentrations of Electrical Conductivity (microsiemens,  $\mu$ -siemens) for each year from 2000 through 2019. This figure also shows approximate TDS (milligrams per liter, mg/L) values, which were estimated using an approximate conversion factor from EC of 0.64. For the 20-year 2000-2019 period, EC at Check 21 averaged 512  $\mu$ -siemens and TDS averaged ~326 mg/L. Average EC during Wet and Above Normal years during proposed recharge periods (February through March and September through December) when recharge would be anticipated was 446 which is roughly equivalent to a TDS of ~285 mg/L. Average EC during proposed extraction periods (May through September) of Dry and Critical years, when extractions would generally occur, was somewhat higher than the average at 574  $\mu$ -siemens which is equivalent to a TDS value of ~368 mg/L.

### Section Three: Operations Evaluation Water Bank Feasibility Study




Figure 3-7 Delta-Mendota Canal Inflow to Mendota Pool Salinity

### 3.2.2 Groundwater Quality

To anticipate water quality from recovery wells for water banking operations, **Figure 3-8** shows TDS measurements from wells within MAGSA. This figure provides a general indication of likely salinity levels. There are limited measurements of TDS available, and these measurements represent a variety of wells – unconfined, confined and composite – that were sampled over a wide range of years. Based on the prior investigations, groundwater quality varies significantly by aquifer zone, geographic location and by time period.

Areas of existing poor groundwater quality that could negatively impact the quality of extracted recharge water were mapped based on available data. As shown in **Figure 3-8**, groundwater quality relative to Total Dissolved Solids (TDS) within the MAGSA was mapped from historically available Groundwater Ambient Monitoring & Assessment Program (GAMA) data and from a 2010 AB303 Study conducted in the areas around the James Irrigation District (JID) well field located within MAGSA.


USGS studies of San Joaquin Valley Groundwater (Page and LeBlanc, 1969) described groundwater water quality based on sampling in the 1950s and 1960s. Their study identified several geochemical types in the MAGSA. The northwestern portion of MAGSA, located outside areas proposed for recharge or extraction, had sodium chloride type water. This water type is typical of portions of the westside of the San Joaquin Valley and adjacent basin areas, which have a high proportion of sediments derived from the Coastal Range. Groundwater quality in this area (in addition to the localized areas affected by the Raisin City Oilfield and the

American Avenue landfill) generally has higher salinity than the rest of MAGSA, with TDS values often exceeding 500 mg/L. The bulk of MAGSA, including areas proposed for recharge and extraction, have groundwater quality types such as sodium bicarbonate, sodium calcium bicarbonate, and calcium sodium bicarbonate that generally are associated with sediments primarily from the Sierra Nevada. Groundwater quality in this recharge and recovery zone of MAGSA has historically had lower TDS values, with widespread occurrence of TDS values of 300 mg/L or less.

**Figure 3-8** includes the American Avenue Landfill and the Raisin City Oil Field where groundwater quality issues are known to exist in MAGSA. The Raisin City Oilfield (located primarily in Township 15S/Range 17E) overlies areas of higher salinity. Historic oilfield extractions and disposal of excess brines on the land appear to have degraded local groundwater quality in the vicinity of the oilfield. As an example, Well T15S/R17E-10R1M, located adjacent to the oilfield, had TDS increase from 336 mg/L in 1953, to 1,310 mg/L in 1959, with a corresponding increase in proportions of sodium and chloride. Measurements of oilfield brine in the Raisin City Oilfield show TDS values of 27,000 mg/L. Discharges of oilfield brine have been regulated in recent decades<sup>1</sup>, but historic areas of high salinity groundwater appear to remain in areas near the Raisin City Oilfield. Proposed water banking recharge and extractions operations are being located upgradient from the oilfield to reduce the potential adverse salinity impacts.

For potential banking operations, additional groundwater quality review was conducted on proposed recharge and recovery areas, identified as areas 1 through 5 in **Figure 3-8**. The more detailed review focuses on the area of MAGSA east of the Raisin City Oilfield and south of Highway 180 (Whitesbridge Road). Additional water quality sampling in this area was conducted for a limited suite of compounds (including TDS, cations and anions) in November and December 2020 (**Figure 3-8**).

<sup>&</sup>lt;sup>1</sup> https://geotracker.waterboards.ca.gov/profile\_report?global\_id=T10000006602



3/16/2021 : \\ppeng.com\pzdata\clients\McMullin GSA-2659\2659 On-going\GIS\Map\Preliminary Sites\McMGSA\_GAMA\_WQ\_v2\_PrelimSites.mxd


**Table 3-4** summarizes TDS and mineral concentrations for sampled groundwater wells in the extraction area. This table includes a variety of groundwater quality measurements including the earlier 1950s and 1960s measurements and more recent groundwater quality sampling from recent decades. These measurements were also evaluated for geochemical characteristics to identify potential causes of groundwater quality trends.

The more recent groundwater quality measurements indicate generally higher salinities in the recharge/ extraction area. Where groundwater salinities in the 1950s and 1960s were typically below 300 mg/L in much of MAGSA, the newer sampling shows higher salinity values, with TDS (salinity) values averaging about 540 mg/L. The new sampling also shows a wide range of variation in salinities, ranging from 111 to 978 mg/L TDS in the potential recharge/recovery area. The sampling revealed large local variations in salinity that did not appear in a systematic pattern and could be related to the source aquifer and well construction. Of the recently sampled wells with construction information, the wells were equally split between unconfined and composite wells. As one example, two wells sampled in Recharge Area 5 had TDS values ranging from 240 at Site 10 to 556 mg/L at Site 11 which are located within a half mile of each other. For these two wells, the 556 mg/L value was in an unconfined well while the 240 mg/L value was in a composite well. There is no obvious reason why the unconfined water quality in that area should be better than confined water quality that would be picked up by the composite well.

The wells tabulated in **Table 3-4** were summarized for geochemical characteristics using a piper diagram (shown as **Figure 3-9**), which shows the relative proportion of major cations and anions. The purpose of this effort was to identify groundwater quality trends and their possible causes. Characteristics were looked at, such as date of the water quality sampling, location, well depth, and total TDS, for possible relationships with salinity.

N	IAGSA W	/ater Bank	Recharge	/Extractior	n Area Rep	resentativ	e Groundwa	ater Chem	ical Analys	es	
											Total
											Dissolved
			Calcium	Magnesium	Sodium	Potassium	BiCarbonate	Sufate	Chloride	Fluoride	Solids
Well Label	Group	Date	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
USGS-363255119550301	GAMA	14-Aug-63	24	1.3	23	3.2	98	11	16	0.1	166
USGS-363317119515001	GAMA	14-Aug-03	110	9.4	94	4.8	248	90	130	0.1	1294
USGS-363342119554301	GAMA	4-Jun-64	35	3.4	27	4.6	-	19	40	0	416
USGS-363353119532001	GAMA	29-Aug-63	47	4.1	35	3.9	120	24	40 50	0.1	277
USGS-363457119521701	GAMA	12-Aug-63	68	8.4	100	5.7	250	59	92	0.1	538
USGS-363500120000001	GAMA	12-Sep-13	84.1	6.19	86.9	13.7	175	58.9	139	0.08	610
USGS-363522119523201	GAMA	8-Jul-87	61	7.3	74	9.5	240	55	62	0.00	471
USGS-363553119550601	GAMA	8-Jul-87	68	14	55	11	222	35	81	0.1	463
USGS-363638120033801	GAMA	17-Dec-65	1400	110	1300	55	120	4.1	4800	0.1	16580
USGS-363700119550001	GAMA	29-Aug-13	1400	33.4	92.4	16.3	496	62.2	96	0.03	621
USGS-363700119550002	GAMA	18-Sep-13	101	14.4	62.8	16.6		42.2	83.3	0.08	478
USGS-363700119590001	GAMA	18-Sep-13	297	88.7	62.8	18.9	381	199	465	0.00	1420
USGS-363711120033801	GAMA	30-Jul-58	15	3	53	6.3	130	4.8	39	0.2	264
USGS-363711120033801	GAMA	13-Jul-59	36	7	65	6.8		4.4	100	0.3	364
USGS-363711120033801	GAMA	19-Jul-60	84	16	83	12	130	2.3	250	0.3	586
USGS-363824120033801	GAMA	19-Jul-60	38	19	38	7.6		27	80	0.2	373
JID/C-58	AB303	28-Jun-10	106	17	96	16	-	74	136	0.2	
JID/C-60	AB303	28-Jun-10	127	31	87	14		89	214	0.2	850
JID/C-71	AB303	30-Jun-10	46	4	111	12	220	57	90	0.1	558
JID/C-72	AB303	30-Jun-10	54	7	101	11	240	51	84	0.1	563
JID/C-80	AB303	30-Jun-10	34	10	42	4		16	27	0.1	342
JID/C-88	AB303	30-Jun-10	40	7	64	5		20	66	0.2	399
JID/D-51	AB303	30-Jun-10	26	2	102	9		28	77	0.2	428
JID/D-57	AB303	28-Jun-10	10	0	196	3	220	11	158	0.5	598
15S17E12J001M	Page	19-Jul-60	38	19	38	7.6		27	80	0.2	373
15S19E15C001M	Page	14-Aug-63	78		50	13		32	56	0.1	499
15S19E35L001M	Page	12-Aug-63	68	8.4	103	5.7	246	59	92	0.1	538
16S19E05P001M	Page	4-Jun-64	35	3.8	27	4.6		19	40		238
16S19E07E001M	Page	27-May-54		6.7		1.8		20	36		
Site #1	MAGSA	19-Nov-20	83	12	55	10	330	79.7	18	<0.1	595
Site #2	MAGSA	19-Nov-20	138	34	76	14		127	95	<0.1	978
Site #5	MAGSA	8-Dec-20	86	6	106	15	160	107	195	<0.1	675
Site #6	MAGSA	19-Nov-20	6	<1	50	1	130	9.8	15	0.2	213
Site #7	MAGSA	19-Nov-20	39		85	8		34.3	74	0.2	454
Site #8	MAGSA	8-Dec-20	79	16	59	13	330	32.8	35	<0.1	590
Site #9	MAGSA	8-Dec-20	92	6	116	12	360	62.5	102	<0.1	836
Site #10	MAGSA	19-Nov-20	14	<1	47	5		10.7	20	0.1	240
Site #11	MAGSA	8-Dec-20	75	11	61	14	190	49.7	108	<0.1	556
Site #12	MAGSA	19-Nov-20	2	<1	37	<1	60	3.8	8	0.3	111

#### Table 3-4 MAGSA Water Bank Recharge/Extraction Area Representative Groundwater Chemical Analyses



#### Figure 3-9 MAGSA Water Bank WQ Tests

No clear trends emerged from the geochemical analysis. The lower TDS samples (shown as a small cross) tended to have higher percentages of bicarbonate and sodium. The lower TDS samples also were more likely to be from older groundwater quality samples, which tended to be shallow wells. In the anions, there may be a trend towards lower chloride concentrations with lower TDS. The lack of a trend may be a function of the large area being sampled and the wide range of depths and well types.

Based on the available groundwater quality data, it appears likely that the available groundwater quality (generally more than 500 mg/L) could have higher salinity than DMC inflows to Mendota Pool (generally less than 400 mg/L). The recently completed Mendota Pool Group Environmental Impact Statement/ Environmental Impact Report includes criteria for surface water quality that are expected to be comparable to those likely to be implemented for the Aquaterra Groundwater Bank. The criteria (**Table 3-5** and **Table 3-6**, taken from the Mendota Pool Group Final EIS/EIR) require that water quality in the Mendota Pool (at sampling point 9, on Fresno Slough south of Highway 180) be maintained at salinity levels that are less than 450 mg/L. These are also the water quality requirements for water returned to the Mendota Pool. While the average groundwater quality that has been characterized for the Aquaterra Groundwater Bank storage area (**Figure 3-8**) appears to average roughly 540 mg/L based on preliminary groundwater quality sampling, there are many areas with groundwater quality that is better than 450 mg/L. The Aquaterra Groundwater Bank will be able to preferentially extract groundwater with better water quality than the 450 mg/L target through locating wells in good groundwater quality areas. During project development, extraction wells would be preferentially located in areas of better water quality and during operations, the better-quality wells could be preferentially operated for extractions

#### Table 3-5 Surface Water Quality Thresholds (Metals)

Parameter	Maximum Concentration	Reference and Notes
Arsenic	10 μg/L <sup>1</sup>	Sacramento-San Joaquin Valley Basin Plan, CVRWQCB 2016a; criteria for Sacramento River and Delta. Dept. of Public Health Primary Maximum Contaminant Level (MCL).
Boron	800 µg/L <sup>1</sup>	Sacramento-San Joaquin Valley Basin Plan, CVRWQCB 2016a; criteria for San Joaquin River reach between Merced River and Vernalis.
Molybdenum	19 µg/L <sup>1</sup>	Sacramento-San Joaquin Valley Basin Plan, CVRWQCB 2016a; criteria for San Joaquin River reach between Sack Dam and Merced River. Beneficial Use Agricultural Water Quality, Ayers & Wescot 1985.
Selenium	2.0 μg/L <sup>1</sup>	Sacramento-San Joaquin Valley Basin Plan, CVRWQCB 2016a; criteria for San Joaquin River reach between Sack Dam and Merced River. Beneficial Use Agricultural Water Quality, Ayers & Wescot 1985.

Notes: Beneficial uses of California waters that may be protected against water quality degradation include domestic, municipal, agricultural, industrial, recreational, aesthetic enjoyment, preservation of fish and wildlife, and aquatic resources or preserves. Beneficial uses do not include all reasonable uses of water (i.e., wastewater disposal or dilution of salts; CVRWQCB 2016a).

As the Basin Plans do not contain specific WQOs for the Mendota Pool or Fresno Slough, objectives that apply to nearby regions included within the Basin Plans are used. Thresholds for arsenic, boron, molybdenum and selenium concentrations are the same as thresholds for trace element concentrations in the 2004 Final EIS and are the WQOs listed in the Annual Reports. Reclamation's standard for selenium concentration in non-Project water introduced into federal facilities or for exchange is ≤ 2 ppb with no allowance for dilution. This criterion is based on the CVRWQCB's 1996 selenium objective of 2 ppb monthly average for Grasslands wetlands water supply channels.

Sources: CDFW 2011; California Toxics Rule; National Toxics Rule; CVRWQCB 2016a.

#### Table 3-6 Surface Water Quality Thresholds (Salinity)

Parameter	Maximum Concentration	Measurement Type
TDS	600 mg/L	Monthly (January – August; December)
	450 mg/L	Monthly (September – November)
	450 mg/L	Annual

Additionally, the water bank will seek to improve groundwater water quality with a variety of approaches. Recharge of surface water with relatively lower TDS should improve the groundwater quality in the unconfined aquifer. Over time, water quality in the unconfined aquifer may improve somewhat in quality to become comparable to the recharge water (which is estimated to have a TDS of about 285 mg/L). The volume of unconfined groundwater above the confining clay layer in the Aquaterra Groundwater Bank

storage area is estimated to be 2.2 million acre-feet based on 2016 groundwater levels, estimated specific yield values and the mapped elevation of the confining clay layer. Assuming 800,000 acre-feet of storage is added to the existing unconfined storage volume through the Aquaterra Groundwater Bank initial storage operations, the overall groundwater quality would improve from 540 mg/L to 476 mg/L.

In addition to the project benefits of lower recharge salinity from water bank operations, MAGSA plans to augment local water supply with other high quality surface water supplies. The addition of lower salinity recharge from water bank operations and other water supply actions will gradually improve local groundwater quality. In summary, it appears that MAGSA extractions can be provided at salinity levels that meet Mendota Pool beneficial uses as identified in the Mendota Pool Group EIR and that Aquaterra Groundwater Bank groundwater salinity will improve over time to levels that approach the extracted water quality targets. Aquaterra Groundwater Bank water quality is a topic that will be reviewed with regulatory agencies and water agencies that rely on water from Mendota Pool as the program is developed. It is expected that agreements will be developed, potentially with discharge requirements similar to the recently adopted Mendota Pool Group requirements, which would address salinity and water quality needs, and would include ongoing monitoring to document compliance.

## 4 Infrastructure Requirements

## 4.1 General Description

The Aquaterra Groundwater Bank infrastructure will consist of canal conveyance, pump stations, recharge basins, recovery wells, and monitoring wells. The project design analyzed is based on a 770 cfs flow into facility during maximum recharge operations, and 480 cfs of flow to the Mendota Pool during maximum recovery operations. **Figure 4-1** shows the overview layout of the Aquaterra Groundwater Bank facilities. During recharge operations, water will be initially pumped from the Fresno Slough into the Jensen Canal at the west end of the Jensen Canal and outside the wildlife refuge. The canal will follow Jensen Avenue to the eastern boundary of MAGSA and to the East-Side Canal. The East-Side Canal will generally follow the eastern MAGSA boundary north and south of Jensen Avenue to deliver water to the four recharge site locations. After the water has been recharged and an interested party is ready to recover water, recovery wells spread out among the basins will return water to the canal system. The canals will then return the water to the starting point at the Fresno Slough. The components of the Aquaterra Groundwater Bank infrastructure are discussed in the following sections. For concept designs, refer to **Appendix E** for Jensen Canal and **Appendix** for East-Side Canal.

## 4.2 Design Considerations

#### **Conveyance**


The canals will be designed to have 1.5:1 side slopes, 0.0001 hydraulic slope, 2 feet of freeboard, and 14 feet drive roads on both sides of the canal. The pump stations will consist of concrete pump structure and a combination of natural gas pumps due to the limited use and electrical pumps to meet air quality standards. The pump stations will be standardized for 13.5 feet of lift which provides MAGSA with simpler operations and maintenance and allows for the canal earthwork to be balanced without requiring large fills.

#### **Recharge Sites**

Recharge sites for the Aquaterra Groundwater Bank will be comprised of multiple basins broken down into cells that are on average 40-acres. The total area for recharge were estimated assuming the basins could recharge 0.5 acre-feet per day. It is assumed only 80% of the acreage would be utilized for active recharge with the remaining 20% of the area would be comprised of levees and drive roads. The basins will have minimum side slopes of 3:1 and have a minimum top width of 14 feet to accommodate a drive road for construction, operations and maintenance equipment.

#### **Recovery Wells**

Recovery wells will be located at the recharge basins to discharge water into the conveyance canal that would be used to send water back to the Fresno Slough and Mendota Pool. The recovered water will either discharge directly into the canal or be returned to canal by a return pipeline. The recovery wells will be spaced at least a quarter mile from each other and from landowner wells to minimize well interference. For the purposes of this study the recovery wells are assumed to produce 2,500 gpm (5.5 cfs) based on experience in other groundwater banks in the area. The well pumps will be driven with electric motors. It is important to note that the recovery wells are planned to be perforated and completed above the E-Clay in order to recover water from the same aquifer that receives the recharged water.



4/22/2022 : G:\McMullin GSA-2659\265921004-MAGSA GW Bank\400 GIS\Map\MAGSA\_GroundwaterBank\_Overview.mxd

#### Monitoring Wells

To track groundwater conditions during recharge and recovery operations, dedicated monitoring wells will be constructed at each of the recharge sites. Each recharge site will have about 10 shallow monitoring wells and 1 or 2 deep monitoring wells. The shallow monitoring wells will be around 100-200 feet deep and be a half a mile between the monitoring wells. In some instances where the basins are close together, there may be a quarter mile between monitoring wells. The deep monitoring wells will be around 500 feet deep with perforations from 200/300 feet to 500 feet depth. Generally, a deep monitoring well will be located next to one of the shallow monitoring wells.

## 4.3 Facilities

To convey water to and from the recharge facilities, approximately 72 miles of canal and 22 pump stations will be built. There will be three connections to the Mendota Pool. The first is a 400 cfs canal from the Mendota Pool along the Jensen Avenue alignment. The second is a 250 cfs connection near the existing Mid-Valley Water District pump station canal utilizing a pump station at Mid Valley Water District and a pump station at the start of the James Bypass. There would be a 250 cfs canal from the James Bypass pump station to the Mid-Valley Water District pump station. After the Mid-Valley Water District pump station, the canal would be 400 cfs and parallel the bypass then follow American Avenue to the east side of MAGSA. The East-Side Canal would be 500 cfs and connect recharge sites 1, 2, 3, 4, and 5. There are two canals that extend the McMullin Phase 1 canal: Siskiyou and McMullin Expansion. The Siskiyou canal goes north from Phase 1 to the East-Side Canal along Siskiyou Ave. The McMullin Expansion goes east along Floral and Nebraska Ave to the East-Side Canal.

There are approximately 3,840 acres of direct recharge facilities planned along the northern and eastern borders of MAGSA. There is approximately 400 acres in site 1, 450 acres in site 2, 550 acres at site 3, 500 acres at site 4, and 1,940 acres at site 5. At full buildout, these sites would provide a combined 1,540 AF/day of recharge capacity.

To return water to the Mendota Canal there are 87 recovery wells with 12 recovery wells at Site 1, 14 recovery wells at Site 2, 10 recovery wells at Site 3, 19 recovery wells at Site 4, and 33 recovery wells at Site 5. The layout of alternative 4 is shown in **Figure 4-1**. Combined these wells could recover up to 485 cfs, or 960 AF/day.

## 4.4 Project Costs

Costs were analyzed for the project assuming a recharge capacity up to 770 cfs (1,540 AF/day) and a recovery capacity of 480 cfs (960 AF/day). The costs were developed to provide a rough order of magnitude estimate, appropriate for the current level of project definition. Earthwork quantities for the canals were estimated based on the McMullin Expansion Project (currently being designed). Costs were developed using a variety of sources including RS Means and experience with other construction projects in the region. Given the level of development of the project, it is appropriate to provide a range of costs between -20% and +30% of the estimated capital costs. Total capital costs are expected to range between \$478,250,000 and \$777,156,000. Capital costs are presented in **Table 4-1**, with more detail provided in **Appendix G**. The capital costs break down to approximately \$598 to \$971 per AF of storage capacity, as shown in **Table 4-2**.

Construction Costs				
Jensen Canal	\$58,557,000			
East-Side Canal	\$82,674,000			
American Canal	\$58,566,000			
Siskiyou Canal	\$23,514,000			
McMullin Canal	\$40,000,000			
Recharge Facilities	\$73,024,000			
Recovery Facilities	\$87,000,000			
Monitoring Wells	\$1,750,000			
General Conditions Costs	\$48,890,000			
Construction Subtotal	\$425,085,000			
Non-Construction Costs				
Land Acquisition	\$87,710,000			
Engineering	\$37,918,000			
Permitting and Compliance	\$18,959,000			
Construction Management	\$37,918,000			
Non-Construction Subtotal	\$172,727,000			
Project Total	\$597,812,000			
Project Total +30%	\$777,156,000			
Project Total -20%	\$478,250,000			

#### Table 4-1 Summary of Capital Costs

#### Table 4-2 Cost of Storage Capacity

	Initial Capital Cost	Storage Capacity (AF)	Initial Capital Cost (\$/AF Capacity)
Project Total -20%	\$478,250,000	800,000	\$598
Project Total	\$597,812,000	800,000	\$747
Project Total + 30%	\$777,156,000	800,000	\$971

To develop annual costs, capital costs were amortized over a 40-year period, assuming a 4% interest rate. Annual maintenance costs are assumed to be 10% of the amortized capital costs. The combined capital amortization and maintenance costs are considered the baseline annual costs. However, costs are expected to vary between recharge and recovery years. During recharge years, there will be additional energy costs, both natural gas and electric, to convey water from the Mendota Pool to the recharge sites through the canals and pump stations. Using PG&E rates, natural gas was assumed to cost of \$1.32 per 100,000 BTU and \$0.30 per kilowatt-hour. The annual recharge assumes water is recharged 24 hours a day for 5 months out of the year. During recovery years, there will be electric energy costs to recover the banked water from the aquifer and convey it to the Mendota Pool. For the purposes of developing recovery pumping costs, pumping depths are assumed to be between 225 and 320 feet below ground surface. Conveyance towards the Mendota Pool will be by gravity, subsequently there will not be significant energy costs associated with recovered water conveyance. The annual recovery costs assume the recovery wells run 24 hours a day for 5 months out of the year. **Table 4-3** summarizes range of baseline annual costs. **Table 4-5** summarizes the additional cost to recover water and return it to the Mendota Pool.

#### Table 4-3 Baseline Annual Costs

	Amortized	Annual	Total
	<b>Capital Costs</b>	Maintenance	Annual Costs
Project Total -20%	\$23,985,000	\$2,398,500	\$26,383,500
Project Total	\$29,982,000	\$2,998,200	\$32,980,200
Project Total + 30%	\$38,976,000	\$3,897,600	\$42,873,600

#### Table 4-4 Recharge Costs

Electric Costs	\$12,714,000
Natural Gas Costs	\$6,660,800
Total Cost	\$19,374,800
Annual Recharge (AF)	208,000
Recharge Cost (\$/AF)	\$93

#### Table 4-5 Recovery Costs

Electric Costs	\$23,934,000
Annual Recovery (AF)	146,000
Recovery Cost (\$/AF)	\$164

## **5 Regulatory Considerations**

## 5.1 Permits and Approvals

Construction and operation of the water bank and conveyance will require coordination, consultation and permits from multiple agencies with jurisdiction for various aspects of Aquaterra Groundwater Bank. The following **Table 5-1** is based on experience in developing various groundwater water banking and conveyance projects. During the environmental review process, the need for the various permits and approvals will be further refined.

Agency	Requirement	Applicability	Compliance Procedure
County of Fresno	Groundwater Export	The groundwater bank will operate to recover banked water	File for a permit as described in County of Fresno Ordinance 14.03.
U.S. Army Corps of Engineers (USACE)	Section 404 Nationwide or Individual Permit	Work requiring discharge of fill to surface waters	Submit Section 404 Permit Application. Wetland delineation may be required. This process may take 18 – 24 months.
U.S. Fish and Wildlife Service (USFWS)	Endangered Species Act	Any work that could impact listed species	Section 7 Consultation prior to submittal of Section 404 Permit Application to USACE.
Central Valley Regional Water Quality Control Board (RWQCB)	Section 401 Water Quality Certification	Work requiring discharge of fill to surface waters	Submit Section 401 Water Quality Certification application during design process.
	Stormwater Pollution Prevention Plan (SWPPP)	Any work disturbing one acre or more.	Develop SWPPP prior to project bidding. Construction contractor to obtain final permit with initiation of construction.
California Department of Fish and Wildlife (CDFW)	Streambed Alteration Agreement	Work altering a stream channel	Submit LSAA application.
	California ESA	Any work that could impact listed species	Initiate with CDFW.

Table 5-1 Permits and Approvals

## Section Five: Regulatory Considerations Water Bank Feasibility Study

Agency	Requirement	Applicability	Compliance
ingeney	nequirement	rippilouomity	Procedure
San Joaquin Valley Air Pollution Control District	Indirect Source Review (ISR)	All development work	Submit ISR application to SJVAPCD during CEQA process.
	Dust Control Plan (DCP)	All development with over 5 acres of disturbed area	Submit plan for conditional approval during design. Contractor to obtain final approval.
	Permit to Operate (PTO)	Only needed if propane or natural gas driven engines are used to operate lift pumps	Submit application during design and prior to initiation of construction.
U.S. Bureau of Reclamation	Warren Act Contract	Project partners conveying non-federal water through federal facilities (i.e., Delta- Mendota Canal)	Coordinate with USBR staff in the local office.
	Acknowledged Water Bank	While not required, this acknowledgement allows CVP contractors to take delivery of their water at the bank. It may be advantageous for MAGSA to obtain for their project partners.	Submit a detailed proposal as outlined in USBR's "Groundwater Banking Guidelines for Central Valley Project Water".
Central California Irrigation District (CCID) / San Luis & Delta-Mendota Water Authority (SLDMWA)	Agreements for utilization of Mendota Pool	CCID owns Mendota Dam. San Luis & Delta- Mendota Water Authority operate the Mendota Pool	Initiate discussions and develop agreement(s) as needed.
Various	Encroachment Permits	Work within other agencies rights-of-way	Coordination and submittals to Union Pacific Railroad, California Dept. of Transportation, Reclamation District 1606, County of Fresno Public Works, and potentially others.

## 5.2 Environmental

California contains several rare plant and animal species. In this context, "rare" is defined as species known to have low populations or limited distributions. As the human population grows, resulting in urban expansion which encroaches on the already limited suitable habitat, these sensitive species become increasingly more vulnerable to extirpation. A variety of state and federal regulations, including the Endangered Species Act, have provided the California Department of Fish and Wildlife (CDFW) and the U.S. Fish and Wildlife Service (USFWS) with a mechanism for conserving and protecting the diversity of native plant and animal species. Numerous native plants and animals have been formally designated as "threatened" or "endangered" under State and federal endangered species legislation. Other formal designations include "candidate" for listing or "species of special concern" by CDFW. The California Native Plant Society (CNPS) maintains a list of native plants considered rare, threatened, or endangered. All plants with a CNPS Rare Plant Rank of 1 or 2 meet the definition of the California Endangered Species Act and are eligible for State listing. Collectively these plants and animals are referred to as "special status species." Impacts to these species, either directly through injury or mortality, or indirectly through habitat loss must be analyzed during the preparation of environmental documents relating to California Environmental Quality Act (CEQA).

A thorough search of the California Natural Diversity Database (CNDDB) for published accounts of special status plant and animal species was conducted for the *Mendota Dam, Gravelly Ford, Tranquillity, Jamesan, Kerman, Kearney Park, San Joaquin, Helm, Raisin, and Caruthers 7.5-minute quadrangles that contain the MAGSA area, and for the 20 surrounding quadrangles: Firebaugh, Poso Farm, Firebaugh NE, Bonita Ranch, Madera, Biola, Hernson, Fresno North, Fresno South, Malaga, Conejo, Laton, Riverdale, Burrel, Five Points, Westside, Tres Picos Farms, Cantua Creek, Levis, and Coit Ranch. A list of these species and a discussion regarding their potential to occur within the Project area can be found in Appendix H. Raw data obtained from the CNDDB is available in Appendix I. Figure 5-1 shows the locations of the CNDDB published accounts of special status species observations within and adjacent to the GSA. It is important to note that CNDDB is a positive detection database. Records only exist in the database where species have been detected. There may be additional occurrences or additional species within this area which have not yet been surveyed and/or mapped. Lack of information in the CNDDB about a species or an area can never be used as proof that <i>no* special status species occur in an area.

The proposed pump station is located within the Fresno Slough in the Mendota Wildlife Area. Several protected aquatic and terrestrial species are known to occur in this area of high-quality wetland habitat. The Fresno Slough is considered a Water of the U.S. or "jurisdictional water" subject to the jurisdiction of the U.S. Army Corps of Engineers (USACE). The USACE regulates the filling or grading of Waters of the U.S. under the authority of Section 404 of the Clean Water Act. All activities that involve the discharge of dredge or fill material into Waters of the U.S. are subject to the permit requirements of the USACE. Such permits are typically issued on the condition that the applicant agrees to provide mitigation that result in no net loss of wetland functions or values. It is important to note that USACE is not obligated to issue a permit if the Project applicant cannot prove that the Project as described is the Least Environmentally Damaging Practicable Alternative (LEDPA). Furthermore, USACE cannot issue a permit until the Regional Water Quality Control Board (RWQCB) issues a Section 401 Water Quality Certification (or waiver of such certification) verifying that the proposed activity will meet state water quality standards.

Under the Porter-Cologne Water Quality Control Act of 1969, the State Water Resources Control Board has regulatory authority to protect the water quality of all surface water and groundwater in the State of California ("Waters of the State"). Nine RWQCBs oversee water quality at the local and regional level. The RWQCB for a given region regulates discharges of fill or pollutants into Waters of the State through the issuance of various permits and orders. Discharges into Waters of the State that are also Waters of the U.S. require a Section 401 Water Quality Certification from the RWQCB as a prerequisite to obtaining certain federal permits, such as a Section 404 Clean Water Act permit. Discharges into all Waters of the State, even those that are not also Waters of the U.S., require Waste Discharge Requirements (WDRs), or waivers of WDRs,

from the RWQCB. The RWQCB also administers the Construction Storm Water Program and the federal National Pollution Discharge Elimination System (NPDES) program. Projects that disturb one or more acres of soil must obtain a Construction General Permit under the Construction Storm Water Program. A prerequisite for this permit is the development of a Storm Water Pollution Prevention Plan (SWPPP) by a certified Qualified SWPPP Developer. Projects that discharge wastewater, storm water, or other pollutants into a Water of the U.S. may require a NPDES permit.

CDFW has jurisdiction over the bed and bank of natural drainages and lakes according to provisions of Section 1601 and 1602 of the California Fish and Game Code. Activities that may substantially modify such waters through the diversion or obstruction of their natural flow, change or use of any material from their bed or bank, or the deposition of debris require a Notification of Lake or Streambed Alteration. If CDFW determines that the activity may adversely affect fish and wildlife resources, a Lake or Streambed Alteration Agreement will be prepared. Such an agreement typically stipulates that certain measures will be implemented to protect the habitat values of the lake or drainage in question.

The following is a list of permits and/or approvals anticipated to be required in order to construct a new turnout or pumping facility within the Fresno Slough:

- Coordination with CDFW regarding construction within the Mendota Wildlife Area
- ESA Consultation with CDFW and Incidental Take Permit (ITP)
- ESA Consultation with USFWS and National Marine Fisheries Service (NMFS)
- USACE Section 404 permit (may qualify for coverage under a Nationwide Permit)
- RWQCB Section 401 Water Quality Certification
- Section 1602 Lake or Streambed Alteration Agreement
- Central Valley Flood Protection Board (CVFPB) Encroachment Permit
- California State Lands Commission (CSLC) Lease
- CEQA and NEPA documentation

In order to obtain the aforementioned permits, the following services are anticipated to be required:


- Biological surveys and reports
  - Giant gartersnake trapping, DNA sampling, and focused surveys
  - USFWS Biological Assessment
  - NMFS Biological Assessment
  - o CDFW Biological Assessment
  - o Protocol-level Swainson's Hawk Surveys
  - o Protocol-level Rare Plant Surveys
- Aquatic Resources Delineation and Jurisdictional Determination or Verification
- Section 106 Cultural Resources Inventory and State Historic Preservation Officer (SHPO) Consultation
- Preparation of a Habitat Conservation Plan and Mitigation and Monitoring Program
- Engineering, design, and implementation of NMFS-approved fish screens
- Dewatering of the channel and implementation of giant gartersnake exclusion fencing (if required by the USFWS and CDFW consultation)
- If dewatering is required, implementation of a fish rescue and relocation plan approved by USFWS, CDFW, and NMFS
- Compensatory mitigation for temporary and permanent impacts within the Fresno Slough and associated wetland habitat

The aforementioned anticipated permits, approvals, and associated services are based on assumptions made from the preliminary Project information available at this time. This is not an exhaustive list. Additional permits, fees, and agency coordination may be required.


Figure 5-2 shows the locations of protected areas administered by public agencies and non-profits. The Mendota Wildlife Area is comprised of approximately 11,800 acres consisting of flatlands and floodplain. Major representative plant communities and habitat types are seasonally flooded freshwater emergent wetland, valley foothill riparian and, to a lesser extent, alkali sink scrub. Wildlife species of particular interest which occur at this wildlife area include a variety of migratory waterfowl, pheasants, and several potentially occurring rare, threatened or endangered plants and animals. Additional state preservation areas in the GSA include the Alkali Sink Ecological Preserve and Kerman Ecological Reserve. Both of these areas provide habitat for special status species and should be avoided if possible. Work within an ecological preserve would require additional agency coordination and would increase the chances of encountering a special status species, as evidenced by the number of CNDDB occurrences recorded in these areas. For example, as illustrated in Figure 5-3, the Alkali Sink Ecological Reserve contains USFWS-designated critical habitat for the state- and federally-threatened Fresno kangaroo rat. Other inventoried non-profit conservation easements are labeled in brown on Figure 5-2. A conservation easement is a voluntary legal agreement that permanently limits uses of the land in order to protect its conservation values. Like ecological preserves, conservation easements also typically provide habitat for special status species. If possible, it is recommended that MAGSA avoid these areas, as well, since there will be land use restrictions and additional agency coordination required to work within these areas.

While the aforementioned discussion describes areas that the Aquaterra Groundwater Bank should potentially avoid, **Figure 5-4** helps to illustrate some areas that may be more suitable for developing groundwater basins within the GSA. **Figure 5-4** illustrates the various vegetation communities within the GSA. Some of these communities provide higher quality habitat for wildlife than others. If possible, Aquaterra Groundwater Bank should aim for development of groundwater basins in areas with lower quality habitat such as those mapped as urban, barren, or cropped.


**Figure 5-5** illustrates the locations of inventoried streams, wetlands, and waterbodies, although many of those illustrated on the map may be historical and no longer accurate. When possible, streams, wetlands, and waterbodies should be avoided because these areas can provide habitat and serve as movement corridors for special status species. Furthermore, impacts to aquatic features typically require additional permitting, restoration, and/or compensatory mitigation depending on the value of the impacted resource. While **Figure 5-5** gives a broad idea of where some of these aquatic resources may be located, it is recommended that a biologist conduct a field survey of proposed Aquaterra Groundwater Bank areas to determine whether jurisdictional aquatic features are present.




4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\Bio\McMGSA\_CNDDB.mxd




4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\Bio\McMGSA\_CPAD.mxd



4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\Bio\McMGSA\_CriticalHabitats.mxd



4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\Bio\McMGSA\_Vegetation.mxd



4/10/2020 : G:\McMullin GSA-2659\2659 On-going\GIS\Map\Bio\McMGSA\_Wetlands.mxd

#### **Cultural Resources**

Record Search 20-139 (**Appendix J**) was received April 14, 2020, for the McMullin Area GSA Groundwater Banking Reconnaissance Study Project. The California Office of Historic Preservation (OHP) contracts with the California Historical Resources Information System's (CHRIS) regional Information Centers (ICs) to maintain information in the CHRIS inventory and make it available to local, state, and federal agencies, cultural resource professionals, Native American tribes, researchers, and the public. According to the information in their files, there have been 30 previous cultural resource studies conducted within portions of the project area.

There are 30 recorded resources within the project area. These resources include prehistoric era lithic scatters, bedrock milling features, beads, groundstones, mounds, firecracked rocks, and burials. They also include historic era railroads, canals, trash scatters transmission lines, a farming community, and various types of buildings.

Resource P-10-006617, the Fresno Slough Bypass, has been given a National Register status code of 2D2, indicating it is a contributor to a district that has been determined eligible for listing in the National Register of Historic Places by a consensus through the Section 106 process. It is also listed in the California Register of Historical Resources. There are no other recorded cultural resources within the project area that are listed in the National Register of Historical Resources, the California Register of Historical Interest, California Inventory of Historic Resources, or the California State Historic Landmarks.

This cultural resources review was conducted with the understanding 1) that the purpose of this project is to identify areas that would be best suited for a groundwater bank and look at a fatal flaws analysis at a programmatic level within the 120,000-acre MAGSA boundary, and 2) that because specific project areas have not yet been identified, no ground disturbance activities are currently planned. Prior to any future ground disturbance activities related to this project, it is recommended that a new record search be conducted for each specific ground disturbance project area identified so specific recommendations can be made.

## 6 Participant Involvement

Initial meetings continue to be held with interested program participants to identify their level of project interest for use in operations planning. A project planning agreement is in development that will provide for joint payment of specified project development costs in return for a future share of the developed project facilities. The planning agreement will specify the percentage involvement of program participants and their role in providing advice on project development.

## 6.1 Physical Aspects of Aquaterra Groundwater Bank

<u>Regulation Capacity</u> – Regulation capacity (or recharge capacity) is defined here as the volume and flow rate that can be delivered to the Aquaterra Groundwater Bank facility and is typically measured at the Point of Delivery at Mendota Pool or James Bypass. The maximum regulation capacity will be determined by the physical limitations of recharging water at the banking site(s). A minimum amount might be needed so that MAGSA is not regulating small amounts of water, or operating for short durations, thus incurring unreasonably high operational costs. An alternative to defining a minimum regulation capacity would be establishing a specified recovery usage charge that would pay for use up front and would be credited to actual recovery operations cost.

<u>Recovery Capacity</u> – Recovery capacity is defined here as the volume and flow rate that can be recovered from the banking facility and delivered to the Point of Delivery. This should be bounded by a minimum amount and a maximum amount. The maximum amount will be limited based on the recovery well capacities and available conveyance capacity. The minimum amount may be needed to minimize operational costs and to allow MAGSA to analyze the return in the context of their SGMA obligations for MOs / MTs. The banking partner would need to propose a recovery schedule by a certain date (April / May) to MAGSA. The schedule allows MAGSA to anticipate their seasonal operational needs and to confirm availability of conveyance capacity, either direct or by exchange. The recovery schedule would also provide the benefit of aiding in a SGMA analysis to ascertain whether the operations would cause the aquifer to approach a MT. This may also be limited based on operational constraints as recovery may cause declining water levels for the adjacent landowners.

<u>Storage Capacity</u> – Storage Capacity is defined as the maximum volume allowed to be stored at any one time in the aquifer below MAGSA. The storage capacity was identified based on physical available groundwater storage (which was not limiting), participant operational needs and ability to recharge or recover stored water over design hydrologic periods. The banking partners are allowed, and even encouraged, to cycle water through the facility often, provided that the maximum storage capacity is not exceeded. The storage capacity will be defined in participant agreements, which may also provide for flexibility in use of other participants' storage capacity if other participants agree. Storage capacity for the initial phase would be 800,000 AF.

<u>Operational Losses</u> – Most banking arrangements account for losses due to evaporation and conveyance as well as losses within the aquifer as a percentage of the volume delivered. Actual recharge losses can be difficult to directly measure or calculate and are typically stipulated at 10% but may be as high as 15%. In programs where the losses are lower, it is usually because the evaporation losses are being directly calculated, but the other losses are still stipulated as a percentage.

<u>Point of Delivery</u> – This location will be where water is measured in and out of the bank. For this program, where water is envisioned to be sourced from either the SWP or the CVP, it is recommended the Point of

Delivery be the Mendota Pool. Any losses to get water back to the banking partners beyond the Mendota Pool would be the responsibility of the banking partner.

<u>Conveyance Priority</u> – Priority for the use of the conveyance system to the banking facilities will need to be defined in project operation agreements. As the banking partners are the major financial contributors to the program, they will need assurances that when they have water available, MAGSA will make the conveyance facility available. If there are conveyance capacity limitations in the local conveyance system, MAGSA may need to shift their operations to accommodate the banking partners.

<u>Recharge Priority</u> – As the banking partners are providing the majority of the capital for the project, it is reasonable that they would expect for their water to be recharged as the priority.

## 6.2 Financial Aspects of Aquaterra Groundwater Bank

<u>Capital Costs</u> – Capital costs are planned to be the responsibility of the banking partner, with MAGSA having the option to provide funding in exchange for recharge or recovery priority. Capital costs (land, construction, design, permitting, etc.) will be agreed to between MAGSA and participants prior to construction and documented in an agreement. MAGSA and the banking partner will mutually agree on project scaling to keep the project within the budget, or mutually agree on budget increases if necessary. The banking partner and MAGSA may also consider pursuing grants for the project to offset capital costs.

<u>Operations, Maintenance and Replacement Costs</u> – The banking partner will be responsible to pay for the operation and maintenance costs actually incurred. MAGSA may consider using a specified recovery usage charge to provide funding in advance of actual use and to assure maintenance of operational capability during periods of low or minimal banking use. If MAGSA utilizes the facilities, then the amount could be prorated for the year based on the volume of water each entity has delivered to the facility.

- Operations costs will include, but are not limited to:
  - Energy costs to pump water to the banking sites
  - Energy costs to recover water from the banking sites
- Maintenance costs will consist of all costs to maintain the facilities and their proper function.
- Replacement costs will be developed based on the present value of components and amortized over the life of the project.

#### **Governance and Partner Relationships**

Generally, there are two ways the Aquaterra Groundwater Bank could be developed. First, a Joint Powers Authority (JPA) could be formed between MAGSA and the banking partner(s). This would provide for joint ownership which would lead to shared operations, maintenance, and management responsibilities. It may also delay development of the project, as very little work would be done until the JPA was formed. Second, the Aquaterra Groundwater Bank could be developed by agreement between MAGSA and program participants. There are various forms of water banking program agreements that range from extremely detailed to very brief; the detail depends on the parties involved and the circumstances under which the bank will operate. The agreements could be developed as MAGSA simultaneously develops the project(s). It is understood that MAGSA desires to develop this program and begin operations as soon as possible as part of their GSP implementation strategy. It is primarily for this reason that it is recommended MAGSA pursue the program through an agreement.

#### Project Development

It is envisioned that MAGSA would retain complete ownership of any project facilities and hold water that is stored in the aquifer in trust for the banking partners. As such, MAGSA will be responsible for the project

execution inclusive of all permits, environmental documentation, design, construction, land acquisition, and other responsibilities to develop a functioning project. The banking partners would review and agree to contracts and costs as they are developed and prior to MAGSA entering into any agreements.

#### Monitoring Committee

A monitoring committee that is made up of representatives from MAGSA, banking partners, and adjacent landowners is recommended. The committee would review operations annually and provide advisory recommendations regarding the bank's operations. It is recommended to include adjacent landowners on the committee so their concerns, if any, can be voiced and directly addressed.

#### Schedule

A preliminary schedule has been prepared to aggressively develop the Aquaterra Groundwater Bank. The schedule assumes MAGSA has banking partners ready to commit to the program, and that the work to develop the program will continue immediately after completion of this study. It is anticipated that environmental permitting could be accomplished by the end of 2023. A phased approach to the engineering and construction will be employed to allow for some work to commence without the entire program design being complete. The first phase of recharge projects could be ready to accept water in the second quarter 2024 with all recharge facilities completed by 2026. Recovery facilities will be developed over a 3-year period beginning in 2024 and ending in 2027. The schedule is shown in **Figure 6-1**, with more detail provided in **Appendix K**.

#### Figure 6-1 Preliminary Schedule

)	Task Name	Duration	Start	Finish	2021 Qtr3 Qtr4 Qtr1 0	2022 Qtr 2 Qtr 3 Qtr 4 Qtr 1	Qtr 2 Qtr 3 Qtr 4	2023 Qtr 1 Qtr 2 Qtr 3 Qtr	2024 4 Qtr 1 Qtr 2 Qtr 3	2025 Qtr 4 Qtr 1 Qtr 2 Qt	2026 tr 3 Qtr 4 Qtr 1 Qtr 2	2027 Qtr 3 Qtr 4 Qtr 1 Qtr 2
1	Program Development	480 days	Mon 10/5/20	Fri 8/5/22								
4	Stakeholder Outreach	1200 day	rs Mon 10/5/20	Fri 5/9/25						1		
9	Legal	480 days	Mon 7/12/21	Fri 5/12/23								
12	Environmental Documenta	ntion 267 days	Thu 9/30/21	Fri 10/7/22		,						
9	Permitting	315 days	Mon 10/10/22	Fri 12/22/23			-		-			
6	Engineering	1225 day	rs Mon 3/22/21	Fri 11/28/25	-							
7	Conceptual Design	440 days	Mon 3/22/21	Fri 11/25/22	-		1					
3	Surveys	170 days	Mon 6/13/22	Fri 2/3/23			-	-				
55	Conveyance Design	670 days	Mon 6/13/22	Fri 1/3/25			• <sub>r</sub>					
19	Recharge Design	680 days	Mon 7/11/22	Fri 2/14/25								
83	Recovery System Desigr	n 595 days	Mon 8/21/23	Fri 11/28/25								
42	Land / Easement Acquisition	on 210 days	Mon 1/23/23	Fri 11/10/23				· · · · · ·				
55	Construction	900 days	Mon 1/15/24	Fri 6/25/27								
56	Conveyance	545 days	Mon 1/15/24	Fri 2/13/26						÷		
265	Recharge Basins	545 days	Mon 2/26/24	Fri 3/27/26						¥		
274	Recovery System	665 days	Mon 12/9/24	Fri 6/25/27								
		Task		Inactive Task		Manual Summary Rollu	ip	External Milestone	٠	Manual Progress		
rojec	t: 2022-0302 AquaTerra S	Split		Inactive Milestone	+	Manual Summary		Deadline	+			
ate:	Wed 4/13/22	Milestone		Inactive Summary	1	Start-only	C	Critical				
		Summary Project Summary		Manual Task Duration-only		Finish-only External Tasks	1	Critical Split Progress				
		reget summary		ouradon-only		CAUCITION LOSIES		rogress				

## 7 Conclusions and Recommendations

## 7.1 Summary of Findings

## 7.1.1 Geology and Soils

As discussed previously and shown in **Table 2-2**, Site 1 has the highest percentage of coarse-grained materials logged in the borings. Followed in descending order with regards to precent coarse grained material by Site 2, Site 3, Site 4 and Site 5. Based on the regional geologic data for geologic facies, SAGBI rating, relative saturated hydraulic conductivity, and geologic deposits, the Site 1 area was not expected to have as permeable materials as Site 5 which is in an area of sand dune deposits with predominately sand and sandy loam soils.

The relatively high ranking of Boring 2-1, ranked second of the ten borings, illustrates that site specific data is needed to confirm the preliminary findings from the regional data. However, Boring 2-2 on Site 2 does appear to confirm KDSA's finding that the southwestern portion of the site does not appear to be favorable for recharge. Based on geologic facies, Site 3 appeared to have a relatively higher percentage of coarse-grained materials with both Facies D and E mapped there. Significant portions of Site 5 are mapped by Page and Leblanc as Facies D however, the two borings conducted do not appear to be in areas mapped as Facies D. Future borings in the Site 5 area should be advanced in locations mapped as Facies D to evaluate and compare material textures between areas not mapped as Facies D and areas mapped as Facies D. In addition, the two borings completed in Site 5 were about 5 miles apart and assessing this large of an area would require addition borings. It is possible, and maybe even likely, that there are areas in Site 5 with soil texture comparable to Site 1, and Boring 2-1.

Based on soil texture data logged in the field, the area around Borings 1-1, 1-2 and 2-1 appears to be relatively better for recharge, however the selection of a site should also consider groundwater quality as, discussed below in **Section 3.2** and available groundwater storage space above local groundwater levels. Considering the variations in soil texture between borings and between sites, additional soil borings should be conducted at sites selected for additional consideration. Furthermore, the information from the borings indicates that if additional lands are identified in the areas near Sites 1 - 5, site specific borings are warranted even if the regional literature may indicate less than favorable conditions for recharge in the area.

## 7.1.2 Groundwater Quality

The better water quality is located on the eastern edge of MAGSA and is the preferred area for recharge basins. It appears that MAGSA extractions are likely to be somewhat higher than exchanged DMC water. This is a topic that will be reviewed with regulatory agencies and water agencies that rely on water from Mendota Pool as the program is developed. It is expected that agreements can be developed that would address salinity degradation concerns and would include ongoing monitoring to document compliance and address potential compensation for possible degradation.

## 7.1.3 Project Operations

The Aquaterra Groundwater Bank has been formulated based on participation of outside water agencies potentially including SWP contractors, CVP contractors, Kings River water users, and other water agencies. MAGSA would develop, construct and operate the facility on behalf of the banking participants. The

development, construction and operation would proceed under contracts between MAGSA and banking participants, which would provide for ongoing review of project costs and characteristics by banking participants.

### 7.1.4 Infrastructure Refinement

After discussions with MAGSA, an expanded initial project formulation was also developed based on a slightly larger group of SWP contractors that would provide a total of 800,000 AF of banking storage. This expanded project formulation would provide for annual recharge capacity of 208,000 AF with instantaneous capacity of 770 cfs. The recovery capacity for this initial project formulation would be 146,000 AF per year, with instantaneous recovery of 480 cfs.

The Aquaterra Groundwater Bank will have a recharge capacity to 770 cfs to accommodate the larger group of potential partners. As currently envisioned, the project consists of approximately 72 miles of canal and 22 pump stations. To accommodate the increase in capacity, there will be two canals from the Mendota Pool to the East-Side Canal. The first canal from the Pool will be the original alignment along Jensen Avenue at 400 cfs. The second canal will be the same alignment as Alternative 2 utilizing a pump station at Mid Valley Water District and a pump station at the start of the James Bypass. There would be a 200 cfs canal from the James Bypass pump station to the Mid-Valley Water District pump station, the canal would be 400 cfs and run parallel to the bypass and then follow American Avenue to the east side of MAGSA. The East-Side Canal would be 500 cfs and connect recharge sites 1, 2, 3, 4, and 5. There are two canals that extend the McMullin Phase 1 Canal: Siskiyou Canal and McMullin Expansion. The Siskiyou Canal goes north from Phase 1 to the East-Side Canal along Siskiyou Ave. The McMullin Expansion goes east along Floral and Nebraska Ave to the East-Side Canal. There is approximately 400 acres in Site 1, 450 acres in Site 2, 550 acres at Site 3, 500 acres at Site 4, and 1,940 acres at Site 5. To return water to the Mendota Canal there are 87 recovery wells with 12 recovery wells at site 1, 14 recovery wells at site 2, 10 recovery wells at site 3, 19 recovery wells at site 4, and 33 recovery wells at site 5.

### 7.1.5 Regulatory Considerations

Construction and operation of the water bank and conveyance will require coordination, consultation and permits from multiple agencies with jurisdiction for various aspects of the Project. This section looks at permits that may be needed for groundwater water banking and conveyance projects. During the environmental review process, the need for the various permits and approvals will be further refined.

### 7.1.6 Participant Involvement

The participant agreements would generally provide for participant payment for the costs of Aquaterra Groundwater Bank facilities and their payment of actual operational costs. Participants would generally have priority access to banking recharge and recovery facilities, with MAGSA having secondary access to those facilities for its own uses on an as-available basis. MAGSA would operate the groundwater bank and maintain banking operations accounts which would reflect physical operational losses, likely as a negotiated percentage included in the project agreements. Aquaterra Groundwater Bank development agreements, including preliminary indication of operational arrangements are in development and will be finalized in the near future. The general parameters identified above may be refined as agreed to by project participants in the course of program development.

## 7.2 Recommended Next Steps

The following next steps are recommended for the continued development of the Aquaterra Groundwater Bank and offered for consideration by MAGSA:

- Considering the variations in soil texture between borings and between sites, additional soil borings should be conducted at sites considered for basin construction. Typically, the depth to future soil borings can be limited to 50 feet below grade to identify potential shallow fine-grained soil layers that could be a limiting factor for groundwater recharge. Furthermore, the information from the borings indicates that if additional lands are identified in the areas near Sites 1 5, site specific borings are warranted even if the regional literature may indicate less than favorable conditions for recharge in the area.
- Continue discussions and pursue commitments from interested parties to further develop the program.
- Refine operations and analyses based on the commitments from interested parties.
- Initiate the CEQA and NEPA processes.
- Initiate a public outreach effort that includes stakeholder discussions with the following groups:
  - Stakeholders that could affect the exchange in the Mendota Pool. These are anticipated to be the San Joaquin River Exchange Contractors and the San Luis & Delta-Mendota Water Authority. MAGSA should also consider *initiating* discussions with US Bureau of Reclamation, US Fish and Wildlife Service, and CA Dept. of Fish and Game to better understand permitting issues and timelines associated with the Mendota Pool.
  - Stakeholders affected by the Aquaterra Groundwater Bank. These would consist of landowners within the recharge sites as well as those along the planned conveyance alignments.
  - Neighboring Agencies. These would consist of the GSAs that adjoin MAGSA, as well as the neighboring irrigation and water districts.
  - MAGSA Landowners. This would be general in nature to educate the landowners within MAGSA of the benefits that will be received by developing the Aquaterra Groundwater Bank.

## 8 Bibliography/References

Cehrs, Soenke, and Bianchi (1980), USDA Technical Bulletin 1604: A Geologic Approach to Artificial Recharge Site Selection in the Fresno-Clovis area, California.

Westlands Water District (2019), Mendota Pool Group 20-Year Exchange Program Final Environmental Impact Statement/Environmental Impact Report.

# Appendix A – Kenneth D. Schmidt & Associates Memorandum

## MEMO

To: Matt Hurley From: Ken Schmidt Topic: Potential Recharge Sites Date: August 14, 2020

I have reviewed and interpreted drillers logs for wells at and near the five preliminary sites identified by Provost and Pritchard. Of most importance are 1) the thickness of surficial deposits that would need to be removed in order to construct basins or ponds, and 2) potential restricting layers above a depth of about 50 feet. A number of the wells were drilled by the cable-tool method, and logs for these are usually highly reliable in terms of texture. Following are my assessments of the sites.

#### Site 1

The site is west of Kerman, generally between Belmont and California Avenues and Lake and Trinity Avenues (Figure 1). We found logs for 27 wells in or near this site. Only three logs indicate apparently favorable or marginal conditions for basin recharge. These were all along a north-northeast to southsouthwest trending area. At two of the well sites, the upper ten feet of deposits would have to be excavated. Hardpan and relatively thick clay were common within the uppermost 60 to 70 feet of deposits at the remaining wells. Where present, sands were relatively thin at these other wells. Four soil borings are recommended in the part of Site 1 shown on Figure 1. Three borings would be done by the hollow-stem auger method to a depth of 50 feet, and the remaining one to a depth of 80 feet.

### Site 2

This site is located southwest of Kerman, primarily between California and North Avenues and Lake and Lassen Avenues (Figure 2). We found logs for 19 wells in or near this site. In general, there is more clay and sandy clay above a depth of about 70 to 80 feet at this site then at Site 1. Hardpan was also indicated at eight of the wells. None of the well logs indicated apparently favorable conditions for basin recharge. I do not recommend any soil borings at this site.

## Site 3

This site is located south of Kerman, generally between North and American Avenues and Shasta and Del Norte Avenues (Figure 3). We found logs for 13 wells in or near the site. Logs for three of these wells indicated apparently favorable conditions for basin recharge. At one well site, about six feet of surficial hardpan would need to be excavated. The favorable well sites were all located in Section 26. At the other sites, relatively thick clays were predominant to a depth of about 60 feet. Hardpan was indicated at seven well sites. I recommend soil borings in the west part of Section 25, the southwest three fourths of Section 26, and in the north half of Section 35. A total of eight borings would be done, six to a depth of 50 feet and two to a depth of 80 feet.

#### Site 4

This site is south of Kerman, between American and Lincoln Avenues and Madera and Howard Avenues. We found logs for 22 wells in or near this site (Figure 4). Only one of these indicated apparently favorable conditions for recharge, due to the presence of thick clays above about 60 feet in depth at the other wells. There were no logs in Section 5, except for one well near the northeast corner. It is possible that favorable conditions may be present in part of this section, as the most favorable log was adjacent to the south boundary of this section. I recommend four borings, two in the west half and two in the south half of Section 5. Three would be 50 feet deep and one would be 80 feet deep.

Site 5

Because of its large size, we divided Site 5 into two parts. Site 5-A is north of Manning Avenue, and Site 5-B is south of Manning Avenue.

## Site 5-A

This area is bounded by American Avenue on the north, Manning Avenue on the south, and is between West Lawn and Brawley Avenues (Figure 5). We found drillers logs for about sixty wells in this area. Apparently favorable conditions for basin recharge were indicated at only six of these. All of the favorable well sites were between South and Manning Avenues and Grantland and Cornelia Avenues. This area is primarily in Sections 21 and 22 of T15S/R19E, just north of Raisin City. At other well sites, thick clay layers were usually predominant in the uppermost 60 to 70 feet of deposits. At one of the favorable well sites, about six feet of surficial material would need to be removed.

#### Site 5-B

This area is bounded by Manning Avenue on the north and Conejo Avenue on the south, and is in between West Lawn and Brawley Avenues. We found logs for about 160 wells in this area (Figure 6). Favorable conditions for basin recharge were indicated at about 24 well sites. One of the largest apparently favorable areas is between Huntsman and Manning Avenues and Bryan and Brawley Avenues. Favorable conditions were indicated at eight well sites in an east-northwest to west-southwest trending area, east and south of Raisin City. Another apparently favorable area is between Nebraska and Mountain View Avenues and Chateau Fresno and Hayes Avenues, where conditions at five well sites were apparently favorable, in an east-west trending area. There were two additional smaller apparently favorable areas. One was near Huntsman Avenue, between Cornelia and Brawley Avenues, and another was between Floral and Rose Avenues and Chateau Fresno and Grantland Avenues. Two well sites in each area indicated apparently favorable conditions, and both areas trended from east to west.

The northernmost large area comprises about 700 acres. I recommend about six soil borings in this area. Four would be 50 feet deep and two would be 80 feet deep. The southernmost large area comprises about 850 acres. I recommend six soil borings in this area, four would be 50 feet deep and two would be 80 feet deep.




FIGURE 1 - LOCATIONS OF WELLS WITH DRILLERS LOGS AND APPARENTLY FAVORABLE AREAS FOR RECHARGE IN SITE 1




FIGURE 2 - LOCATIONS OF WELLS WITH DRILLERS LOGS FOR SITE 2

R. 17 E.




FIGURE 3 - LOCATIONS OF WELLS WITH DRILLERS LOGS AND APPARENTLY FAVORABLE AREAS FOR RECHARGE IN SITE 3




FIGURE 4 - LOCATIONS OF WELLS WITH DRILLERS LOGS AND APPARENTLY FAVORABLE AREAS FOR RECHARGE IN SITE 4




FIGURE 5 - LOCATIONS OF WELLS WITH DRILLERS LOGS AND APPARENTLY FAVORABLE AREAS FOR RECHARGE IN SITE 5A




FIGURE 6 - LOCATIONS OF WELLS WITH DRILLERS LOGS AND APPARENTLY FAVORABLE AREAS FOR RECHARGE IN SITE 5B

# Appendix B: Soil Boring Logs and Lab Reports

## Appendix B1: Soil Boring Logs

Provost & Pritchard Consulting Group • June 2022

	<b>C</b> -	ES	ST. 19	Job No. 2659-20-002 GWB						
PR	O	O	ST	Page 1 of 3						
PR	ITC	CH.	AR	D	Boring Log	Date:				
CON	ISULI	ING	GRO	UP	1-1	Project:				
An Em	ployee	Owned	d Comp	oany		Logged by:				
						Drilling Equipment:	CME-55 HSA			
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De	escriptions	Notes			
-	er	Jsed	Jsed	SM	(0-2') Silty Sand, light brown, fine	-grained, dry, loose				
- - 5 - - - 10	5' Continous Tube Sampler	Not Used	Not Used		(2-9.5') Silty Sand, reddish brown loose.					
-				ML	(9.5-12.5') Silt, gray, moist, firm, ı	red oxidation staining.				
- - 15 -				SP	(12.5-20') Sand, poorly graded, w coarse-grained, moist, loose.	white to gray, medium to				
- - 20					(18-20') Occasional pea gravel.					
- - -				SM	(20-24') Silty Sand, gray, very fine dense.	e-grained, moist, medium				
25 - - 30 - - -				SP	(24-33.5') Sand, poorly graded, gi moist, loose.					
- 35 - - - 40				ML	(33.5-40') Silt, dark brown, moist,	33.5-40') Silt, dark brown, moist, very stiff, white streaks.				

		ES	5T. 19	Job No. 2659-20-002 GWB			
PR	O	/O	ST	Page 2 of 3			
PR	ITC	Ή	ĂŔ	Ď	Boring Log	Date:	November 6, 2020
CON	ISUL	TING	GRO	UP	1-1	_ Project:	
An Err	nployee	Owned	d Com	pany		Logged by:	
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De		Notes
<b>d</b> a - - - 45 - - - - 50 - - - 55 - - - - - - - - -	5' Continous Tube Sampler	Not Used Blov	Not Used	SP ML SP SMML SP	(40-48') Sand, poorly graded, gra loose. (48-53') Sandy Silt, reddish brow moist, hard. (53-57') Sand, poorly graded, red moist, loose. (57-59') Sandy Silt/Silty Sand, gra moist, red oxidation staining. (59-63') Sand, poorly graded, wh moist, loose. (63-68') Sandy Silt/Silty Sand, gra moist, red oxidation staining.	n, fine-grained sand, Idish brown, fine-grained, ay, very fine-grained, ite to gray, fine-grained,	Lab result: 70% Sand, 30% Silt/Clay
- - - - - - 75 - - - - - 80				SM SM ML	(68-73.5') Silt, gray, moist, firm. (73.5-75' Silty Sand, gray, very fir (75-78') Sandy Silt/Silty Sand, dan moist, firm. (78-80') Silt, bright reddish brown oxidized	rk gray, very fine-grained,	

E	ST. 19	68			Job No. 2659-20-002 GWB
PROVO	ST	&	5.	Page 3 of 3	
PRITCHARD			Boring Log	Date:	November 6, 2020
CONSULTING	11111		1-1	_ Project: _ Logged by:	Mid-Valley Water Bank SEV
An Employee Owne	d Com	oany			CME-55 HSA
Depth, feet Type of Sampler Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Do	escriptions	Notes
Image: system         Image: system           -         -           - <td>Not Used PID/I</td> <td>SM SP ML SP</td> <td>(80-83') Silty Sand, gray, very fine (83-90') Sand, poorly graded, gra loose. (90-93.5) medium-grained with of inch in diameter. (93.5-98') Silt, gray, moist, hard. (98-100') Sand, poorly graded, gr grained, moist, loose. Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engine Driller: Allen Bushey/Josh Palme</td> <td>ray, fine-grained, moist,</td> <td></td>	Not Used PID/I	SM SP ML SP	(80-83') Silty Sand, gray, very fine (83-90') Sand, poorly graded, gra loose. (90-93.5) medium-grained with of inch in diameter. (93.5-98') Silt, gray, moist, hard. (98-100') Sand, poorly graded, gr grained, moist, loose. Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engine Driller: Allen Bushey/Josh Palme	ray, fine-grained, moist,	

PR PR con		/C CH	1.000.000	™ RD	Boring Log 1-2	Date: Project: Logged by: Drilling Equipment:	Mid-Valley Water Bank SWO/ARB/SEV
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De	scriptions	Notes
- - - - - - - - - - - - - - - - - - -	5' Continous Tube Sampler	Not Used B	Not Used P	ML SP ML SP ML SP ML SP ML	(0-2') Silt with Sand, light yellowis (2-10') Very fine sand with silt, lig moderately loose, grades to light Very dense from 5 to 6 ft. Loose from 6 to 6.5 ft, mottled lig cemented sand Loose at 9 feet, very fine. (10-12') Silt, light brown and gray moderately oxidized (12-18') Fine to very fine sand, lig loose, some oxidation mottling Dense SP lens at 15.5 ft, 4 in Dense SP lens at 17 ft, 3 in (18-19') Silt, brown (19-20) Fine sand, light gray, mois (20-21.5') Silt, gray-brown, moist, (21.5-24') Fine to medium sand, g (24-26') Silt, gray-green, moist, de (26-36') Silty sand, gray-green, moi Prevalent CaCO3 at 29.5 ft Yellow-brown at 31 ft Reddish-brown at 32.5 ft	ht gray, moist, brown at 4 ft. ght gray/orange, partially , moist, loose, ht gray-yellow, moist, st, loose , dense gray, moist, loose ense oist, dense, cemented	Hard drilling at 28 ft
- - 40				SP	by 38.5 ft, some oxidation (38.5-53.5') Fine sand, gray with p oxidation, moist, dense, prevalen	_	

		E	ST. 1	968			Job No. 2659-20-002 GWB
PR	O'	VС	)ST	-&	Boring Log		Page 2 of 3
PR	IT	Π	IAF	RD	Bornig Log	Date:	November 4/5, 2020
CON	ISUL	TING	GRO	DUP	1-2	Project:	Mid-Valley Water Bank
An En	nployee	e Owne	ed Con	npany		Logged by:	SWO/ARB/SEV
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De	escriptions	Notes
a         -         -         45         - <tr tr="">     &lt;</tr>	5' Continous Tube Sampler Type	Not Used BIo	Not Used PID	SP SM SP ML	Becomes loose at about 40ft Siltier than above, light brown, de Silt decreases at 46.5ft, coarsens trace very coarse sand, CaCO3 an (50-55') Silty Sand, reddish brown loose. (55-60') Sand, poorly graded, wh moist, loose. (60-67') Silt, gray, moist, firm, blc (67'-81') Sand, poorly graded, wh moist, loose.	to medium grained with d trace silt n, fine-grained moist, ite to gray, fine grained, ocky structure	

			ST. 1				Job No. 2659-20-002 GWB
PK	O	V C	)ST	Å	Boring Log	Date:	Page 3 of 3 November 4/5, 2020
PRITCHARD				KD	1-2	Project:	Mid-Valley Water Bank
CONSULTING GROUP An Employee Owned Company					1-2	Logged by:	SWO/ARB/SEV
	ipicyce	, owne		ipany		Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Des	scriptions	Notes
-	ŗ	sed	sed		(80-81') fine to medium-grained.		
- - 85 - - - 90 - - - 95 - - 95 - - - 100	5' Continous Tube Sampler	Not Us	Not Used		(81-88.5') Silt, gray, moist, firm, re (88.5-100') Sand, poorly graded, w grained, moist, loose, red oxidatio	vhite to gray, fine-	
- - - 105 - - - 110 - - - 115 - - - 120					Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Enginee Driller: Allen Bushey/Josh Palmer	ering Group	

		ES	ST. 19	68		Job No. 2659-20-002 GWB
PROVOST&					Boring Log	Page 1 of 3
PR	PRITCHARD			D	2-1 Date	
CON An Em	SULT		14 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		Logged by	
/u/ Em	pioyee	owned	u ooni	ouny	Drilling Equipment	
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descriptions	Notes
- - 5 - - - 10 -	5' Continous Tube Sampler	Not Used	Not Used	SM	(0-4') Fine sand with silt, light yellow-brown, moist, moderately loose. (5-17.5') Fine to medium sand, light yellow-gray, slightly moist, loose, trace pebbles.	
- - 15 - -					(13.5') Fine to very fine sand, slightly gray. (15.5-16') Silt lens.	Hard drilling at 13.5
- 20 - - - 25 - - - 30 - - 30 - - 35 - - 35 - - -				ML SM SP	<ul> <li>(17.5-24') Silt, light gray, moist, moderately dense, oxidation mottles at contact</li> <li>Gray-brown, friable</li> <li>Structureless</li> <li>(24-25') Silty sand, gray-brown, moist, moderate dense</li> <li>(25-29') Medium to coarse sand, trace pebbles, orange, moist, moderately dense.</li> <li>(29-38.5') Silt with fine sand, light brown, moist, dense, CaCO3 mottling</li> <li>(34') No to trace sand??</li> <li>Orange oxidation mottles, friable.</li> </ul>	
40				SP	(38.5-46') Fine to very fine sand, yellow-olive, moist, moderately loose.	

		FS	ST. 19	88			Job No. 2659-20-002 GWB
DR	$\bigcirc$	/0	-		Boring Log		Page 2 of 3
	ITC	ν Δ				Date:	November 4, 2020
					2-1	Project:	Mid-Valley Water Bank
1000		Owned	3- 3 2 1 C - 5			gged by:	SWO/ARB
					Drilling Equ	upment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descriptions		Notes
- - -	Continous Tube Sampler	Not Used	Not Used	SP	Grades to light gray by 41.5'. 6" silt at 41-41.5'.		
45 -	ous Tub				Some oxidation mottling.		
- -				SM	(46-51') Silty sand, orange brown to gray, moist, de	ense.	
- 50 -	5'				CaCO3 mottles prevalent at 49'.		
-				SP	51-54') Fine to medium sand with trace coarse intervals, ray-brown, moist, moderately loose.		
55 -				ML	(54-57') Silt, gray, moist, dense, CaCO3 mottles		
- - - 60 -				SP	Grades to SM/ML by 57', light yellow-gray-brown. (57-62') Fine to very fine sand, gray with yellow-br streaks, moderately loose. Prelavent black oxidation mottling, cross-bedding.		
- - -					(62-69') Light brown-gray, moist, medium dense.		
65 - - -					Silt lens at 65'.		
- 70 - - -	- 59 ML - 60 - 70 - 70 - 70 - 70 - 70 - 70 - 70				(69-76') Silt and very fine sand, light gray, moist, do with orange oxidation mottling, sand contains crossbedding	ense,	
75 - - -				SP	(76-79') Fine to medium sand, light, moist, loose, prevalent oxidation		
80				ML	(79-81') Silt with fine sand, orange oxidation mottl moist, medium dense, prevalent orange & black ox mottling at contact with above		

PR PR	ITC		ST. 19 ST AR	& CD		Boring Log 2-1	 Project:	November 4, 2020	ge 3 of 3
An En	nployee		2010-0010 (0.0019) 2010-0010 (0.0019)		-		Logged by:	SWO/ARB	
							Drilling Equipment:	CME-55 HSA	
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID		Classification	Field Material Desc	riptions	Notes	
- - - 85	Continous Tube Sampler	Not Used	Not Used	MI	L	(81-85') Silt, light gray, moist, mediu oxidation mottles	um dense, orange		
- - -	5' Continous			SP		(85-91') Fine sand, light gray, moist, oxidation mottles	medium loose, orange		
90 -						Turns light brown with trace of silt.			
-				M		(91-92') Silt, light gray, moist, dense, orang			
- - 95 -				SP MI SP	L ML	(92-93') Fine sand, light gray, moist, moderately loose (93-95.5') Silt, light gray, moist, den mottles, bioturbation (95.5-99') Very fine sand with silt, lig moderately dense, grades to SM by	se, orange oxidation ght gray, moist,		
- -						oxidation mottles, oxidation lessens			
100 -				SN	١	(99-100') Silty sand, light gray, moist, n	noderately dense.		
- - 105 - - -						Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engineeri Driller: Allen Bushey/Josh Palmer	ing Group		
- 110									
-									
-									
- 115									
-									
-									
[									
120									

				Job No. 2659-20-002 GWB			
DE			ST. 1	968	Boring Log	5.	Page 1 of 3
PK	(U)	хO	121	Å		Date: Project:	
PR			Ar	<b>KD</b>	2-2	Logged by:	
	nployee					Drilling Equipment:	
Depth, feet	Type of Sampler	Blow Count (bpf)		USCS Field Classification	Field Material De		Notes
- - -	Sampler	Not Used	Not Used PID/FID	ML	(0-2') Sandy Silt, light brown, fine (2-5') Sandy Silt, brown, fine-grain		
- 5 - - 10 - - - -	5' Continous Tube Sampler			SMML	(5-13') Sandy Silt/Silty Sand, gray, soft to firm, red oxidation staining (13-15') Sand, poorly graded, red	, very fine-grained, moist, g.	Lab Result - 10': 14% Sand, 86% Silt/Clay
15 - - 20 - - - -				SP	moist, loose. (15-23.5') Sand, poorly graded, re medium-grained with some occas loose.	sional pea gravel, moist,	
25 - - 30 - - - -				ML	(23.5-34.5') Sandy Silt, reddish br sand, moist, hard, white streaks,		Lab Result - 25'/30': 31% Sand, 69% Silt/Clay
35 - - - 40				ML	(34.5-36.5') Sand, poorly graded, moist, loose. (36.5-38') Silt, gray, moist, firm, r (38-40') Silty Sand, reddish browr loose.	ed oxidation staining.	

		ES	6T. 19	968			Job No. 2659-20-002 GWB
PR	O	/0	ST	Page 2 of 3			
PR	ITC	ΞĤ.	AR	D	Boring Log	Date:	
COM	ISUL	ГING	GRO	UP	2-2	Project:	
An En	nployee	Owned	d Com	pany		Logged by: Drilling Equipment:	
		Ē		-		Drining Equipment.	
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Soil Group	Field Material De		Notes
- - - 45 - - - 50 - - - 55 - - - - 60 - - - - 60 - - - - - - - - -	5' Continous Tube Sampler	Not Used E	Not Used F	SM ML SM ML SP ML SP ML SP	(40-48') Sandy Silt/Silty Sand, gramoist, firm. (48-50') Silt, red to pink in color, vocemented. (50-58.5') Sandy Silt/Silty Sand, regrained, moist, firm. (58.5-61.5') Sand, poorly graded, moist, loose. (61.5'-65') Silt, gray, moist, firm, roblocky and brittle (65'-68') Sand, poorly graded, gragrained, moist, loose. (68-70') Silt, gray, moist, very stiff oxidation staining. (70'-75') Sand, poorly graded, redemoist, loose. (75-84') Sandy Silt/Silty Sand, red grained, moist, firm.	very hard, partially eddish brown, very fine- gray, very fine grained, red oxidation staining, y, fine to medium f, white streaking, red dish brown, fine-grained,	Lab Report - 45': 7% Sand, 93% Silt/Clay Driller indicated very hard drilling at 48'. Paleosol soil hard pan?

		ES	ST. 19	Job No. 2659-20-002 GWB			
PROVOST& Boring Log							Page 3 of 3
PRITCHARD				ñ	Borning Log	Date:	November 5, 2020
	ISUL		GRO		2-2	Project:	Mid-Valley Water Bank
An En	nployee					Logged by:	SEV
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Soil Group	Field Material De	escriptions	Notes
- - - 85 - - - - 90 - - - 95 - - - 95 - - - 100	5' Continous Tube Sampler	Not Used	Not Used PID/FID		(84-90') Sand, poorly graded, red medium-grained, moist, loose (90-98') with some occasional pe (98-100') Sandy Silt, gray, very fir firm, red oxidations staining.	a gravel, moist, loose	
- - - 105 - - - - 110 - - - 115 - - 115 - 120					Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engine Driller: Allen Bushey/Josh Palme		

	O\ IT(	/O CH,	11000	& D	Boring Log 3-1	Date: Project:	Mid-Valley Water Bank
An Em	ployee	Owned	d Com	bany		Logged by: Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Des	scriptions	Notes
- - - - 5 - - - - - - - - - - - - - - -	5' Continous Tube Sampler	Not Used	Not Used	ML SP SM SP	(0-2') Silty Sand/Sandy Silt, light br dry, loose. (2-4') Moist. (4-8') Sandy Silt, light gray, very fir red oxidation staining, blocky strue (8-17') Sand, poorly graded, reddis grained, moist, loose. (17-20') Silty Sand, reddish brown, loose. (20-44') Sand, poorly graded, redd grained, moist, loose.	ne-grained, moist, firm, cture sh brown, very fine-	Farmer indicated soil has been deep ripped to 6' due to hard pan.

			б <b>Т.</b> 18			Job No. 2659-20-002 GWB
PR	O	O	ST	Page 2 of 3 : November 3, 2020		
PR	PKIICHAKD				Boring Log Date 3-1 Project	
	ployee				Logged by	
					Drilling Equipment	
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descriptions	Notes
- - - 45 - - - 50 - - - 55 - - - - 60 - - - - - - 60 - - - - - 60 - - - -	5' Continous Tube Sampler	Not Used BI	Not Used PI	SP ML SM	(44-47') Sandy Silt, gray, very fine-grained sands, moist, firm, red oxidation staining. (47-48') Sandy Silt, gray to reddish brown, very fine- grained, white streaking, partially cemented. (48-58.5') Silty Sand, reddish brown, fine-grained, moist, medium dense. (58.5-71') Sand, poorly graded, gray to reddish brown, medium to coarse-grained with occasional pea size gravel.	Lab Report - 45': 46% Sand, 54% Silt/Clay Possible paleosol hard pan? Driller indicated drilling became very hard at 47'.
- 70 - - 75 - - - - 80				ML SP	(71-75') Silt, gray, moist, firm, red oxidation staining. (75-84') Sand, poorly graded, gray, fine to medium- grained, moist, loose, red oxidation staining.	

PR	O		ST. 18	Boring Log	Date:	Job No. 2659-20 November 3, 2	Page 3 of 3	
					3-1	Project:		
	nployee	1.	1111			Logged by:		
						Drilling Equipment:	CME-55 HS	A
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descripti	ions	Notes	
- - - 85 - - - - 90 - - - 95 - - 95 - - - 100	5' Continous Tube Sampler	Not Used	Not Used	SP	(84-90') Sandy Silt, gray, very fine-grain firm, red oxidation staining. (90-95') Sand, poorly graded, white to g moist, loose, red oxidation staining. (95-100') Silt, gray, moist, firm, red oxid	gray, fine-grained,		
- - - 105 - - - - 110 - - - 115 - - - 120					Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engineering ( Driller: Allen Bushey/Josh Palmer	Group		

		ES	it. 19	Job No. 2659-20-002 GWB			
PR	O\	O'	ST	&	Boring Log		Page 1 of 3
PR	ITC	H	AR	D	Bornig Log	Date:	November 2&3, 2020
CON	SULT	ING	GRO	UP	3-2	Project:	Mid-Valley Water Bank
An Em	ployee	Ownec	d Comp	bany		Logged by:	SEV
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De		Notes
-	L	sed	sed	SM	(0-1.5') Silty Sand, light brown, ve	ery fine-grained, dry,	
- - 5 -	Continous Tube Sampler	Not Used	Not Used	SM	loose. (1.5-8') Silty Sand, reddish brown dense.	n, very fine-grained, moist,	Farmer indicated soil has been deep ripped to 6' due to hard pan.
- - 10 - -	5' Cont				(8-11') Sand, poorly graded, whit grained, moist, loose. (11-15') Silt with some clay, gray,		
- 15 - - - 20				ML	(15-17.5') Sand, poorly graded, d grained, moist, loose. (17.5-20') Silt, gray, moist, loose, oxidation staining	blocky structure, red	
- - - 25 - - - -					(20-25') Silty Sand, reddish brown moist, loose. (25-38') Sand, poorly graded, red moist, loose.		
30 - - - 35 - -					(33-35') very red.		
- - 40					(38-40') Sandy Silt, gray, very fine stiff.	e-grained sand, moist,	

		ES	ST. 19	68			Job No. 2659-20-002 GWB
PR	O	O	ST	&	Boring Log		Page 2 of 3
PR	ITC	CH	AR	D		Date:	November 2&3, 2020
CON	ISUL	ring	GRO	UP	3-2	Project:	
An Err	nployee	Owned	d Com	oany		Logged by: Drilling Equipment:	SEV CME-55 HSA
	۲.	Ē				Drining Equipment.	
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De		Notes
-	L	lsed	Ised	SP	(40-43') Sand, poorly graded, gra	y, very fine-grained,	
-	nple	Not Used	Not Used		dense, moist.		
_	s Sar	Z	_	SMMI	(43-47') Sandy Silt/Silty Sand, red	ldish brown moist hard	Lab Report: 80% Sand, 17%
45 - -	Continous Tube Sampler				brittle, partially cemented, white		Silt/Clay. Driller indicated hard drilling at 43-45'. Has hard pan appearance. Paleosol?
-	5' Cont				(47-48.5') Silty Sand, reddish brov moist, medium dense.	wn, very fine-grained,	
50				SP	(48.5-64') Sand, poorly graded, redc	dish brown, fine-grained,	
- - - 55 - - - - 60 -					(59-60') coarse-grained.	asin brown, nine grained,	
- - -							Driller indicated harder drilling at 63'.
65 - -				SP	(64-65') Silt, gray, moist, dense, r (65-65.5') Sand, poorly graded, gr moist, loose, red oxidation stainir	ray, very fine-grained,	
-					(65.5-69') Sandy Silt, reddish brov		
- 70				SP	moist, medium dense, red oxidat	-	
-				55	(69-70.5') Sand, poorly graded, re grained, moist, loose.	eduish brown, nne-	
-				ML	(70.5-76') Silt, gray, moist, firm, r	ed oxidation staining.	
-							
- 75 -							
- - - 80				SMML	(76-80') Silty Sand/Sandy Silt, gra moist, firm, red oxidations stainir		

		ES	ST. 19	Job No. 2659-20-002 GWB			
PR	O	O	ST	Page 3 of 3			
PR	ITC	CH.	AR	D	Boring Log	Date:	
CON	and the second sec	ring	GRO	UP	3-2	Project: Logged by:	
An En	nployee	Owned	d Com	oany		Drilling Equipment:	
	5	f)				Diming Equipment	
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Desc		Notes
- - 85 - - - - - - 90 - - - 95 - - - -	5' Continous Tube Sampler	Not Used	Not Used		(80-89') Silt, gray with white streaki portions appear partially cemented (89-92') Silty Sand/Sandy Silt, gray, moist to wet, firm, wet from 91-92'. (92-100') Sand, poorly graded, gray, moist, loose, red oxidation staining,	very fine-grained sand, very fine-grained, wet from 97 to 98'.	Apparent groundwater percolation barrior.
- 100 - - - 105 - - - - - - 110					(98-100') medium to coarse grained Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engineeri Driller: Allen Bushey/Josh Palmer		
- - - 115 - - - - 120							

		ES	ST. 19	Job No. 2659-20-002 GWB			
PR	O	O	ST	&	Boring Log		Page 1 of 3
PR	ITC	CH.	AR	D		Date:	
CON	ISUL	ING	GRO	UP	4-1	Project:	
An En	nployee	Owned	d Com	oany		Logged by:	
					Γ	Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De	-	Notes
- - - 5	Continous Tube Sampler	Not Used	Not Used	ML	(0-4.5') Silty Sand, reddish brown loose. (4.5-5') Silt, gray to brown, moist		
- - - 10 - -	5' Continous			SP	(5-15') Sand, poorly graded, gray moist, loose.	to red, fine-grained,	
- 15 - - - 20 - - -					(15-19') Sandy Silt, reddish brown (19-27') Sand, poorly graded, red moist, loose.		
- 25 - - - 30 - - 35 - - 35 - - 40					(27-37.5') Sandy Silt/Silty Sand, ro grained, moist, firm, occassional sands, very fine-grained, up to a thickness. (37.5-42') Sand, poorly graded, w moist, loose.	beds of poorly graded several inches in	Lab Report: 57% Sand, 43% Silt/Clay.

		ES	ST. 19	68		Job No. 2659-20-002 GWB
PR	O	/O	ST	&	Boring Log	Page 2 of 3
PR	ITC	ĨĤ	ĂŔ	Ď	Date.	
CON	ISUL	ring	GRO	UP	4-1 Project:	Mid-Valley Water Bank
An En	nployee	Owned	d Com	bany	Logged by: Drilling Equipment:	SEV CME-55 HSA
		(j				CML-35 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descriptions	Notes
-	5	lsed	lsed			
- - 45	Lube Sample	Not Used	Not Used	ML	(42-45') Silt, gray, moist, stiff, red oxidation staining and white streaking.	
45 - - 50 - - - 55 - - - - 60 - - - - 65 - - - - -	5' Continous Tube Sampler			SP	(45-60') Sandy Silt/Silty Sand, gray to reddish brown, very fine-grained, moist, stiff, red oxidation staining. (60-64') Sand, poorly graded, gray, fine grained, moist, loose, red oxidation staining, damp to wet at 63'. (64-67.5') Sandy Silt, dark brown, very fine-grained, moist, firm.	Lab Report: 19% Sand, 81% Silt/Clay.
- 70 - - -				SM	(67.5-68.5') Sandy Silt, dark brown, very fine-grained, moist, very hard, red oxidation staining, white streaking, hard pan? (68.5-73') Silty Sand, dark brown, fine-grained, moist, medium dense. (73-85') Sand, poorly graded, reddish brown, fine to	
- - - - 80				Jr	medium-grained, moist, loose.	

		ES	ST. 19	68			Job No. 2659-20-002 GWB
PR	$\bigcirc$		ST		<b>Dering</b> Leg		Page 3 of 3
	UT (	<u>'</u>			Boring Log	Date:	December 3, 2020
PK			AK		4-1	Project:	
and the second	ISUL <sup>1</sup> nployee					Logged by:	
7 UT 271	ipicy cc	onnoc	2 00111	ouny		Drilling Equipment:	CME-55 HSA
et	ampler	ınt (bpf)		d tion			Notes
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Des	criptions	Notes
- - 85 - - - - 90 - - - 95 - -	5' Continous Tube Sampler	Not Used	Not Used	SP	(85-95') Sand, poorly graded, reddi medium-grained, wet, very loose. Bottom of boring: 95' due to heavin Hole backfilled with cuttings.		Driller indicates drilling becomes very soft.
- - 100 - - - - 105 - - - 110 - - 110 - - 115 - - 115 - 120					Hole backfilled with cuttings. Drilling Contractor: Salem Engineer Driller: Allen Bushey/Josh Palmer	ring Group	

			ST. 19	Job No. 2659-20-002 GWB			
PR	O	O	ST	&	Boring Log		Page 1 of 3
PR		CH.	AR	D		Date:	
and the second	ISUL				4-2	_ Project:	Mid-Valley Water Bank
An En	nployee	Owned	d Com	oany		Logged by:	SEV
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De		Notes
-         -         -         -         -         -         10         -         -         10         -         -         20         -         -         20         -         -         20         -         -         300         -         -         300         -         -         300         -         -         300         -         -         300         -         -         300         -         -         300         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -         -	5' Continous Tube Sampler	Not Used E	Not Used	ML ML SMML	(0-3') Sandy Silt, reddish brown, soft. (3-5') Sandy Silt, reddish brown, shard, white streaking. (5-15') Silt, gray, moist, firm, red (15-20') Sandy Silt/Silty Sand, red fine-grained, moist, firm. (20-35') Sand, poorly graded, wh moist, loose. (35-40') Silt, reddish brown, mois	very fined grained, very oxidation staining. ddish brown to gray, very ite to gray, fine-grained,	Lab Report - 15': 50% Sand, 50% Silt/Clay.

		ES	ST. 19	Job No. 2659-20-002 GWB			
PR	O	/O	ST	&	Boring Log		Page 2 of 3
PR	ITC	Ή	ĂR	Ď		Date:	
CON	ISUL	ring	GRO	UP	4-2	Project:	Mid-Valley Water Bank
An Err	ployee	Owned	d Com	pany		Logged by: Drilling Equipment:	SEV CME-55 HSA
		6					
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De		Notes
-	L.	Jsed	Jsed	SMM	(40-50') Sandy Silt/Silty Sand, dar		Lab Report - 40'/45': 47% Sand,
- - 45 - - - 50 -	5' Continous Tube Sampler	Not Used	Not Used	ML	grained, moist, firm, some white (50-58') Silt, gray, moist, firm, red		53% Silt/Clay.
- - 55 - - -				SP	streaking. (58-59.5') Sand, poorly graded, g	ray to light brown, moist,	
60 - - - 65 - -				ML	loose (59.5-61') Silt, gray, moist, firm (61-69') Sandy Silt/Silty Sand, gra moist, firm.	n, red oxidation staining.	Driller indicates hard drilling at 67'.
-							
- 70 - - -				SM SP	(69-70') Silty Sand, reddish brown grained, moist, dense. (70-75') Sand, poorly graded, fine		
75 - - -				SP	(75-78.5') Sand, poorly graded, v loose.	ery fine-grained, moist,	
- 80				ML	(78.5-80') Silt, gray, moist, firm, r	ed oxidation staining.	

		ES	ST. 19	68		Job No. 2659-20-002 GWB
PR	0				Boring Log	Page 3 of 3
	ITC	́ЧЧ		n n	Date.	
	ISUL"				4-2 Project:	Mid-Valley Water Bank
	nployee		11		Logged by:	SEV
					Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descriptions	Notes
<u>-</u> - - - - - - - - - - - - - - - - - -	5' Continous Tube Sampler	Not Used BI	Not Used PID/FID	ML	(80-85') Silt, gray to reddish brown, moist, firm. (88-92.5') Heavily oxidized. Sand, poorly graded, reddish brown, fine to medium-grained, loose, moist. Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engineering Group Driller: Allen Bushey/Josh Palmer	
- 120						

	EST. 1968						Job No. 2659-20-002 GWB
PROVOST&				&	Boring Log		Page 1 of 3
PR	ITC	CH	AR	D		Date:	
CONSULTING GROUP				UP	5-1	Project:	Mid-Valley Water Bank
An Employee Owned Company						Logged by:	SEV
Drilling Equipme							CME-55 HSA
Depth, feet	Type of Sampler				Notes		
- - - - - - - - - - - - - - - - - - -	5' Continous Tube Sampler	Not Used B		SMML SM SP SM ML SP	(0-2') Silty Sand/Sandy Silt, light b dry, loose/soft. (2-9') soil is moist (9-13.5') Silty Sand, reddish brow loose, red oxidation staining. (13.5-21') Sand, poorly graded, w grained, moist, loose, red oxidatio (21-22') Silty Sand, reddish browr (22-23') Silt, gray, moist, firm, red (23-41') Sand, poorly graded, whi grained, moist, loose, red oxidatio	n, fine-grained, moist, hite to light gray, fine- on staining. h, very fine-grained, l oxidation staining. te to light gray, fine-	Lab Report - 5': 31% Sand, 69% Silt/Clay.
							around 40'

		ES	ST. 19	888	Job No. 2659-20-002 GWB					
PR	O\	/O	ST	&	Boring Log		Page 2 of 3			
PR	ITC	CH	AR	D		Date:	November 2, 2020			
CON	ISUL	TING	GRO	UP	5-1	Project:	Mid-Valley Water Bank SEV			
An Err	nployee	Owned	d Com	pany		Logged by: Drilling Equipment:	CME-55 HSA			
		£.				Drining Equipment.	CML-35 HSA			
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De	Field Material Descriptions				
<b>Jag</b>	5' Continous Tube Sampler	Not Used Blo	t Used	ML SMML SP CL SP SMML SP	<ul> <li>(41-41.5') Sandy Silt, grayish brow blocky structure</li> <li>(41.5-45') Silty Sand/Sandy Silt, g fine-grained, moist, dense/stiff.</li> <li>(45-47.5') Sand, poorly graded, regrained, moist, loose.</li> <li>(47.5-53') Silty Clay, gray, moist, l staining, blocky structure.</li> <li>(53-55') Sand, poorly graded, whi grained, moist, loose.</li> <li>(53-55') Sand, poorly graded, whi grained, moist, loose.</li> <li>(55-58') Silty Sand/Sandy Silt, gra grained, moist, dense/stiff.</li> <li>(58-59') Sand, poorly graded, gra moist, loose.</li> <li>(59-65') Silty Sand/Sandy Silt, gra moist, dense/stiff.</li> <li>(65-72') Silt/Clay, gray, moist, har</li> </ul>	rayish brown, very fine to eddish/brown, fine- hard, red oxidation ite to light gray, fine- y, very fine to fine- y/brown, fine-grained, y, very fine-grained,				
- - 75 - - -				SP	(72-79') Sand, poorly graded, red moist, loose.	dish brown, fine-grained,				
80				ML	(79-88') Sandy Silt, gray, moist, h	ard				

PR PR CON		/O CH ting	ST ST AR GRO	& D	Boring Log 5-1	Date: Project: Logged by: Drilling Equipment:	Mid-Valley Water Bank       x:     SEV
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descript	ions	Notes
- - - 85 - - - - 90 - - - - 95 - - - 100 - - - 100	5' Continous Tube Sampler	Not Used	Not Used	CL SP	(88-92') Clay, gray, moist, hard, blocky s (92-95') Sand, poorly graded, gray, fine loose. (95-98.5') Clay, gray, moist, hard, red of blocky structure. (98.5-100') Sand, poorly graded, reddis <u>grained, moist, loose.</u> Bottom of boring: 100' Hole backfilled with cuttings.	-grained, moist, xidation staining,	
- 105 - - - 110 - - - 115 - - - 120					Drilling Contractor: Salem Engineering ( Driller: Allen Bushey/Josh Palmer	Group	

		ES	ST. 19	68			Job No. 2659-20-002 GWB
PR	O	O	ST	&	Boring Log		Page 1 of 3
PR	IT(	H	AR	D	Bornig Log	Date:	November 17, 2020
CON	SULT	ING	GRO	UP	5-2	Project:	Mid-Valley Water Bank
An Em	ployee	Owned	d Comp	bany		Logged by:	SEV
				Drilling Equipment:	CME-55 HSA		
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Desc	Notes	
-	<u> </u>	Not Used	Not Used	ML	(0-1.5') Sandy Silt, light brown, very loose.	fine-grained sand, dry,	
- 5 - -	' Continous Tube Sampler	2	2		(1.5-5') Sandy Silt, light brown, very moist, loose. (5-10') Silt, tan to gray, moist, firm	fine-grained sand,	
- 10 - - 15 - - - 20 - - - 20 - - - - 30 - - - 30 - - - 30 - - - 33 - - - 35 -	5'			ML SP	(10-11.5') Sand, poorly graded, rede grained, moist, loose. (11.5-12.5') Silt, reddish brown, ver firm. (12.5-15') Sand, poorly graded, rede grained, moist, loose. (15-34') Sand, poorly graded, reddis medium-grained, moist, loose. (34-42') Silt, gray, moist, firm, red o	y fine-grained, moist, dish brown, fine- sh brown, fine to	
- - - 40							

		ES	6T. 19	68		Job No. 2659-20-002 GWB	
PR	O	/O	ST	&	Boring Log		Page 2 of 3
PR	ĬТĊ	Ή	ĂR	ñ	Bornig Log	Date:	November 17, 2020
CON	SUL	ring	GRO	UP	5-2	Project:	Mid-Valley Water Bank
An Em	ployee	Owned	d Comp	bany		Logged by:	SEV
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Des	criptions	Notes
-	Ľ	Not Used	Not Used				
-	5' Continous Tube Sampler	ot U	ot U			<b>6</b>	
-	San	ž	ž		(42-43') Sand, poorly graded, gray,		
- 45	adu				grained, moist, loose, red oxidation		
4J -	IS TI				(43-49.5') Silty Sand, dark brown, f medium dense.	ine-graineu, moist,	
_	nor				mediam dense.		
-	onti						
-	C 2						
50	-			ML	(49.5-50') Silt, gray, moist, stiff, red	d oxidation staining.	
-				SM	(50-55') Silty Sand, reddish brown,	fine-grained, moist,	
-					medium dense.		
-							
-							
55							
-				SMML	(55-65') Sandy Silt/Silty Sand, gray,		
-					moist, firm, red oxidation staining.		
-							
- 60							Lab Report - 60'/65': 29% Sand,
-							71% Silt/Clay.
-							
-							
-							
65							
-				SP	(65-75') Sand, poorly graded, gray	to reddish brown, fine	
-					to medium-grained, moist, loose.		
-							
-							
70							
_							
_							
75							
-				SMML	(75-85') Sandy Silt/Silty Sand, gray	to brown, very fine-	
-					grained, moist, firm.	-	
-							
-							
80							

PR PR CON		/O CH,	and a second second	& D ⊔₽	Boring Log 5-2	Date: Project: Logged by: Drilling Equipment:	Job No. 2659-20-002 GWB Page 3 of 3 November 17, 2020 Mid-Valley Water Bank SEV CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descri	Notes	
- - - 85 - - - - 90 - - - - 95 - - - - 100	5' Continous Tube Sampler	Not Used	Not Used	ML	(85-87') Sand, poorly graded, gray, fi loose. (87-90') Sandy Silt/Silty Sand, gray to grained, moist, firm. (90-100') Sand, poorly graded, gray, grained, moist, loose.	o brown, very fine-	
- - - 105 - - - - 110 - - - 115 - - - 120					Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engineerin Driller: Allen Bushey/Josh Palmer	ng Group	

PR	0\		эт. 19 ST	бв &	Job No. 2659-20-002 GWB Page 1 of 3						
PR	IT(	CH.	AR	D	Boring Log	Date:	November 17, 2020				
and the second	ISUL		and the second second second		A-1	Project: _ Logged by:	Mid-Valley Water Bank SEV				
An En	ployee	Owned	i Comp	Jany		Drilling Equipment:	CME-55 HSA				
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material De	Notes					
-	er	Jsed	Jsed	SM	(0-1.5') Silty Sand, light brown, fin	e-grained, dry, loose.					
- - 5	Continous Tube Sampler	Not Used	Not Used	SM		(0-1.5') Silty Sand, light brown, fine-grained, dry, loose. (1.5-5') Silty Sand, reddish brown, moist, loose.					
-	tinous <sup>-</sup>			ML	(5-7') Silt, gray, moist, firm, red o>	kidation staining.					
- - 10	5' Cont			SP	(7-10') Sand, poorly graded, gray, moist, loose.						
- - - 15 -				ML	(10-17') Silt, gray, moist, firm, red	oxidation staining.					
- - 20 -				SP	(17-21.5') Sand, poorly graded, gr loose.	ay, fine-grained, moist,					
- -				ML	(21.5-24') Silt, dark gray, moist, fir staining.	rm, red oxidation					
25 - - -				SP	(24-35') Sand, poorly graded, redo moist, loose.	dish brown, fine-grained,					
30 - - - -											
35 - - - 40				ML	(35-40') Sandy Silt, reddish brown moist, firm.	n, very fine-grained,					

		ES	ST. 19	968			Job No. 2659-20-002 GWB
PR	O	/O	ST	&	Boring Log		Page 2 of 3
PR	ITC	Ή	ĂŔ	Ď		Date:	November 17, 2020
CON	ISULT	ring	GRO	UP	A-1	Project:	Mid-Valley Water Bank
An Em	ployee	Owned	d Com	pany		Logged by:	SEV
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	Notes			
-	<u>ب</u>	sed	sed	SM ML	(40-54') Sandy Silt/Silty Sand, gray	, very fine-grained,	
- - 45 - - 50 - - 55 - - - - - -	5' Continous Tube Sampler	Not Used	Not Used		moist, medium dense. (54-59') Sandy Silt, blue/gray, fine dense.		
60 - - -				MI CL	(59-63.5') Clay/Silt, blue/gray, moi	ist, stiff.	
65 -					(63.5-65') Sand, poorly graded, blu grained, moist, dense.	ue/gray, fine to medium-	
- - 70 - - - 75 - - - 80				ML	(65-70') Sandy Silt, blue/gray, very firm. (70-85') Silt, blue/gray, moist, stiff		

PR	$\bigcirc$		<sup>вт. 1</sup> ≘ ST		Boring Log		Job No. 2659-20-002 GWB Page 3 of 3
PR	ITC	ĹΗ	ĂŔ	Ď		Date:	November 17, 2020
	ISUL				A-1	Project: _ Logged by:	Mid-Valley Water Bank SEV
An En	nployee	Owned	d Com	bany		Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descrip	Notes	
- - - 85 - - - 90 - - -	5' Continous Tube Sampler	Not Used	Not Used	ML CL	(85-95') Clay/Silt, blue/gray, lean, moi	st, stiff.	
- 95 - - - - 100				SMMI	(95-100') Sandy Silt/Silty Sand, gray/b grained, moist, firm.	lue, very fine-	
- - - 105 - - - - 110 - - - 115 - - 115 - 120					Bottom of boring: 100' Hole backfilled with cuttings. Drilling Contractor: Salem Engineering Driller: Allen Bushey/Josh Palmer	Group	

		ES	ST. 19	968			Job No. 2659-20-002 GWB		
PR	O	<u>(O</u>	<b>ST</b>	&	Boring Log	<b>.</b> .	Page 1 of 3		
PR		_H	AK	D		Date:			
a the second second	SULTING GROUP     A-2     Project       ployee Owned Company     Logged by				Project:				
An Em	pioyee	Owned	Com	pany		Drilling Equipment:	-		
		_				Drining Equipment.			
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descrip	Field Material Descriptions			
- - -	Sampler	Not Used	Not Used	SM	(0-4') Silty Sand, light brown, fine-grai	Annoars to be bard non layer at			
5 - -	Continous Tube Sampler			ML	(4-8') Silt, gray to red, stiff		Appears to be hard pan layer at 4.5'.		
- - 10 - - -	5' Con			ML CL	(8-9') Sand, poorly graded, reddish bro moist, loose. (9-12') Silt/Clay, gray, moist, stiff, red (12-15') Sand, poorly graded, gray, fin	oxidation staining.			
- 15 - - -					grained, moist, loose. (15-17.5') Sandy Silt, reddish brown, v moist, firm.				
- 20 -				SP ML	(17.5-18.5') Sand, poorly graded, gray	-			
- - 25 - - - 30					(18.5-30') Sandy Silt, reddish brown, v moist, firm, red oxidation staining.				
- - -				SP	(30-34') Sand, poorly graded, gray, fin loose.	e-grained, moist,			
35 - - -				ML	(34-38') Sandy Silt, reddish brown, ver moist, firm, red oxidation staining.	ry fine grained,			
- 40					(38-45') Sand, poorly graded, gray, fin loose.	e-grained, moist,			

PR	O		ST. 19	бв &	Boring Log	Date:	Job No. <u>2659-20-002 GWB</u> Page 2 of 3 November 18, 2020
PR			AK	D	A-2	Project:	
An Em	ployee	and the second	GRO d Com	20 - 10 Au		Logged by:	
						Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Des	criptions	Notes
- - - 45 - - - - 50 - - - - 55 - - - - 60 - - - - - - - - - - - 70 - - - - 70 - - - -	5' Continous Tube Sampler	Not Used		ML SMSC SP	(45-50') Sandy Silt, gray, very fine- occasional interbedded sand layer thickness. (50-55') Sandy Silt, gray/green, ver (55-60') Silty Sand/Clayey Sand, bl (60-67') Sand, poorly graded, gray, moist. (67-90') Silty Sand/Sandy Silt, gray moist, firm. Occasional interbedde 3 to 4 inches in thickness.	s a few inches in ry fine-grained, moist. ue/gray, moist, firm. /blue, fine-grained,	Driller indicates hard drilling around 70'.

PR	$\bigcirc$		эт. 19 ST		Dering Log	Job No. 2659-20-002 GWB Page 3 of 3
PR	ITC	ĽΗ	ĂŔ	Ď	Boring Log Date:	November 18, 2020
	ISULT	de la complete de la	11 Mar 2013	er 4 é	A-2 Project:	Mid-Valley Water Bank SEV
An Em	ployee	Owned	a Com	bany	Logged by: Drilling Equipment:	CME-55 HSA
Depth, feet	Type of Sampler	Not Used Blow Count (bpf)	PID/FID	USCS Field Classification	Field Material Descriptions	Notes
- - - 85 - - - - 90 - - - - - - - 100 - - - 100 - - - 100 - - - 100 - - - 100 - - - 100 - - - 100 - - - -	5' Continous Tube Sampler	Not Used	Not Used PID/FID		Drilling stopped at 90' due to hard drilling and equipment conerns. Bottom of boring: 90' Hole backfilled with cuttings. Drilling Contractor: Salem Engineering Group Driller: Allen Bushey/Josh Palmer	

Boring 1-1	Total Score										
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'							
SP & SM Combined	95%	83%	77%	64%							
Ranking Points (%SP/SM)	2	2	2	3	9						
Boring 1-2	Boring 1-2										
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'							
SP & SM Combined	80%	75%	78%	75%							
Ranking Points (%SP/SM)	3	4	1	1	9						

Boring 2-1					Total Score
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	100%	88%	68%	61%	
Ranking Points (%SP/SM)	1	1	5	5	12
Boring 2-2					<b>Total Score</b>
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
Soil Type SP & SM Combined	Upper 10' 0%	Upper 20' 35%	Upper 50' 29%	Upper 100' 40%	

Boring 3-1					Total Score
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	20%	60%	76%	74%	
Ranking Points (%SP/SM)	5	6	3	2	16
Boring 3-2					<b>Total Score</b>
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
CD 9 CNA Comphined	100%	68%	75%	62%	
SP & SM Combined	10070	0070		• = / •	


Boring 4-1					Total Score
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	95%	78%	54%	60%	
Ranking Points (%SP/SM)	2	3	8	6	19
Boring 4-2					Total Score
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	0%	0%	30%	31%	
Ranking Points (%SP/SM)	7	10	11	10	38

Boring 5-1					<b>Total Score</b>
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	10%	56%	67%	49%	
Ranking Points (%SP/SM)	6	7	6	8	27

Boring 5-2					<b>Total Score</b>
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	0%	45%	61%	58%	
Ranking Points (%SP/SM)	7	9	7	7	30

Boring A-1					Total Score
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	80%	55%	47%	25%	
Ranking Points (%SP/SM)	3	8	9	12	32
Notes from log:					
Boring A-2					Total Score
Soil Type	Upper 10'	Upper 20'	Upper 50'	Upper 100'	
SP & SM Combined	50%	45%	40%	30%	
Ranking Points (%SP/SM)	4	9	10	11	34

Appendix B2: Soil Boring Lab Reports



3/4 men	100.070
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.8%
#16	97.2%
#30	86.1%
#50	64.3%
#100	43.9%
#200	29.8%


		Coefficient	S	
85=		<b>D</b> 60=		D50=
<b>D</b> 30=		<b>D</b> 15=		<b>D</b> 10=
C <sub>u</sub> =	N/A	$C_c =$	N/A	

Silty Sand (SM)

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914

Boring: 1-1 @ 50'





USCS CLASSIFICATION

C<sub>c</sub>=

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914 Boring: 2-2 @ 10'

 $C_u =$ 

N/A

#30

#50

#100

#200

96.0%


92.0%

88.8%

85.8%



N/A




Sieve Size	Percent Passing	
3/4 inch	100.0%	
1/2 inch	100.0%	
3/8 inch	100.0%	
#4	100.0%	
#8	100.0%	
#16	96.2%	
#30	90.2%	
#50	86.4%	
#100	81.4%	
#200	68.7%	

PL=		LL=		PI=
		~ ~ ~ ~ ~		
		Coefficient	S	
D85=		D60=		D50=
D30=		<b>D</b> 15=		<b>D10</b> =
C <sub>u</sub> =	N/A	$C_c =$	N/A	

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914 Boring: 2-2 @ 25' / 30'





USCS CLASSIFICATION

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914

#100


#200

96.8%

92.8%

Boring: 2-2 @ 45'






Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	100.0%
#16	99.8%
#30	94.9%
#50	81.5%
#100	66.0%
#200	53.8%

DI	Atterberg Lin	nits	DI
PL=	LL=		PI=
	Coefficient	s	
<b>D</b> 85=	D60=		<b>D</b> 50=
D30=	<b>D</b> 15=		<b>D</b> 10=
$C_{u}=$			

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914 Boring: 3-1 @ 45'





Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	99.2%
#4	97.2%
#8	94.4%
#16	81.6%
#30	64.5%
#50	46.2%
#100	28.1%
#200	16.7%


PL=		LL=		PI=			
		Coefficient	s				
D85=		D60=		D50=			
D30=		D15=					
C <sub>u</sub> =	N/A	$C_c =$	N/A				
u		S CLASSIFIC					

Silty Sand (SM)

**Project Name: 2659 Mid Valley Waterbank** Project Number: 1-120-0914

Boring: 3-2 @ 45'





Silty Sand (SM) Project Name: 2659 Mid Valley Waterbank

**D**85=

D30=

 $C_u =$ 

N/A

Project Number: 1-120-0914

#16

#30

#50

#100

#200

96.7%

90.3%

76.0%

58.3%

42.6%

Boring: 4-1 @ 30' / 35'



N/A

D50=


**D**10=

D60=

D15=

USCS CLASSIFICATION

C<sub>c</sub>=



Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	100.0%
#16	98.8%
#30	96.0%
#50	91.8%
#100	87.0%
#200	81.1%


PL=		LL=		PI=
		Coefficient	S	
D85=		<b>D</b> 60=		D50=
D30=		D15=		<b>D</b> 10=
C <sub>u</sub> =	N/A	$C_c =$	N/A	

USCS CLASSIFICATION

**Project Name: 2659 Mid Valley Waterbank** Project Number: 1-120-0914

Boring: 4-1 @ 55'





3/4 inch	100.0%	
1/2 inch	100.0%	
3/8 inch	100.0%	
#4	100.0%	
#8	100.0%	
#16	94.6%	
#30	83.5%	
#50	72.2%	
#100	61.9%	
#200	50.4%	


PL=		LL=		PI=
		Coefficient	S	
D85=		<b>D</b> 60=		<b>D</b> 50=
D30=		D15=		D10=
C <sub>u</sub> =	N/A	$C_c =$	N/A	

USCS CLASSIFICATION

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914

Boring: 4-2 @ 15'





Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.6%
#16	95.5%
#30	86.1%
#50	75.6%
#100	63.1%
#200	53.0%


		Atterberg Lin	nits			
PL=		LL=		PI=		
		Coefficient	s			
			~			
D85=		D60=		D50=		
D30=		D15=		<b>D10</b> =		
C <sub>u</sub> =	N/A	$C_c =$	N/A			

Project Name: 2659 Mid Valley Waterbank

Project Number: 1-120-0914

Boring: 4-2 @ 40' / 45'





USCS CLASSIFICATION

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914

#50

#100

#200


89.5%

80.1%

68.7%

Boring: 5-1 @ 5'





Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	100.0%
#16	99.7%
#30	98.5%
#50	93.5%
#100	85.1%
#200	71.5%

PL=	LL=		PI=
	 Coefficient	s	
D85=	D60=		D50=
D30=	D15=		<b>D</b> 10=
C <sub>u</sub> =	$C_c =$	N/A	

USCS CLASSIFICATION

Project Name: 2659 Mid Valley Waterbank Project Number: 1-120-0914

Boring: 5-2 @ 60' / 65'



# Appendix C – Historical Mendota Pool Diversion Data

#### Attachment 1- San Joaquin River Total Mendota Pool Diversions San Joaquin River

(acre-feet)													
Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
1980	4,154	32,027	52,097	92,021	110,654	132,740	155,339	150,912	92,470	67,661	33,314	2,071	925,460
1981	15,246	44,632	36,832	84,536	122,150	151,208	171,236	142,355	85,673	60,360	9,482	173	923,883
1982	9,723	49,197	40,404	42,598	148,464	146,415	162,565	162,741	92,935	73,782	11,634	1,354	941,812
1983	1,671	14,625	12,507	56,515	112,950	149,842	156,957	152,231	94,552	67,009	9,244	266	828,369
1984	11,307	52,988	63,384	82,235	130,613	147,056	166,837	149,336	83,482	73,245	4,422	0	964,905
1985	5,563	51,074	86,739	73,527	102,098	129,317	140,783	118,407	79,180	42,568	8,029	0	837,285
1986	7,293	15,499	31,282	76,875	110,578	144,416	153,480	127,397	64,867	62,861	34,117	876	829,541
1987	12,533	39,460	48,944	76,525	97,819	126,413	136,095	120,001	66,378	61,267	18,272	93	803,800
1988	10,029	58,374	54,554	47,056	85,631	122,949	148,685	132,129	65,733	37,612	9,199	5,892	777,843
1989	10,581	43,448	61,888	69,139	92,704	122,193	134,646	119,723	78,596	42,744	28,022	10,215	813,899
1990	8,990	45,638	57,935	54,076	62,349	117,192	161,540	140,044	70,021	87,756	19,839	449	825,829
1991	14,727	49,824	41,316	30,991	52,907	98,291	119,406	105,057	51,944	63,443	41,697	5,148	674,751
1992	4,531	20,337	56,332	41,878	61,311	98,648	109,771	88,500	39,606	69,878	24,961	6,233	621,986
1993	811	13,116	52,645	51,172	85,012	112,204	131,124	129,169	80,834	67,020	38,150	25,956	787,213
1994	10,014	51,131	65,590	44,124	44,488	105,519	127,856	91,270	15,894	55,558	12,854	9,064	633,362
1995	2,596	54,249	26,012	45,366	64,692	121,272	158,770	162,040	100,683	100,394	29,826	13,063	878,963
1996	13,194	42,061	48,876	74,112	94,195	131,640	158,766	140,030	75,161	73,605	22,050	16,112	889,802
1997	4,015	50,624	92,730	56,446	110,005	130,069	156,375	130,257	127,145	54,140	37,283	4,202	953,291
1998	14,742	8,122	36,408	19,431	29,177	89,483	152,671	155,342	117,632	73,378	52,770	15,871	765,027
1999	42,098	71,053	60,284	51,035	116,597	129,835	151,202	132,877	127,833	94,839	50,445	6,533	1,034,631
2000	10,371	40,629	56,312	60,881	97,607	146,571	147,652	137,195	128,529	71,212	34,917	40,040	971,916
2001	30,038	66,313	52,202	51,081	106,840	150,597	158,285	132,800	108,793	77,041	41,364	10,644	985,998
2002	8,525	72,197	58,554	59,165	77,137	143,230	160,074	130,708	81,834	155,047	46,993	33,194	1,026,658
2003	20,299	72,919	65,032	49,126	83,517	147,398	164,819	173,497	139,873	94,456	35,350	13,566	1,059,852
2004	20,385	71,826	67,710	61,810	107,859	131,088	146,885	126,300	111,313	123,180	56,363	0	1,024,719
2005	14,219	43,516	49,365	43,196	70,230	135,515	170,181	148,650	101,655	78,963	49,752	6,043	911,285
2006	11,484	92,884	37,557	11,783	96,075	129,684	179,449	156,179	103,188	95,700	48,273	30,759	993,015
2007	41,267	80,993	47,511	47,657	95,934	121,114	137,800	98,602	67,696	67,236	20,941	17,343	844,094
2008	14,838	54,656	75,231	60,196	98,165	105,374	122,707	100,027	86,811	67,028	30,196	1,609	816,838
2009	7,964	34,689	55,020	57,264	93,763	113,828	129,361	99,045	100,302	74,174	29,047	0	794,457
2010	4,339	41,850	43,163	29,934	99,458	139,412	155,006	137,555	99,130	70,831	35,391	24,601	880,670
2011	16,634	57,662	47,980	49,977	92,010	120,691	161,623	155,227	113,054	79,641	34,455	2,016	930,970
2012	18,652	95,231	39,165	37,566	103,088	129,077	139,834	129,500	88,844	66,401	31,983	15,627	894,968
2013	18,057	73,523	62,801	69,596	120,564	120,425	133,794	99,391	69,544	63,301	30,732	14,628	876,356
2014	13,035	25,919	21,529	30,028	59,540	95,454	101,548	85,748	60,441	65,905	46,816	18,347	624,310
2015	5,215	35,070	41,722	31,350	44,028	81,697	83,295	58,860	39,962	43,919	26,375	17,364	508,857
2016	8,913	30,993	45,946	47,557	80,312	123,861	125,493	102,070	80,017	68,043	35,416	7,120	755,741
2017	13,422	17,353	50,573	56,889	127,725	139,460	147,862	127,828	89,455	69,160	38,832	28,731	907,290
2018	22,311	67,614	27,854	39,673	93,189	123,320	140,741	108,742	77,336	64,054	44,037	12,178	821,049
Average	12,754	49,093	51,323	53,341	91,117	125,496	145,734	128,308	86,433	72,865	30,404	10,260	857,128
Maximum	42,098	95,231	92,730	92,021	148,464	151,208	179,449	173,497	139,873	155,047	56,363		1,059,852
Minimum	811	8,122	12,507	11,783	29,177	81,697	83,295	58,860	15,894	37,612	4,422	0	508,857
	- · ·	-,-==	,	,	- ,	. ,			-,,	- ,	, -==	5	/

Minimum Av	ailable (Ba	sed on 201	8 Historical	Use)								
Acre-Feet	98,643	45,510	48,011	48,720	0	0	0	0	868	0	84,378	100,701
cfs	1,604	819	781	819	0	0	0	0	15	0	1,418	1,638
90-Percentil	e Use											
Acre-Feet	22,311	73,523	67,710	76,875	122,150	147,398	166,837	156,179	127,145	95,700	49,752	28,731
90-Percentil	e Availabili	ty										
Acre-Feet	157,138	105,926	111,739	102,574	57,299	32,051	12,612	23,270	52,304	83,749	129,697	150,718
cfs	2,556	1,907	1,817	1,724	932	539	205	378	879	1,362	2,180	2,451

# Appendix D – Analysis of Water Needs for Potential Project Participants

As described in this Feasibility Report, the Aquaterra Groundwater Bank program would be available for use by a wide variety of potential water agencies, subject to provisions that are defined in banking program framework agreements. The potential water bank needs of water agencies would vary depending on their portfolio of water supplies, the characteristics of their water demands and other water management options (such as in-district surface or groundwater storage). For the analysis here, the focus is on the potential needs for SWP contractor participants, many of which have many common water management objectives. The use of SWP contractors as target Water Bank participants is for purposes of defining potential project facility capacities and does not preclude other water agency groups from participating in the Aquaterra Groundwater Bank. The project operations described here are a first level analysis and will be refined in the future as specific water users are identified for potential project participation. Additionally, while the analysis here is focused on specifics of SWP water supply availability and constraints, it can be refined in the future based on operational needs for agencies with other types of water supplies.

In informal discussions with SWP contractors, there are several individual contractors that potentially have an interest in participation in a project like the Aquaterra Groundwater Bank. These contractors have experienced periods in recent years when their carryover water supply in San Luis Reservoir has been placed at risk on relatively short notice due to fast developing wet water supply conditions in the Sacramento-San Joaquin Delta. In addition to potentially losing carryover water supplies, these contractors have often lost access to available Article 21 Water supplies, which only are provided on an immediate basis. The ability to store water in a project like the Aquaterra Groundwater Bank would potentially provide benefits for both protection of carryover water supplies and access to Article 21 Water.

To give a range of the potential needs, a typical project has been identified that starts with a 1% share of Table A amounts<sup>2</sup> for SWP contractors. This hypothetical 1% SWP Table A share is then used to quickly scale up to likely participation rates by a range of SWP contractors. For purposes of this discussion, a range of SWP contractor participation is assumed for between 6% and 14%. The 6% level of SWP contractor participation is considered to be likely, while a higher percentage participation is less likely and may be more price-sensitive. The development of likely operations for the Aquaterra Groundwater Bank starts with the 1% SWP contractor share and is then scaled up to 6% and to 14%. Because the level of participation is likely price-sensitive, project facilities will be sized and costs estimated for both the lower and higher participation levels.

For recharge, there are potentially two different conditions that would define the recharge capacity needed. Carryover water could occur in years when SWP Table A allocations are higher than a SWP contractor's own direct needs. The Table A allocations are normally finalized sometime in spring – typically in March or April. A typical SWP contractor would be able to quantify how much water it needs in a year and how much could be available for carryover by summer. Once the amount of potential carryover is known, it could be recharged in the Aquaterra Groundwater Bank over an extended period. The length of this recharge period is defined by when recharge conveyance capacity is available (the beginning) and when carryover water supplies are vulnerable to "spilling" (technically, this would result from SWP water displacing the carryover water in San Luis Reservoir storage). Based on the recharge capacity for the 10% wettest year identified above, there would be firm capacity available for the months of October through December. This three-month period is a conservative assumption and in actual operation, water agencies would likely take advantage of additional capacity in earlier months such as September. The amount of recharge capacity needed for carryover would be divided by three to get the monthly and instantaneous capacity needed.

The other potential need for recharge conveyance capacity would be for Article 21 Water. As noted previously, this water is available on a near instantaneous basis and potentially requires high capacity to store. Article 21 Water becomes available once the SWP share of San Luis Reservoir fills, which would normally not happen prior to January and would be most likely to occur in the last half of February and throughout the

<sup>&</sup>lt;sup>2</sup> SWP water supply is allocated based on each SWP contractors Table A amounts. The total Table A amounts for all SWP contractors is 4,172,786 acre-feet. Water supplies are typically made available based on each individual SWP contractors share of the total Table A amounts.

entire month of March. After April 1, restrictions in the Sacramento-San Joaquin Delta limit available SWP exports and Article 21 Water would no longer be available.

The potential availability of Article 21 Water for recharge in the Aquaterra Groundwater Bank was determined from available CALSIM operations studies. Studies were obtained with Delta Conveyance facilities with best estimates of likely future operations with the 2020 Incidental Take Permit and anticipated Voluntary Agreements with in-basin water users. Based on these studies, the frequency of available Article 21 Water for the months of February and March was documented as shown in Figure 1. This figure shows the availability of Article 21 Water for a hypothetical 1% of a Table A SWP contractor's share using two computations. Incremental supply is taken as the amount of reported Article 21 Water from CALSIM. This computation is considered potentially subject to underestimation of actual availability as it relies on DWR assumptions about the actual carryover of water by SWP contractors in San Luis Reservoir. In recent years, SWP contractors have often retained allocated Table A amounts in San Luis Reservoir storage that are higher than the amounts assumed in CALSIM studies. A potentially more realistic metric for the amount of Article 21 Water available can be determined by using CALSIM monthly deliveries for the total of Table A Amounts, Article 56 (Carryover) Water and Article 21 Water. The total deliveries are considered to be a more realistic estimate of the potential supply available for recharge. Finally, the reported amounts from CALSIM are based on a 1-percent SWP contractor's allocated share of Article 21 Water. In actual operation, an SWP contractor would also have access to unused shares of Article 21 Water for other SWP contractors that are not able to use Article 21 Water.

Based on **Figure 1**, the likely maximum capacity needed by a one-percent SWP contractor would be slightly more than 60 cfs based on total deliveries. Depending on the cost of facilities and price sensitivity, a lower rate of 40 cfs might also be appropriate based on the incremental amount of water supply available. Alternatively, a higher recharge rate of up to 80 cfs might be preferable based on the ability to recharge all available Article 21 Water. This higher recharge capacity would provide the ability to recharge all available Article 21 Water. Scaling up to a larger project (for 14% of SWP Table A Amounts), the total potential recharge capacity would be about 1,120 cfs. For the month of March, when available DMC capacity would be more limiting than in February, 1,120 cfs would be equivalent to about 69,000 acre-feet. 69,000 acre-feet is slightly less than the available lower DMC capacity identified above, indicating that that amount would be feasible for banking recharge operations.




Figure 1 SWP Contractor Delivery Probability

To estimate extraction quantities, an approximate operation of water bank facilities is needed. Specifically, the water bank performance requirements in terms of ability to extract water over a design drought period. Realistically, this would vary for individual SWP contractors and ultimately needs to be developed on a contractor-by-contractor basis considering the characteristics of each SWP contractor's service area demand and other water management facilities (both local and out of district) that would be available. As the project development proceeds, the potential operation of facilities should be refined to reflect the specific SWP contractors that would participate and their water management capabilities and needs.

In the absence of information on specific SWP contractors' participation, a generalized water banking operation was developed for a generic SWP contractor. This operation is based on the availability of SWP Table A allocations and does not integrate the banking operations with other water management capabilities. The starting point for the theoretical 1% SWP contractor banking operation is the Table A allocations, which are summarized by allocation level in **Figure 2**.




Figure 2 SWP Table A Allocations with Delta Conveyance

As shown in **Figure 2**, SWP allocations are frequently higher than 70% and have two extended dry periods that dominate water supply planning – the 1929-1934 drought and the 1987-1992 drought. Since the CALSIM water supply simulation ends in 2003, it does not represent the recent 2007-2010 and 2012-2016 drought periods.

For planning purposes, thresholds were selected to trigger when extractions would occur and when recharge of higher Table A allocations could occur. For extractions, an assumption has been made that extractions would occur when Table A allocations are less than 60%. Table A allocations are below 60% roughly 30% of the time during the 82-year operations study period. For recharge, a threshold of 80% was used, which occurs in about 40% of the years in the operations study. In addition to recharge of Table A allocation amounts in excess of 80%, it is also assumed that SWP contractors would recharge any available Article 21 Water, which is assumed to occur primarily in February and March, regardless of year type. These assumptions were made as a general guide to project planning for SWP contractors. Individual SWP or CVP contractors are expected to have specific recharge and extraction thresholds based on their own water use characteristics and overall water management strategies.

Using Table A allocations as a guide, a sequence of recharge and extraction events were evaluated to identify the total amount of stored water and extraction rates for a project. A general guideline of maintaining a balanced supply and use over the 82-year study period was used to identify the storage amounts and extraction rates. The extraction rates were identified as those necessary to extract available storage amounts over the two extended dry periods in the analysis period. Based on these goals and using the projected maximum recharge rate of 80 cfs, a storage account of 80,000 acre-feet was identified as appropriate for the model 1% SWP contractor. To use the available storage, the 1% SWP contractor would have access to 50 cfs

of extraction capability. As discussed above, the 50 cfs capacity was assumed to be available for a five-month (May through September) extraction period. Maximum extraction in one year would be 15,200 acre-feet. Because the operations studies start with one of the drought periods occurring relatively soon after the start of the studies, the assumption is made that operations would begin after a period of recharge has allowed storage to fill to normal operational levels. For the analysis, the initial storage level was assumed as 70,000 acre-feet.

Based on these parameters, a theoretical operation of the water bank for a 1% SWP contractor was developed and is shown in **Figure 3**.




Figure 3 Aquaterra Groundwater Bank Projected Operations

The water bank operation shown would extract essentially the entire volume in the bank by 1934. Subsequently, water would be recharged over an extended period of years and would remain full or near full during the 1970s and 1980s. A large portion of the available storage would then be used again during the early 1990s drought period.

**Table 1** was prepared to show the scaling-up of water bank operations for the smaller and larger contractor groups. This shows total project storage potentially ranging from 500,000 acre-feet for a smaller group of SWP Contractors, to 800,000 acre-feet for a medium group and a total of 1,100,000 acre-feet for a larger group. As noted earlier, these estimates are approximate and have been developed to identify a range of project facilities that would be required for the proposed project. Future evaluations will refine the parameters in **Table 1**. based on the specific SWP or CVP contractors that are interested in participation.

	Period	Prototype 1% SWP Contractor	Small SWP Contractor Group (Options 1a, 1b, 2a, 2b, 3)	Medium SWP Contractor Group (Option 4)	Large SWP Contractor Group
Table A Amounts		41.7	248.7	400.0	556.8
Percent Table A Amounts		1.0%	6.0%	9.6%	13.3%
Recharge					
Capacity (cfs)		80	480	770	1070
Recharge (TAF)	Monthly	4.8	28.6	45.8	63.7
Table A Recharge (TAF)	Oct-Dec	14.6	87	140	195
Article 21 Water Recharge (TAF)	Feb-Mar	7.1	43	68	95
Extraction					
Capacity (cfs)**		50	300	480	670
Monthly (TAF)	Monthly	3.0	17.9	28.6	39.9
Annual (TAF)	May-Sep	15	91	146	203
Maximum Storage (TAF)		80	500	800	1,100


Table	1	Aquaterra	Groundwater	Bank Pro	ogram	Characteristics
Table		Aquaterra	oroundwater	Dankin	ogram	onaracteristics

\*Only water that has been recharged may be extracted.

As described in the feasibility report, the Aquaterra Groundwater Bank operations have been based on the characteristics for the Medium SWP Contractor Group. Further refinement of these parameters and corresponding design capacities will be updated during future design efforts based on the specific needs of Aquaterra Groundwater Bank project participants.

# Appendix E – Jensen Canal Concept Designs


Provost & Pritchard Consulting Group • June 2022



## McMULLIN GSA

## FRESNO COUNTY, CA

## **AQUATERRA WATER BANK - JENSEN AVE**





SPECIAL NOTE WHERE UNDERGROUND AND SURFACE STRUCTURES ARE SHOWN ON THE PLANS, THE LOCATIONS, DEPTH AND DIMENSIONS OF STRUCTURES ARE BELIEVED TO BE REASONABLY CORRECT, BUT ARE NOT GUARANTEED. SUCH STRUCTURES ARE SHOWN FOR THE INFORMATION OF THE CONTRACTOR, BUT INFORMATION SO GIVEN IS NOT TO BE CONSTRUED AS A REPRESENTATION THAT SUCH STRUCTURES WILL, IN ALL CASES, BE FOUND WHERE SHOWN, OR THAT THEY REPRESENT ALL OF THE STRUCTURES WHICH MAY BE ENCOUNTERED.

SITE SAFETY AND PROTECTION NOTES THE DUTY OF THE ENGINEER, OWNER OR ITS AGENTS TO CONDUCT CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE AND THE UNDERTAKING OF INSPECTIONS ON THE GIVING OF INSTRUCTIONS AS AUTHORIZED HEREIN IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF THE ACTUAL CONSTRUCTION NOR MAKE THE ENGINEER, OWNER OR ITS AGENTS RESPONSIBLE FOR PROVIDING A SAFE PLACE FOR THE PERFORMANCE OF WORK BY THE CONTRACTOR, SUBCONTRACTORS, OR SUPPLIERS, OR FOR ACCESS, VISITS, USE, TRAVEL OR OCCUPANCY BY ANY PERSON.

THE CONTRACTOR SHALL HAVE AT THE WORK SITE, COPIES OR SUITABLE EXTRACTS OF CONSTRUCTION SAFETY ORDERS, ISSUED BY CAL-OSHA. CONTRACTOR SHALL COMPLY WITH PROVISIONS OF THESE AND ALL DITHER APPLICABLE LAWS, ORDINANCES AND REGULATIONS. THE CONTRACTOR MUST COMPLY WITH PROVISIONS OF THE SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION, PROMULGATED BY THE SECRETARY OF LABOR UNDER SECTION 107 OF THE CONTRACT WORK HOURS AND SAFETY STANDARDS ACT, AS SET FORTH IN TITLE 29 C.F.R.

TO PROTECT THE LIVES AND HEALTH OF CONTRACTOR'S EMPLOYEES UNDER THE CONTRACT, THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT PROVISIONS OF THE "MANUAL OF ACCIDENT PREVENTION IN CONSTRUCTION" ISSUED BY THE ASSOCIATED GENERAL CONTRACTORS OF AMERICA, INC., AND SHALL MAINTAIN AN ACCURATE RECORD OF ALL CASES OF DEATH, OCCUPATIONAL DISEASE, AND NJURY REQUIRING MEDICAL ATTENTION OR CAUSING LOSS OF TIME FROM WORK, ARISING OUT OF AND IN THE COURSE OF EMPLOYMENT THE CONTRACT WORK UNDER

THE CONTRACTOR ALONE SHALL BE RESPONSIBLE FOR THE SAFETY, EFFICIENCY, AND ADEQUACY OF CONTRACTOR'S FACILITIES, APPLIANCES, AND METHODS AND FOR ANY DAMAGE, WHICH MAY RESULT FROM THEIR FAILURE OR THEIR IMPROPER CONSTRUCTION, MAINTENANCE OR OPERATION.

THE CONTRACTOR AGREES THAT IT SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER, PROVOST & PRITCHARD CONSULTING GROUP, AND THEIR RESPECTIVE AGENTS HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF OWNER, ENGINEER, OR THEIR RESPECTIVE AGENTS.


THE OWNER AND ITS AGENTS' SITE RESPONSIBILITIES ARE LIMITED SOLELY TO THE ACTIVITIES OF THEIR EMPLOYEES ON SITE. THESE THE OWNER AND ITS AGENTS SHE RESPONSIBILITIES ARE LIMITUS SOLET TO THE ACTIVITIES OF THEIR EMPLOYEES ON SHE. THESE RESPONSIBILITIES SHALL NOT BE INFERRED BY ANY PARTY TO MEAN THAT THE OWNER OR ITS AGENTS HAVE RESPONSIBILITY FOR SITE SAFETY. SAFETY IN, ON, OR ABOUT THE SITE IS THE SOLE AND EXCLUSIVE RESPONSIBILITY OF THE CONTRACTOR ALONE. THE CONTRACTOR'S METHODS OF WORK PERFORMANCE, SUPERINTENDENCE AND THE CONTRACTOR'S LEPHOYEES, AND SEQUENCING OF CONSTRUCTION ARE ALSO THE SOLE AND EXCLUSIVE RESPONSIBILITIES OF THE CONTRACTOR ALONE.

### TOPOGRAPHY NOTE

TOPOGRAPHY SHOWN WAS COLLECTED BY PROVOST & PRITCHARD CONSULTING GROUP DURING A FIELD SURVEY CONDUCTED IN AUGUST OF 2020.

#### BOUNDARY NOTE

THE BOUNDARY/EASEMENT INFORMATION SHOWN ON THESE PLANS IS BASED UPON RECORD INFORMATION TIED TO PHYSICAL MONUMENTS, AND WAS PREPARED UNDER THE DIRECTION OF BRYAN W. BOWERS, PLS 8469.



#### GENERAL NOTES

- 2.

- McMULLIN GSA SPECIFICATIONS.


- 9 10.
- 11.
- 12.
- GSA AND THE ENGINEER.

1. ALL CONSTRUCTION SHALL BE IN CONFORMANCE WITH THESE PLANS AND PROJECT SPECIFICATIONS CONTRACTOR SHALL FIELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING FACILITIES PRIOR TO COMMENCING WORK. CALL UNDERGROUND SERVICE ALERT (USA) AT 8-1-1. CONTRACTOR SHALL MAKE ENGINEER AWARE OF ANY DISCREPANCIES. 3. ALL CAST-IN-PLACE CONCRETE STRUCTURES SHALL BE FORMED INSIDE AND OUT AND CONCRETE VIBRATED SUFFICIENTLY TO PROVIDE FOR SMOOTH SURFACED WALLS/FLOORS WITHOUT VOIDS AND HONEYCOMBS. McMULLIN GSA SHALL INSPECT ALL WORK PHASES ON CONCRETE FACILITIES FOR CONFORMANCE TO McMULLIN GSA SPECIFICATIONS. REINFORCING SHALL NOT BE ENCASED IN CONCRETE WITHOUT PRIOR MCMULLIN GSA INSPECTIONS. LIKEWISE, CONCRETE SHALL NOT BE COVERED WITH EARTH PRIOR TO MCMULLIN GSA INSPECTION. Barte o a state o a state CONCRETE DESIGN MIX SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL. ALL CONCRETE SHALL HAVE A 28-DAY MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI UNLESS OTHERWISE SPECIFIED. ALL STEEL PIPE AND FITTINGS SHALL BE FURNISHED WITH A SHOP APPLIED HIGH SOLIDS EPOXY COATING ON THE INTERIOR AND EXTERIOR, UNLESS OTHERWISE INDICATED. ALL OTHER EXPOSED STEEL SHALL BE PAINTED WITH A PRE-TREATMENT PRIMER, AN UNDERCOAT AND A FINAL COAT OF PAINT IN ACCORDANCE WITH S ALL NUTS, BOLTS, AND WASHERS USED TO SECURE UNDERGROUND FITTINGS SHALL BE STAINLESS STEEL. AFTER INSTALLATION, ALL STEEL HARDWARE SHALL BE COATED WITH A RUST PREVENTATIVE, WRAPPED WITH 4 MIL POLYETHYLENE SHEETING, AND SECURE WITH PVC TAPE. CONSTRUCTIO 3/26/21 PRELIMINAR THRUST RESTRAINTS TO BE PROVIDED AT ALL PIPELINE BENDS, WHETHER OR NOT SHOWN ON THE PLANS. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE HEALTH AND SAFETY LAWS OF THE STATE OF CALIFORNIA AND CAL/OSHA STANDARDS. TRENCH BACKFILL AND RESERVOIR EMBANKMENTS SHALL BE COMPACTED IN ACCORDANCE WITH THE SPECIFICATIONS AND THE GEOTECHNICAL REPORT CONTAINED IN THE SPECIFICATIONS. FOR CONTRACTOR WILL BE RESPONSIBLE FOR THE REPAIR OF ALL PIPELINE CRACKS, WHICH DEVELOP DURING Not CONSTRUCTION OF IMPROVEMENTS AFFECTING EXISTING FACILITIES. CONCRETE VAULTS AND BOXES MAY BE PURCHASED FROM A PRECAST MANUFACTURER OR CONTRACTOR MAY CONSTRUCT THE STRUCTURES IF STRUCTURAL CALCULATIONS AND DESIGN IS APPROVED BY THE MCMULLIN 16. ALL EXCESS MATERIAL AND/OR DEBRIS SHALL BE REMOVED UPON COMPLETION OF INSTALLATION. 17. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES. FOR THE AND JENSEN \_ ⊖ GSA 'T≺, SHEET INDEX BANK McMULLIN G ESNO COUNT GENERAL NUMBER SHEET DESCRIPTION GENERAL WATER G1 COVER G2 LEGEND & ABBREVIATIONS G3 TYPICAL CROSS SECTION G4 INDEX SHEET PLAN & PROFILE STA 10+00 TO STA 33+00 PP1 PP2 STA 33+00 TO STA 60+50 PP3 STA 60+50 TO STA 88+00 STA 88+00 TO STA 116+00 PP4 PP5 STA 116+00 TO STA 144+00 PP6 STA 144+00 TO STA 172+00 PP7 STA 172+00 TO STA 200+00 PP8 STA 200+00 TO STA 228+00 PP9 STA 228+00 TO STA 256+00 PP10 STA 256+00 TO STA 284+00 STA 284+00 TO STA 312+00 PP11 STA 312+00 TO STA 340+00 PP12 PP13 STA 340+00 TO STA 368+00 PP14 STA 368+00 TO STA 396+00 PP15 STA 396+00 TO STA 424+00 DESIGN ENGINEER: PP16 STA 424+00 TO STA 452+00 20 LYNN GROUNDWATER STA 452+00 TO STA 480+00 PP17 ICENSE NO: PP18 STA 480+00 TO STA 508+00 22 PAD BY: 23 PP19 STA 508+00 TO STA 536+00 CHECKED BY PP20 STA 536+00 TO STA 562+00 DATE: 3/26/21 CROSS SECTIONS JOB NO: 256920002 CROSS SECTIONS CS1 25 OJECT NO: CROSS SECTIONS 26 CS2 DATE PHASE: 27 CS3 CROSS SECTIONS STRUCTURAL ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FOR REDUCED OR ENLARGED PLANS 28 S1 PUMP STATION DETAILS SHEET G1 DATE D1 CONSTRUCTION DETAILS 29 CONSTRUCTION DETAILS 30 D2 1 OF 30

ABBREVIATIO	DNS					LINETYPES		
AB	AGGREGATE BASE ASPHALT CONCRETE	HORIZ HP	HORIZONTAL HINGE POINT, HIGH POINT, HORSEPOWER	TC TCE	TOP OF CURB TEMPORARY CONSTRUCTION EASEM		LINETYPE	DESCRIPTION
ACP AD	ASBESTOS-CEMENT PIPE ALUMINUM DISK	HP GAS HPS	HIGH PRESSURE GAS HIGH PRESSURE SWITCH	TDI TELE	TENSILE DUCTILE IRON TELEPHONE			WATER LEVEL
AGG AH	AGGREGATE AHEAD	HR H/T	HANDRAIL HUB & TACK	TF TFC	TOP OF FOOTING TOP FACE OF CURB			BARRICADE
ALT AP	ALTERNATE ANGLE POINT	HWL HYDRO	HIGH WATER LEVEL HYDROPNEUMATIC	TG TH	TOP OF GRATE THREAD	123	123	CONTOUR (DEPRESSION) CONTOUR (MAJOR)
APPROX	APPROXIMATE	ID	INSIDE DIAMETER	TL TOE	TOP OF LINING TOE OF SLOPE			CONTOUR (MINOR)
APN ARV	ASSESSOR'S PARCEL NUMBER AIR RELIEF VALVE	IN INV	INCH INVERT	TOP	TOP OF SLOPE	· · · · · · ·		EMBANKMENT TOE
ASTM AV	AMERICAN SOCIETY FOR TESTING AND MATERIALS AIR VENT	IP IRR	IRON PIPE IRRIGATION	TP TR	TELEPHONE POLE TELEPHONE RISER			EMBANKMENT TOP
AVE	AVENUE AMERICAN WATER WORKS ASSOCIATION	JP LBS	JUNCTION POLE POUNDS	TRANS TRFC	TRANSFORMER TRAFFIC			FENCE (BLOCK WALL)
BAR	BARRIER	LC	LENGTH OF CURVE	TS	TOP OF STRUCTURE			FENCE (CHAIN LINK) FENCE (WOOD)
BC BD	BEGIN CURVE BRASS DISK	LCW LF	LONG CRESTED WEIR LINEAR FEET	TSB TYP	TELEPHONE SPLICE BOX TYPICAL	xx		FENCE (WRE)
BFP BK	BACKFLOW PREVENTER BACK	LG LT	LONG LEFT	TWL UG	TOP OF WALL UNDERGROUND	SF	SF	FENCE (SILT)
BLDG BM	BUILDING BENCHMARK	LPG MAX	LIQUEFIED PETROLEUM GAS	UP UT	UTILITY POLE UTILITY			GATE SWING
BO	BOLLARD	MB	MAILBOX	U/S	UPSTREAM			GRADE BREAK
BTM BVC	BOTTOM BEGIN VERTICAL CURVATURE	MCC MFR	MOTOR CONTROL CENTER MANUFACTURER	VCP VERT	VERIFIED CLAY PIPE VERTICAL	0 0 0 0		GUARDRAIL
BW BWL	BACK OF WALK BACK OF WALL	MH MIN	MANHOLE MINIMUM	VG VLT	VALLEY GUTTER VAULT			RAILROAD RETAINING WALL
BWR C, CONC	BARB WIRE CONCRETE	MISC MJ	MISCELLANEOUS MECHANICAL JOINT	VLV	VALVE			SWALE CENTERLINE
CA	CALIFORNIA	MN	MAG NAIL	(W) W	WEST WATER		· · · · <b></b>	SWALE W/FLOW ARROWS
CAB CBL CFS	CABINET CABLE	MP MPT	MEDIUM PRESSURE GAS LINE MALE PIPE THREAD	WL WM	WATER LINE WATER METER			WATER (LAKE/POND)
CFS C&G	CUBIC FEET PER SECOND CURB & GUTTER	MRKR MS	MARKER MILD STEEL	WS WV	WATER SERVICE WATER VALVE			WATER (MARSH/SWAMP)
CHK	CHECK	(N)	NORTH	ww	WASTE WATER	c/c	XX" C/C XX" ELEC (AERIAL)	COMPUTER/COMM. (BURIED)
CI	CHAIN LINK CAST IRON	ŇÁVD NC	NORTH AMERICAN VERTICAL DATUM NORMALLY CONSOLIDATED	₩/ ₩/0	WITH WITHOUT	——————————————————————————————————————	XX ELEC (AERIAL)	ELECTRIC (AERIAL)
CIP CIPCP	CAST IRON PIPE CAST-IN-PLACE CONCRETE PIPE	NGVD NIC	NATIONAL GEODETIC VERTICAL DATUM NOT IN CONTRACT			EEEE	XX ELEO (BORLED)	ELECTRIC (BURIED)
CL CLVT	CLASS CULVERT	NPT NTS	NATIONAL PIPE THREAD NOT TO SCALE			F0	XX" GAS	FIBER-OPTIC GAS
φ.	CENTERLINE	OC	ON CENTER				XX" IRR	GAS
CLF CLR	CHAIN LINK FENCE CLEAR, CLEARANCE	OD OH	OUTSIDE DIAMETER OVERHEAD			0	XX" OIL	OIL
CMLC CMP	CEMENT MORTAR LINED & COATED CORRUGATED METAL PIPE	OP OSHA	OPERATING OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION			s	XX" SS	SANITARY SEWER
CN	CONCRETE NAIL	O&M	OPERATIONS & MAINTENANCE			FM	XX" FM	SANITARY SEWER FORCE MAIN
CNS CO	COMPACTED NATIVE SOIL SEWER CLEAN OUT	(P) PB	PROPOSED PULL BOX				XX" SI	SANITARY SEWER LATERAL
CONT CONST	CONTINUOUS CONSTRUCT/CONSTRUCTION	PC PCC	POINT OF CURVATURE POINT OF COMPOUND CURVATURE			S I	XX" STEAM	SIGNAL INTERCONNECT (BURIED)
COR	CORNER CORPORATION	PCC PE	PORTLAND CEMENT CONCRETE PERMANENT EASEMENT			SD	XX" SD	STEAM STORM DRAINAGE
COL	COLUMN	PER	PERIMETER				XX" TELE (AERIAL)	TELEPHONE (AERIAL)
COUP CP	COUPLING CONTROL POINT	PI PIP	POINT OF INTERSECTION PLASTIC IRRIGATION PIPE			ттттт	XX" TELE (BURIED)	TELEPHONE (BURIED)
CR CU CY	CROWN CUBIC	PLC P	PROGRAMMABLE LOGIC CONTROLLER PROPERTY LINE			Tv	XX" TV (AERIAL) XX" TV (BURIED)	TELEVISION (AERIAL LINE)
CY	CUBIC YARDS	PNL	PANEL			TV	XX TV (BURIED)	TELEVISION (BURIED LINE)
DA DEC	DRIVE APPROACH DECIDUOUS	POC POL	POINT ON CURVE POINT ON LINE			W		WATER
DEMO DI	DEMOLISH/DEMOLITION DROP_INLET	POT PP	POINT ON TANGENT POWER POLE					CENTERLINE EASEMENT
DIA, Ø	DIAMETER	PRC	POINT OF REVERSE CURVATURE					MEANDER LINE
DIM DIP	DIMENSION DUCTILE IRON PIPE	PRV PSF	PRESSURE REDUCING VALVE POUNDS PER SQUARE FOOT					PROPERTY LINE
D/S DW	DOWNSTREAM DRIVEWAY	PSI PT	POUNDS PER SQUARE INCH POINT OF TANGENCY					RESERVATION/PARK/FOREST
DWG	DRAWNG	PVC PVCC	POLYVINYL CHLORIDE POINT OF VERTICAL COMPOUND CURVATURE					RIGHT-OF-WAY
(E) EA	EXISTING, EAST EACH	PVMT	PAVEMENT					RELINQUISH ACCESS LINE
EC ECC	END CURVE ECCENTRIC	PVRC PVI	POINT OF VERTICAL REVERSE CURVATURE POINT OF VERTICAL INTERSECTION				-	SECTION LINE
EF EG	EACH FACE EXISTING GRADE	R RBR	RADIUS REBAR					STATE/COUNTY/CORPORATE LIMIT REVISION CLOUD
EL, ELEV	ELEVATION	RC RCP	RADIUS OF CURVE REINFORCED CONCRETE PIPE					SAWCUT LINE
ELC ELEC	EPOXY LINED & COATED ELECTRIC	RD	RELATIVE DENSITY					DEMO LINE
ELL EM	ELBOW ELECTRIC METER	RD RE	ROAD REFERENCE			HATCHES	• • • • • • • • • • • • • • • • • • • •	WORK LIMITS
EOL	END OF LINE EDGE OF PAVEMENT	REQD RET	REQUIRED RETURN				701 705	
EQUIV	EQUIVALENT	REV RGRCP	REVISION RUBBER GASKETED REINFORCED CONCRETE PIPE			<b>HA</b> EXISTING	ATCH TYPE NEW	DESCRIPTION
ESMT EUC	EASEMENT EUCALYPTUS	RGS	RIGID GALVANIZED STEEL					
EVC EW	END VERTICAL CURVE EACH WAY	RP RR	RADIUS POINT RAILROAD					AGGREGATE
EXP	EXPOSED	RT RTU	RIGHT REMOTE TERMINAL UNIT					
(F) F&I	FUTURE FURNISH & INSTALL	R/W	RIGHT OF WAY					AC PAVEMENT
FD FDC	FOUND FIRE DEPARTMENT CONNECTION	(S) S	SOUTH, SOLVENT WELD SLIP					
FF	FINISHED FLOOR	S= SCH	SLOPE SCHEDULE				- 4 ···	CONCRETE
FG FH	FINISHED GRADE FIRE HYDRANT	SCP	STANDARD CONCRETE PIPE			n	. مە <sup>ر</sup> ىي 1	OUNCLEE
FLG	FLOW LINE FLANGE	SD SDMH	STORM DRAIN STORM DRAIN MANHOLE					CONCRETE LINING (PLAN VIEW)
FLGD	FLANGED	SEC SERV	SECTION SERVICE					CONSILIE LINING (I LAN VIEW)
FM FNC	FORCE MAIN FENCE	SF	SQUARE FEET					
FRP FT	FIBER REINFORCED POLYESTER PIPE FOOT/FEET	SP SPEC	SERVICE POLE SPECIFICATION					EARTH
FW FWL	FRONT OF WALK FACE OF WALL	SPNDL SQ	SPINDLE SQUARE					
GA	GAUGE	SS SS OR STS	SANTARY SEWER STAINLESS STEEL				KA	RIP RAP
GAL GALV	GALLON GALVANIZED	SSMH	SANITARY SEWER MANHOLE					
GB GM	GRADE BREAK GAS METER	STA STD	STATION STANDARD					SAND
GPM	GALLONS PER MINUTE	STL STP	STEL STAND PIPE					
GRVL GS	GRAVEL GAS	STRC	STRUCTURE					GRATING
GSV GUY	GAS VALVE GUY WIRE	STRP SWL	STRIPING SWALE					
GV	GATE VALVE	STWL (T)	STILLING WELL THREADED					
HD HDPE	HEAD HIGH DENSITY POLYETHYLENE	Ť	THREAD					EXPANDED METAL
HDR HDW	HEADER HEADWALL	T&B TB	TOP & BOTTOM TOP OF BANK					
HGL	HYDRAULIC GRADE LINE	TBM	TEMPORARY BENCHMARK					

A A CONTROL POWI A BENCH MARK A CANACELEHYDRANT A CANACELEHYDRANT A CANACELEHYDRANT A CANACELEHYDRANT A CANACELEHYDRANT A CANACELEHYDRANT A CANACELEHYDRANT A RELEFV AULCE B A WATER VALVE B A WATER VALVE B B A WATER VALVE B A B A WATER VALVE B B A WATER VALVE A B A B A B A B A B A B A B A B A B A B	SYMBOLS     DESCRIPTION       EXISTING     NEW       Image: Symbol in the sy	CHEAR OF LOSS IN THE CARL AND A CONTRACT AND A CO
Q     Q     Z=NOZZLE HYDRANT       Image: Solution of the solution o	<ul> <li>IRON PIPE</li> <li>MONUMENT</li> <li>MONUMENT (OPTI</li> <li>MONUMENT (OPTI</li> <li>MO</li> <li>MO</li> <li>MO</li> <li>MO</li> <li>LOT NUMBER</li> </ul>	ONAL)
Image: marked bit water line     PROJECT NO:       Image: marked bit water line     PHASE:       Image: marked bit water line     Image: marked bit water line       Image: marked bit water line     Image: marked bit water line       Image: marked bit water line     Image: marked bit water line       Image: marked bit water line     Image: marked bit water line       Image: marked bit water line     Image: marked bit water line       Image: marked bit water line     Image: marked bit water line       Image: marked bit water line     Image: marked bit water line	T       T       TELEPHONE VAULT         Q       ♠       2-NOZZLE HYDR,         -Ò-       ♣       3-NOZZLE HYDR,         (F0)       F0)       FIRE DEPT. CONN         F       F       FIRE DEPT. CONN         F       F       FIRE VAULT         ⊞       ■       WATER METER         🐵       ⑩       ₩         ♦       ●       WATER VALVE         ↓       ↓       BLOW-OFF         ♀       ♥       ▲         ●       ▶       BLOW-OFF         ♀       ♥       ▲         ●       ▶       BLOW-OFF         ♀       ♥       ▲       AIR RELIEF VALVE         ▶       ▶       BLOW-OFF         ♀       ♥       ▲       AIR RELIEF VALVE         ▶       ▶       BLOW-OFF         ♀       ♥       ▲       AIR RELIEF VALVE HAN         ☑       ☑       STILLING WELL         ↓       ↓       ♥	AQUATERRA WATER BANK – JENSEN AVE McMULLIN GSA FRESNO COUNTY, CA GENERAL LEGEND & ABBREVIATIONS
	Image: Construction c	ROW DESIGN ENGINEER: LYNN GROUNDWATER LCENSE NO:  DRAFTED BY: CHECKED BY: PAD DATE: 3/26/21 JOB NO: 256920002 PROJECT NO: PHASE: Q ORIGINAL SCALE SHOWN IS ORIGINAL SCALE SHOWN IS ORIGINAL SCALE FOR REDUCED OR ENLARGED PLANS.






TYPICAL CROSS SECTION - JENSEN AVE ALIGNMENT


EXPENDENT SOLT AP-REDUCES & PERTURATED EXONETENNC GROUP INC. ALL RIGHTS RESERVED. The firm of Provest & Pitchard Engineering doup, Inc. apresery reserves in a common increase plana. These other applicable property rights in these plana. These	plons are not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to a third party without first obtaining the written permission and consent of Provost &	Prictors Expigneering corrum, inc. In the event of unathenized reader of these plans by a third party, the third party shall hold the firm of Provids & Prictors Expinering Davio, inc. Innerses, and shall bear the cost of Provest & Pritchard Engineering bear the cost of Provest & Pritchard Engineering the provest of Provest & Provest & Pritchard Engineering the provest of Provest & Provest & Provest & Pritchard Engineering the provest of Provest & Pro	<ul> <li>Group, Inc.'s legal fees associated with defending and enforcing these rights.</li> </ul>
RY RUCTION			BY DATE
PRELIMINARY NOT FOR CONSTRUCTION	3/26/21		REVISION
			No.
ب م لا	EVIE	1 27 27	
< 2	MCMULLIN 55A FRESNO COUNTY, CA		TYPICAL CROSS SECTION
<u> DST&amp;</u>	KIICHARD	An Employee Owned Company 286 wEST CROMWELL AVENUE FRESNO, CALLEORNIA 93711-6162	009/449-2/00 FAX 009/449-2/10 www.ppeng.com
DESIGN E LYNI LICENSE DRAFTED PAD	NGINEE N GROU NO: BY:	R: UNDWATE CHECKED	
DESIGN E LYNI LICENSE DRAFTED PAD DA JOB 1	NGINEE N GROU NO: BY: TE: 3/2	R: UNDWATE	R
DESIGN E LYNI LICENSE DRAFTED DA JOB 1 PROJECT 1 PROJECT 1 PROJECT 1 ORIGINA REDUCED	NGINEE N GROI NO: BY: BY: TE: 3/2 NO: 256 NO: SE:	R: UNDWATE CHECKED 26/21 5920002	R

2:1 DAMIGHT — EG






10+00	20-	+00
170		
160		
150		
140		





33+00	40+00	50+00	
170			
170			
160			
150			
140			




60-	+50	70-	+00	80-	+00
_170					
_160					EG –
_150					
140					














116	+00 120	9+00	130	+00	
170					
	-TOP 166.80				
_160					
	-INV 155.80				
_150					
140					















00+00	210+00	220+00	
0		(E) POND BANK	
-TOP 166.80			
			ľ
<u>)</u>			
-INV 155.80			














256	5+00 260	)+00	270	9+00	280+0
190					
_180	-TOP 180.50				
				(E) EG	
170					
	-INV 169.50				
160					
_160		1	1	1	1
























































+00 540+00	550+00	560+
-TOP 205.80		
/^		
	EG –⁄	
-INV 194.80		




Completion and the should are performed to the should be performed to the should be performed by the s	Group, Inc.'s legal fees associated with defending and enforcing these rights.
	BY DATE
RY RUCTION	B
PRELIMINARY NOT FOR CONSTRUCTION 3/26/21	REVISION
	No.
FOR LEW REVENT	
AQUATERRA WATER BANK – JENSEN AVE McMULLIN GSA FRESNO COUNTY, CA CROSS SECTIONS	CROSS SECTIONS
DESIGN ENGINEER: LYNN GROUNDWATE LICENSE NO:	
PAD DATE: 3/26/21 JOB NO: 256920002	BY:
REDUCED OR ENLARGED PLA	S OR NS.
SHEET OOA	






DeProdent T_2021_by FPORDST_S_R PILICHARD EXCENTEENIG_SROLP_ING_ALL RELATE RESERVED. The firm of Provest & Pritchard Engineering Ocup. Inc. expressly reserves its common long recypright and other applicable property rights in these plans. These	plans are not to be reproduced, changed, or copied in any form or manner whitscrever, nor are they to be assigned to a third party without first obtaining the written permission and consent of Provost &	Pricticned Expineering Carou, Inc., In the event of unauthorized reuse of these plans by a brind party, the third party shall had the firm of Provest & Prictored Expineering Octow, Inc., Inniness, and shall bear the cast of Provest & Pritchard Engineering	DATE Group, Inc.'s legal fees associated with defending and enforcing these rights.
NO			BY DA
PRELIMINARY NOT FOR CONSTRUCTION	3/26/21		. REVISION
			No.
¢, ¢		N 1	
< :	MCMULLIN GSA FRESNO COUNTY, CA	CROSS SECTIONS	CROSS SECTIONS
DESIGN E		<b>■</b>	209/449-2/00 FAX 559/449-2/15 www.ppeng.com
	TE: 3/2		BY:
JOB I PROJECT I	NO:	920002	
	SE:	1	
	AL SCAL		5
õ	AL SCAL H. ADJUS OR ENL		S 'OR INS.




COPYRIGHT 2021 by PROVOST & PRITCHARD ENGINEERING SROUP, INC. ALL RIGHTS RESERVED. The firm of Provost & Pritchord Engineering Group, Inc. exoressiv reserves its common law coowhight and	other applicable property rights in these plans. These plans are not to be reproduced, changed, ar copiel in any form or manner whotsoever, nor are they to be assigned to a third porty without fract obtaining the written permission and consent of Provest &	Pritchard Engineering Group, Inc. In the event of mouthingher tease of these plans by third party, the third party shall hold the firm of Provost & Pritchard Engineering Octon, Inc. Immess, and shall bear the cast of Provost & Pritchard Engineering	
			DATE
			ΒY
PRELIMINARY	3/26/21		REVISION
			No.
	PENE PENE		
aquaterra water bank – Jensen ave	MCMULLIN GSA FRESNO COUNTY, CA	STRUCTURAL	PUMP STATION
OST &	RITCHARD	An Employee Owned Company 286 WEST CROMWELL AVENUE FRESNO, CALIFORNIA 93711-6162	559/449-2700 FAX 559/449-2715 www.ppeng.com
VOAd VOAd			
LICENS	I ENGINEE INN GRO E NO:	R: UNDWATE	
L` LICENS – DRAFTI P/	I ENGINEE INN GRO E NO: ED BY: AD DATE: 3/	R: UNDWATE	R BY:
L' LICENS – DRAFTI P/ JOI PROJEC PI	L ENGINEE (NN GRO E NO: ED BY: AD DATE: 3/ 3 NO: 250 T NO: HASE:	R: UNDWATE CHECKED 26/21 6920002	
L' LICENS – DRAFTI P/ JOI PROJEC PI	L ENGINEE (TNN GRO E NO: ED BY: AD DATE: 3/ 3 NO: 250 T NO: HASE: 0	R: CHECKED     CHECKED     26/21     6920002    1"	


/26/2021 3:26 PM g:/mcmullin gsa-2659/2659 on-going/CAD/340 sheet sets/03\_Structural/S1 PUMP STATION.dwg -Lindsey Sciacca





COPTROL 2011 by FRUNCI & FRUNCI & FRUNCI COPTROL 2011 by FRUNCI & FRUNCI & FRUNCI & FRUNCI Inc. average of the framework of the started Double Inc. average/reserves (the framework) for the second plans are not to be reproduced, change, or copter plans are not to be reproduced, change, or copter plans are not to be reproduced, change, or copter plans are not to be reproduced, change, or copter plans are not to be reproduced, change, or copter plans are not to be reproduced. The reserves of the average area of the reproduced and the reproduced the average area of the reproduced and the reproduced the average area of the reproduced and the reproduced the average area of the reproduced and the reproduced and the reproduced area of the reproduced and the PRELIMINARY NOT FOR CONSTRUCTION 3/26/21 FOR FUN AQUATERRA WATER BANK - JENSEN AVE S CONSTRUCTION DETAIL McMULLIN GSA FRESNO COUNTY, CA DETAILS  $\Delta \infty$ āγα 00 DESIGN ENGINEER: LYNN GROUNDWATER LICENSE NO: DRAFTED BY: CHECKED BY: PAD DATE: 3/26/21 JOB NO: 256920002 ROJECT NO: PHASE: 0\_\_\_\_\_1" ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FOR REDUCED OR ENLARGED PLANS. SHEET D1 29 OF 30



SECTION VIEW - ROADWAY ALL DIMENSIONS ALONG CENTERLINE OF PIPELINE







#### PLACEMENT OF SPACERS ON CARRIER PIPE

- GENERAL ONE SPACER SHALL BE PLACED NOT MORE THAN TWO FEET FROM EACH END OF CASING. SUBSEQUENT SPACERS SHALL BE PLACED AT 6' INTERVALS WITHIN THE CASING, OR IN ACCORDANCE WITH PIPE MANUFACTURERS RECOMMENDATIONS.
- FOR ALL CARRIER PIPE, ONE SPACER SHALL BE PLACED ON THE SPIGOT END OF EACH SEGMENT AT THE LINE MARKING THE LIMIT OF INSERTION INTO THE BELL WHEN THE JOINT IS COMPLETE, THE SPACER SHALL BE IN CONTACT WITH THE BELL OF THE JOINT SO THAT 2. THE SPACER PUSHES THE JOINT AND RELIEVES COMPRESSION WITHIN THE JOINT. SUBSEQUENT SPACERS SHALL BE PLACED AT 6'-10' INTERVALS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

#### CARRIER PIPE

1. CARRIER PIPE SHALL BE CENTERED WITHIN CASING BY USING OF ONE OF THESE METHODS:

WOOD SKIDS PRESSURE TREATED #2 DF 2XS, #3 REDWOOD 2XS

MANUFACTURED SPACERS HDPE OR STEEL

## CASING SPACERS AS MANUFACTURED BY ONE OF THE FOLLOWING ADVANCE PRODUCTS & SYSTEMS, INC.; CCI PIPELINE SYSTEMS; PUBLIC WORKS MARKETING, INC.; PIPELINE SEAL & INSULATOR, INC.; OR APPROVED EQUAL

#### BLOWN SAND

CASING SHALL BE FILLED WITH BLOWN SAND AFTER INSTALLATION OF CARRIER PIPE

CASING END SEALS

1. CASING END SEALS SHALL BE SEALED BY USING ONE OF THESE METHODS:

RUBBER SEALS WRAP AROUND, NEOPRENE RUBBER, MIN. THICKNESS:1/8"; TEMPERATURE RATING: -20°F TO 170°F.

STEEL BAND STAINLESS STEEL BANDING; MIN. 2 BANDS PER SEAL; T304 STAINLESS STEEL WITH 100% NON-MAGNETIC WORM GEAR, 1/2" MIN. WIDTH.

#### BORE AND RECEIVING PIT NOTES

- THE [AGENCY] HAS OBTAINED IT'S PORTION OF A [AGENCY] ENCROACHMENT PERMIT. THE CONTRACTOR SHALL OBTAIN HIS PORTION OF THE [AGENCY'S] PERMIT (NO PERMIT FEE) PRIOR TO PERFORMING ANY WORK WITHIN THE [AGENCY'S] RIGHT OF WAY.
- 2. ALL WORK WITHIN THE [AGENCY'S] RIGHT OF WAY SHALL BE IN CONFORMANCE WITH [AGENCY'S] ENCROACHMENT PERMIT REQUIREMENTS.
- 3. BORE AND RECEIVING PITS SHALL BE LOCATED 5 FEET (MINIMUM) OUTSIDE OF [AGENCY'S] RIGHT OF WAY.
- 4. IF THE AGENCY IS CALTRANS: THE BORE AND RECEIVING PITS ARE UNDER STATE OF CALIFORNIA JURISDICTION, REGARDLESS OF THEIR LOCATION, SIZE AND LOCATION OF BORE AND RECEIVING PITS ARE THE CONTRACTOR'S RESPONSIBILITY SUBJECT TO CALTRANS APPROVAL.
- 4. IF THE AGENCY IS NOT CALTRANS:SIZE AND LOCATION OF BORE AND RECEIVING PITS ARE THE CONTRACTOR'S RESPONSIBILITY SUBJECT TO [AGENCY'S] APPROVAL.
- 5. ACCESS TO THE BORE AND RECEIVING PITS SHALL ONLY BE FROM THE CONSTRUCTION EASEMENTS OBTAINED BY [AGENCY]. THE PARKING OF EQUIPMENT AND/OR MATERIALS SHALL NOT BE WITHIN 20' OF THE ROADWAY LANES.
- 6. BORE AND RECEIVING PITS SHALL BE ADEQUATELY FENCED AND/OR HAVE A TYPE-K BARRIER PLACED AROUND THEM.
- 7. BORE AND RECEIVING PITS SHALL BE ADEQUATELY SHORED IN ACCORDANCE WITH CAL OSHA REQUIREMENTS.
- 8. SHORING PLANS, SIGNED BY A REGISTERED ENGINEER, SHALL BE SUBMITTED AND APPROVED BY [AGENCY] BEFORE EXCAVATING.
- 9. CASING PIPE MAY BE NEW OR USED STEEL PIPE WITH A MINIMUM YIELD STRENGTH OF 36,000 PSI. (ASTM A36). USED STEEL PIPE SHALL BE PRE-APPROVED BY [AGENCY'S] BEFORE INSTALLATION.
- 10. CASING PIPE MAY BE SPIRAL WELDED PIPE PROVIDED THE PIPE IS NEW AND THE WELD IS SMOOTH.
- 11. ALL CASING LENGTHS SHALL BE EQUAL TO THE AUGER LENGTH.
- 12. ALL CASING JOINTS WELDED IN THE FIELD SHALL BE FULLY WELDED AROUND THE CIRCUMFERENCE OF THE PIPE WITH COMPLETE PENETRATION WELD.
- 13. [AGENCY] SHALL SET AND CHECK A SURVEY GRID PER [AGENCY'S] APPROVED ENCROACHMENT PERMIT. CONTRACTOR SHALL PRESERVE ALL MONUMENTS ASSOCIATED WITH SURVEY GRID.


NOT TO SCALE (###\#\ D1

JACK AND BORE

PPNO ROVOST & PRITCHARD NC. ALL RIGHTS RESERV Pritchard Engineering G its common law copyrig ts con. ty rights in v produced, chinv produced, chinv r whotsoew, no d party without ' n and consent o and consent o of these plans b of these plans b of these plans b rich hich vost & Pritch vost & Pritch COPYRIGHT 2 COPYRIGHT 2 The firm of the other optication in any form in any fo PRELIMINARY F FOR CONSTRUCTION 3/26/21 NOT FOR FUR ₹ JENSEN DFTAII S GSA NTY, WATER BANK McMULLIN G FRESNO COUNT DETAILS CONSTRUCTION AQUATERRA DESIGN ENGINEER: LYNN GROUNDWATER ICENSE NO: DRAFTED BY: CHECKED BY: PAD DATE: 3/26/21 JOB NO: 256920002 ROJECT NO: PHASE: 0 ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FOR REDUCED OR ENLARGED PLANS SHEET D2 30 OF 30

# Appendix F – East-Side Canal Concept Designs

Provost & Pritchard Consulting Group • June 2022



THE CONTRACTOR SHALL HAVE AT THE WORK SITE, COPIES OR SUITABLE EXTRACTS OF CONSTRUCTION SAFETY ORDERS, ISSUED BY CAL-OSHA. CONTRACTOR SHALL COMPLY WITH PROVISIONS OF THESE AND ALL OTHER APPLICABLE LAWS, ORDINANCES AND REGULATIONS. THE CONTRACTOR MUST COMPLY WITH PROVISIONS OF THE SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION, PROMULGATED BY THE SECRETARY OF LABOR UNDER SECTION 107 OF THE CONTRACT WORK HOURS AND SAFETY STANDARDS ACT, AS

SET FORTH IN TITLE 29 C.F.R.

TO PROTECT THE LIVES AND HEALTH OF CONTRACTOR'S EMPLOYEES UNDER THE CONTRACT, THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT PROVISIONS OF THE "MANUAL OF ACCIDENT PREVENTION IN CONSTRUCTION" ISSUED BY THE ASSOCIATED GENERAL CONTRACTORS OF AMERICA, INC., AND SHALL MAINTAIN AN ACCURATE RECORD OF ALL CASES OF DEATH, OCCUPATIONAL DISEASE, AND INJURY RECURING MEDICAL ATTENTION OR CAUSING LOSS OF TIME FROM WORK, ARISING OUT OF AND IN THE COURSE OF EMPLOYMENT OR WORK UNDER THE CONTRACT.

THE CONTRACTOR ALONE SHALL BE RESPONSIBLE FOR THE SAFETY, EFFICIENCY, AND ADEQUACY OF CONTRACTOR'S FACILITIES, APPLIANCES, AND METHODS AND FOR ANY DAMAGE, WHICH MAY RESULT FROM THEIR FAILURE OR THEIR IMPROPER CONSTRUCTION, MAINTENANCE OR OPERATION.

THE CONTRACTOR AGREES THAT IT SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER, PROVOST & PRITCHARD CONSULTING GROUP, AND THEIR RESPECTIVE AGENTS HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF OWNER, ENGINEER, OR THEIR RESPECTIVE AGENTS.

THE OWNER AND ITS AGENTS' SITE RESPONSIBILITIES ARE LIMITED SOLELY TO THE ACTIVITIES OF THEIR EMPLOYEES ON SITE. THESE RESPONSIBILITIES SHALL NOT BE INFERRED BY ANY PARTY TO MEAN THAT THE OWNER OR ITS AGENTS HAVE RESPONSIBILITY FOR SITE SAFETY. SAFETY IN, ON, OR ABOUT THE SITE IS THE SOLE AND EXCLUSIVE RESPONSIBILITY OF THE CONTRACTOR ALONE. THE CONTRACTOR'S METHODS OF WORK PERFORMANCE, SUPERINTENDENCE AND THE CONTRACTOR'S LEPLOYEES, AND SEQUENCING OF CONSTRUCTION ARE ALSO THE SOLE AND EXCLUSIVE RESPONSIBILITIES OF THE CONTRACTOR ALONE.

### TOPOGRAPHY NOTE

TOPOGRAPHY SHOWN WAS COLLECTED BY PROVOST & PRITCHARD CONSULTING GROUP DURING A FIELD SURVEY CONDUCTED IN AUGUST OF 2020.

#### BOUNDARY NOTE

THE BOUNDARY/EASEMENT INFORMATION SHOWN ON THESE PLANS IS BASED UPON RECORD INFORMATION TIED TO PHYSICAL MONUMENTS, AND WAS PREPARED UNDER THE DIRECTION OF BRYAN W. BOWERS, PLS 8469.


APPROVALS -- APPROVAL 1----APPROVAL 2--

		ਦ
BALL NOT BE CEVERED WITE ART MERRO TO LARENCY UNPERTON.     SHALL BE SUBMITED TO THE ENANGER FOR REVEW AND APPROVAL ALL ONCETES     SHALL SUBMITED TO THE ENANGER FOR REVEW AND APPROVAL ALL ONCETES     SHALL SUBMITED TO THE ENANGER FOR REVEW AND APPROVAL ALL ONCETES     SHALL SUBMITED TO THE ENANGER FOR REVEW AND APPROVAL ALL ONCE THE THE INTERVISES SUBSTIMESTING ADDIA TO SODO PSI UNLESS DIFFERING. STREET OR PARTY IN ACCORDANCE WITH     SHALL STEEL HARDWARE SHALL BE COMPACING IN ACCORDANCE WITH     NN.     NUMBERCONT AND A FINAL COAT OF PANT IN ACCORDANCE WITH     NN.     NUMBERCONT AND A FINAL COAT OF PANT IN ACCORDANCE WITH     NN.     NUMBERCONT AND A FINAL COAT OF PANT IN ACCORDANCE WITH     NN.     NUMBERCONT SHALL BE COMPACITIEN IN ACCORDANCE WITH THE     EERONADE AT ALL PRETURE GRADS, WHETHER OR NOT SHOWN ON THE PLANS.     ALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE HEALTH AND SAVETY LWS OF     NN. AND SCORE SHALL BE COMPACITIEN IN ACCORDANCE WITH THE     EERONADE AT ALL PRETURE GRADS, WHETHER OR ON THEOLOP DURING     NN. AND SCORE SHALL BE COMPACITIEN IN ACCORDANCE WITH THE     EERONADEL AT ALL PRETURE GRADS, WHETHER OR CONTRACTOR MAY     NUMBERCONTS SHALL BE COMPACITIEN IN ACCORDANCE WITH THE     EERONADEL FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES.     SHEET INDEX     NUMBERCONTS SHALL BE REMOVED UP ON COMPLETION OF INSTALLATION.     E RESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES.     SHEET INDEX     NUMBERCONTS SHALL BE REMOVED UP ON COMPLETION OF INSTALLATION.     E RESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES.     SHEET INDEX     NUMBERCONTON OF INSTALLATION.     ERESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES.     SHEET INDEX     NUMBERCONTON OF INSTALLATION.     ERESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL     NUMPERCONTON.     NUMPERCONTON OF INSTALLATION.     ERESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL     NUMPERCONTON     NUMPERCONTON OF INSTALLATION.     ERESPONSIBLE FOR PROVIDER PARTY LAWS     NUMPERCONTON OF INSTALLATION.	DISTRICT FACILITIES. TS, MISFITS, OR SECONDS, ETC. ARE NOT ACCEPTABLE FOR USE ON [AGENCY] ALL BE IN CONFORMANCE WITH THESE PLANS, PROJECT SPECIFICATIONS AND [AGENCY] ELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING FACILITES WORK. CALL UNDERGROUND SERVICE ALERT (USA) AT 8–1–1. CONTRACTOR SHALL : OF ANY DISCREPANCIES. ONCRETE STRUCTURES SHALL BE FORMED INSIDE AND OUT AND CONCRETE VIBRATED DE FOR SMOOTH SURFACED WALLS/FLOORS WITHOUT VOIDS AND HONEYCOMBS.	Competent J. 2020. In Sector S. E. Bourds K. A. M. 2020. In Sector S. E. Distributed Feature Structure Science 4. Behavior de la media provente Sector and the sector an
TURES IF STRUCTURAL CALCULATIONS AND DESIGN IS APPROVED BY THE [AGENCY] AND/OR DEBRIS SHALL BE REMOVED UPON COMPLETION OF INSTALLATION. E RESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES.	HALL NOT BE COVERED WITH EARTH PRIOR TO [AGENCY] INSPECTION. SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL. ALL CONCRETE Y MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI UNLESS OTHERWISE SPECIFIED. ITTINGS SHALL BE FURNISHED WITH A SHOP APPLIED HIGH SOLIDS EPOXY COATING ON ERIOR, UNLESS OTHERWISE INDICATED. ALL OTHER EXPOSED STEEL SHALL BE PAINTED IT PRIMER, AN UNDERCOAT AND A FINAL COAT OF PAINT IN ACCORDANCE WITH NS. WASHERS USED TO SECURE UNDERGROUND FITTINGS SHALL BE STAINLESS STEEL. ALL STEEL HARDWARE SHALL BE COATED WITH A RUST PREVENTATIVE, WRAPPED WITH 4 LETING, AND SECURE WITH PVC TAPE. D BE PROVIDED AT ALL PIPELINE BENDS, WHETHER OR NOT SHOWN ON THE PLANS. ALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE HEALTH AND SAFETY LAWS OF INA AND CAL/OSHA STANDARDS. RESERVOIR EMBANKMENTS SHALL BE COMPACTED IN ACCORDANCE WITH THE HE GEOTECHNICAL REPORT CONTAINED IN THE SPECIFICATIONS. RESPONSIBLE FOR THE REPAIR OF ALL PIPELINE CRACKS, WHICH DEVELOP DURING ROVEMENTS AFFECTING EXISTING FACILITIES.	PRELIMINARY NOT FOR CONSTRUCTION 3/26/21 REVISION
SHEET INDEX     SHEET INDEX       SHEET INDEX     SHEET INDEX       SHEET NO.     DESCRIPTION       GENERAL     GI       GI     COVER SHEET       LAND DEVELOPMENT     LD1       LD1     HORIZONTAL CONTROL       LD2     GRADING PLAN       LD3     UTULTY PLAN       LD4     PARKING LOT       LD5     PIPELINE PLAN AND PROFILE       LD6     STREET CONSTRUCTION       LD7     ROAD SUPERELEVATION DIAGRAM       LD8     ROADWAY CROSS SECTIONS       LD9     TPICAL DETAILS       AGRICULTURAL     AG1       AG2     CANAL PLAN AND PROFILE       AG2     CANAL PLAN AND PROFILE       AG4     TYPICAL DETAILS       AG4     TYPICAL DETAILS	CTURES IF STRUCTURAL CALCULATIONS AND DESIGN IS APPROVED BY THE [AGENCY]	FOR ENT
SHEET INDEX         SHEET INDEX         SHEET INDEX         SHEET INDEX         GENERAL         G1       COVER SHEET         G2       ABBREVIATIONS & SYMBOLS         G3       INDEX SHEET         LAND DEVELOPMENT       LD1       HORIZO DEVELOPMENT         LD2       GRADING PLAN       LD3         LD3       UTILITY PLAN       LD4       PARNING LOT         LD5       PIPELINE PLAN AND PROFILE       LYNN GROUNDWATER         LD6       STREET CONSTRUCTION       LCENSE NO:         LD7       ROAD SUPERELEVATION DIAGRAM       DRAFTED BY:         LD8       ROADWAY CROSS SECTIONS       DATE         AG1       SITE DETAILS       DATE: 3/26/21         DATE       AG2       CANAL PLAN AND PROFILE       PHASE:         AG3       CANAL CROSS SECTIONS       Q       1'         AG4       TYPICAL DETAILS       OF MASE: SCALE       PHASE:		WATER BANK – EAST SID CANAL McMULLIN GSA RESNO COUNTY, CA GENERAL COVER
LD9     TYPICAL DETAILS     DATE: 3/26/21       AGRICULTURAL     JOB NO: 256920002       AG1     SITE DETAILS     PROJECT NO:       DATE     AG2     CANAL PLAN AND PROFILE     PHASE:       AG3     CANAL CROSS SECTIONS     Q     1"       AG4     TYPICAL DETAILS     ORIGINAL SCALE SHOWN IS     ORIGINAL SCALE SHOWN IS	SHEET NO.DESCRIPTIONCENERALG1COVER SHEETG2ABBREVIATIONS & SYMBOLSG3INDEX SHEETLAND DEVELOPMENTLD1LD1HORIZONTAL CONTROLLD2GRADING PLANLD3UTILITY PLANLD4PARKING LOTLD5PIPELINE PLAN AND PROFILELD6STREET CONSTRUCTIONLD7ROAD SUPERELEVATION DIAGRAM	
DATE ST2 STRUCTURAL DETAILS SHEET G1	LD9 TYPICAL DETAILS AGRICULTURAL AG1 SITE DETAILS AG2 CANAL PLAN AND PROFILE AG3 CANAL CROSS SECTIONS AG4 TYPICAL DETAILS STRUCTURAL	PAD           DATE: 3/26/21           JOB NO: 255920002           PROJECT NO:           PHASE:           Q1"           ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FOR REDUCED OF ENLARGED PLANS.

ABBREVIATIO	vs					LINETYPES			
AB AC	AGGREGATE BASE ASPHALT CONCRETE	HORIZ HP	HORIZONTAL HINGE POINT, HIGH POINT, HORSEPOWER	TC TCE	TOP OF CURB TEMPORARY CONSTRUCTION EASEM	AFNT EXISTING	LINETYPI	E	DESCRIPTION
ACP AD	ASBESTOS-CEMENT PIPE ALUMINUM DISK	HP GAS HPS	HIGH PRESSURE GAS HIGH PRESSURE SWITCH	TDI TELE	TENSILE DUCTILE IRON TELEPHONE				WATER LEVEL
AGG AH	AGGREGATE AHEAD	HR H/T	HANDRAIL HUB & TACK	TF TFC	TOP OF FOOTING TOP FACE OF CURB				BARRICADE
	ALTERNATE ANGLE POINT	HŴL	HIGH WATER LEVEL	TG TH	TOP OF GRATE THREAD	123		123	CONTOUR (DEPRESSION)
APPROX	APPROXIMATE	HYDRO ID	HYDROPNEUMATIC INSIDE DIAMETER	TL	TOP OF LINING	IZJ			CONTOUR (MAJOR) CONTOUR (MINOR)
APN ARV	ASSESSOR'S PARCEL NUMBER AIR RELIEF VALVE	IN INV	INCH INVERT	TOE TOP	TOE OF SLOPE TOP OF SLOPE	· · · ·	- ·		EMBANKMENT TOE
ASTM AV	AMERICAN SOCIETY FOR TESTING AND MATERIALS AIR VENT	IP IRR	IRON PIPE IRRIGATION	TP TR	TELEPHONE POLE TELEPHONE RISER				EMBANKMENT TOP FENCE (BLOCK WALL)
AVE AWWA	AVENUE AMERICAN WATER WORKS ASSOCIATION	JP LBS	JUNCTION POLE POUNDS	TRANS TRFC	TRANSFORMER TRAFFIC	 0			FENCE (CHAIN LINK)
BAR BC	BARRIER BEGIN CURVE	LC LCW	LENGTH OF CURVE LONG CRESTED WEIR	TS TSB	TOP OF STRUCTURE TELEPHONE SPLICE BOX			O	FENCE (WOOD)
BD BFP	BRASS DISK BACKFLOW PREVENTER	LF LG	LINEAR FEET LONG	TYP TWL	TYPICAL TOP OF WALL	xx		××	FENCE (WRE)
BK BLDG	BACK BUILDING	LT LPG	LEFT LIQUEFIED PETROLEUM GAS	UG UP	UNDERGROUND UTILITY POLE	SF		SF	FENCE (SILT)
BM BO	BENCHMARK BOLLARD	MAX	MAXIMUM MAILBOX	UT	UTILITY UPSTREAM				GATE SWING GRADE BREAK
BTM BVC	BOTTOM BEGIN VERTICAL CURVATURE	MCC	MOTOR CONTROL CENTER MANUFACTURER	U/S VCP VERT	VERIFIED CLAY PIPE VERTICAL	0 0 0 0	0 0	<del>0 0 0 0 0</del>	GUARDRAIL
BW BWL	BACK OF WALL	MH MIN	MANHOLE	VG VLT	VALLEY GUTTER VAULT			-++++++++++++++++++++++++++++++++++++++	RAILROAD
BWR	BARB WIRE	MISC	MISCELLANEOUS	VLV	VALVE				RETAINING WALL
C, CONC CA	CONCRETE CALIFORNIA	MJ MN	MECHANICAL JOINT MAG NAIL	(W) W	WEST WATER			· · · <b></b>	SWALE CENTERLINE SWALE W/FLOW ARROWS
CAB CBL	CABINET CABLE	MP MPT	MEDIUM PRESSURE GAS LINE MALE PIPE THREAD	WL WM	WATER LINE WATER METER				WATER (LAKE/POND)
CFS C&G	CUBIC FEET PER SECOND CURB & GUTTER	MRKR MS	MARKER MILD STEEL	WS WV	WATER SERVICE WATER VALVE				WATER (MARSH/SWAMP)
CHK CHLK	CHECK CHAIN LINK	(N) NAVD	NORTH NORTH AMERICAN VERTICAL DATUM	ww w/	WASTE WATER WITH	c/c		XX 0/0 XX" ELEC (AERIAL)	COMPUTER/COMM. (BURIED)
CI CIP	CAST IRON CAST IRON PIPE	NC NGVD	NORMALLY CONSOLIDATED NATIONAL GEODETIC VERTICAL DATUM	w/o	WITHOUT	E		XX" ELEC (BURIED)	ELECTRIC (AERIAL) ELECTRIC (BURIED)
CIPCP CL	CAST-IN-PLACE CONCRETE PIPE CLASS	NIC	NOT IN CONTRACT NATIONAL PIPE THREAD			F0		XX" F0	FIBER-OPTIC
CLVT	CULVERT CENTERLINE	NTS OC	NOT TO SCALE ON CENTER			G		XX" GAS XX" IRR	GAS
CLF CLR	CHAIN LINK FENCE CLEAR, CLEARANCE	OD OH	OUTSIDE DIAMETER OVERHEAD			IRR		XX" OIL	IRRIGATION OIL
CMLC CMP	CEMENT MORTAR LINED & COATED	OP	OPERATING			s		XX" SS	SANITARY SEWER
CN	CORRUGATED METAL PIPE CONCRETE NAIL	OSHA O&M	OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION OPERATIONS & MAINTENANCE			FM		XX" FM XX"	SANITARY SEWER FORCE MAIN
CNS CO	COMPACTED NATIVE SOIL SEWER CLEAN OUT	(P) PB	PROPOSED PULL BOX					XX" SI	SANITARY SEWER LATERAL
CONT CONST	CONTINUOUS CONSTRUCT/CONSTRUCTION	PC PCC	POINT OF CURVATURE POINT OF COMPOUND CURVATURE			S I		XX" STEAM	SIGNAL INTERCONNECT (BURIED) STEAM
COR CORP	CORNER	PCC PE PER	PORTLAND CEMENT CONCRETE PERMANENT EASEMENT					XX" SD	STORM DRAINAGE
COL COUP	COLUMN COUPLING	PER PI	PERIMETER POINT OF INTERSECTION			T		XX" TELE (AERIAL) XX" TELE (BURIED)	TELEPHONE (AERIAL)
CP	CONTROL POINT CROWN	PIP PLC	PLASTIC IRRIGATION PIPE PROGRAMMABLE LOGIC CONTROLLER			T		XX" TV (AERIAL)	TELEPHONE (BURIED)
CR CU CY	CUBIC CUBIC YARDS	PNL	PROPERTY LINE PANEL			TV		XX" TV (BURIED)	TELEVISION (AERIAL LINE) TELEVISION (BURIED LINE)
DA DEC	DRIVE APPROACH DECIDUOUS	POC POL	POINT ON CURVE POINT ON LINE			W		XX" W	WATER
DEMO	DEMOLISH/DEMOLITION	POT	POINT ON TANGENT						CENTERLINE
DI DIA, Ø	DROP INLÉT DIAMETER	PP PRC	POWER POLE POINT OF REVERSE CURVATURE						EASEMENT MEANDER LINE
DIM DIP	DIMENSION DUCTILE IRON PIPE	PRV PSF	PRESSURE REDUCING VALVE POUNDS PER SQUARE FOOT						PROPERTY LINE
D/S DW	DOWNSTREAM DRIVEWAY	PSI PT	POUNDS PER SQUARE INCH POINT OF TANGENCY						RESERVATION/PARK/FOREST
DWG (E)	DRAWNG EXISTING, EAST	PVC PVCC	POLYVINYL CHLORIDE POINT OF VERTICAL COMPOUND CURVATURE						RIGHT-OF-WAY
ÉÁ	EACH END CURVE	PVMT PVRC	PAVEMENT POINT OF VERTICAL REVERSE CURVATURE					<u></u>	RELINQUISH ACCESS LINE SECTION LINE
EC ECC EF	ECCENTRIC EACH FACE	PVI R	POINT OF VERTICAL INTERSECTION RADIUS						STATE/COUNTY/CORPORATE LIMIT
ËG EL, ELEV	EXISTING GRADE ELEVATION	RBR RC	REBAR RADIUS OF CURVE						REVISION CLOUD
ELC ELEC	EPOXY LINED & COATED ELECTRIC	RCP RD	REINFORCED CONCRETE PIPE RELATIVE DENSITY						SAWCUT LINE DEMO LINE
ELL EM	ELBOW ELECTRIC METER	RD RE	ROAD REFERENCE			114 701/50		••••••••••••••••••••••	WORK LIMITS
EOL	END OF LINE	REQD RET	REQUIRED RETURN			HATCHES			
EP EQUIV	EDGE OF PAVEMENT EQUIVALENT	REV RGRCP	REVISION RUBBER GASKETED REINFORCED CONCRETE PIPE			EXISTING	HATCH TY	PE NEW	DESCRIPTION
ESMT EUC	EASEMENT EUCALYPTUS ENDATED TOAL OUD/F	RGS RP	RIGID GALVANIZED STEEL RIGID GALVANIZED STEEL RADIUS POINT						
EVC EW	END VERTICAL CURVE EACH WAY	RR RT	RADUS POINT RAILROAD RIGHT						AGGREGATE
EXP (F)	EXPOSED FUTURE	RTU	REMOTE TERMINAL UNIT			Contract - Autors			
F&I FD	FURNISH & INSTALL FOUND	R/W (S) S	RIGHT OF WAY SOUTH, SOLVENT WELD						AC PAVEMENT
FDC FF	FIRE DEPARTMENT CONNECTION FINISHED FLOOR	S=	SLIP SLOPE						
FG FH	FINISHED GRADE FIRE HYDRANT	SCH SCP	SCHEDULE STANDARD CONCRETE PIPE			e, 14		4	CONCRETE
₩Ĺ,FL FLG	FLOW LINE FLANGE	SD SDMH	STORM DRAIN STORM DRAIN MANHOLE						CONCRETE LINING (PLAN VIEW)
FLGD FM	FLANGED FORCE MAIN	SEC SERV	SECTION SERVICE						CONTRACT LINING (FLAIN VIEW)
FM FNC FRP	FENCE FENCE FIBER REINFORCED POLYESTER PIPE	SF	SQUARE FEET SERVICE POLE						5407U
FT	FOOT/FEET	SPEC SPNDL	SPECIFICATION SPINDLE						EARTH
FW FWL	FRONT OF WALK FACE OF WALL	SQ SS	SPINDLE SQUARE SANITARY SEWER						
GA GAL	GAUGE GALLON	SS OR STS	STAINLESS STEEL			203		1 de la companya de la compan	RIP RAP
GALV GB	GALVANIZED GRADE BREAK	SSMH STA	SANITARY SEWER MANHOLE STATION STANDARD						SAND
GM GPM	GAS METER GALLONS PER MINUTE	STD STL	STANDARD STEEL						SAND
GRVL GS	GRAVEL GAS	STP STRC	STAND PIPE STRUCTURE						
GSV GUY	GAS VALVE GUY WIRE	STRP SWL	STRIPING SWALE						GRATING
GV HD	GATE VALVE HEAD	STWL (T)	STILLING WELL THREADED						EXPANDED METAL
HD HDPE HDR	HIGH DENSITY POLYETHYLENE	T T&B	THREAD TOP & BOTTOM						EAFANDED METAL
HDW	HEADER HEADWALL	TB	TOP OF BANK TEMPORARY BENCHMARK						
HGL	HYDRAULIC GRADE LINE	1.51							


SYME	BOLS		ED Croup.
	SYMBOL	DESCRIPTION	<u>HARD</u> <u>RESER</u> we conyr sise plan first ob first ob
EXISTIN	IG NEW		k PRIT A CHART A CHART Find the char
۲	•	ELECTRIC METER	VOST & ALL - ALL - A
		PAD MOUNTED TRANSFORMER	<u>P PRO</u> P INC P INC P PRO P PR
E		ELECTRIC VAULT	2021 b 5 GROU 5 GROU 5 Frows 1 to th of t
ب م			RIGHT EFERING signed for a gappics ing throrized point cing th
	÷		COPY FINGIN Pritch and plans of Group
©	©	ELECTRIC MANHOLE	
Ø		GAS METER	DATE
¢	DI	GAS VALVE	
	•	SANITARY SEWER CLEAN OUT	S 🗎
S	-	SANITARY SEWER MANHOLE	
_	•	SSMH (ECCENTRIC CONE)	ly N = 1
		STORM DRAIN CATCH BASIN	LIMINARY CONSTRU 3/26/21
°=		STORM DRAIN INLET	Sec. M
, 		STORM DRAIN CULVERT	
D		STORM DRAIN MANHOLE	PREI -OR (
	-	MAIL BOX	
л ~	<b>⊥</b> ∵	SIGN	
×	×	YARD LIGHT	
•	•	GUARD POST	
Δ		CONTROL POINT	Ś
+	÷	BENCH MARK	
0	•	IRON PIPE	
•	0	MONUMENT	FOLEW
۵		MONUMENT (OPTIONAL)	
		OWNERSHIP TIE	
(NO.	) (NO.)	LOT NUMBER	
		TELEPHONE RISER	
LT		TELEPHONE VAULT	SIDE
A	<b>A</b>	2-NOZZLE HYDRANT	
- -	<b>●</b>	3-NOZZLE HYDRANT	EAST
60	(D)	FIRE DEPT. CONNECTION	
F	F	FIRE VAULT	ANK – L GSA NTY, CA AL AL
<b></b>		WATER METER	- NNK - GSA LTY, C L ZEVIZ
6	W	WELL	BBF ERA
8	0	WATER VALVE	N WATER BA CANAL McMULLIN FRESNO COUL GENERA GENERA MBDI
م	ہ مہ	BLOW-OFF	McM McM
ද BFP	_ <b>₽</b> 3 <b>653</b>	AIR RELIEF VALVE	
	BFP A	BACK FLOW PREVENTOR	
8	8	GATE VALVE HANDLE	AQUATERRA WATER CAN McMULL FRESNO O GENI LEGEND & AB
Ŀ	$\square$	STILLING WELL	NA I
	· ·	FENCE POST	AQ
/	i /i	FENCE GATE	
		DEMOLON	
	<u>/xxx</u>	REVISION	PART 1 SHIFT
	$\langle \mathbf{x} \rangle$	CONSTRUCTION CALLOUT	
(# SHT	DETAIL NUMBER SHEET NUMBER	DETAIL CALLOUT	AQUATER BAL ACTIONAL SCREEP AND IN CONSTANT AND
	_/_	LINE BREAK	
	}	PIPE END (SCHEMATIC)	DESIGN ENGINEER:
	8	PIPE END	LYNN GROUNDWATER
Y	Y		C
		EMBANKMENT ARROW	DRAFTED BY: CHECKED BY: PAD
			DATE: 3/26/21
$\nabla$	HWL= XXX.XX	HIGH WATER LINE	JOB NO: 256920002
=	-		PHASE:
(E) XX XX	x.xx 🔨 xx xxx.xx	SPOT ELEVATION	ORIGINAL SCALE SHOWN IS
		JEUT LLEVATION	ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FOR REDUCED OR ENLARGED PLANS.
$\wedge$		SECTION VIEW	SHEET G2
			OF
			<sup></sup>








TYPICAL CROSS SECTION - EAST SIDE CANAL ALIGNMENT


Detection 1.2011. De PRODUCT & Ref (DELARD) DEMERRING (SOUP INC, ALL BICHTS, EEEROLD The more from controls and the Bichts EEEROLD The expressive sets and the expressive and the control of the other applicable preserves its common due controlled the plants are not to be reproduced, changed, or copied in any form remain whitever, for one rely to be assigned to a third porty without first outdring the existence of these plants of the event of the retring pressive and control of the event of the third porty shell hold the firm of Provids & Prictoric Engineering Occup, first, in the event of which the event of the third porty shell hold the firm of Provids & Prictoric Engineering Occup, first, more set and peer the cost of Provids & Prictoric Engineering Occup, first, more and and peer the cost of Provids & Prictoric Engineering and peer the cost of Provids & Prictoric Briteria and and peer the cost of Provids & Prictoric Briteria and Pr	<ul> <li>Uroup, Inc. s legal rees associated with defending and enforcing these rights.</li> </ul>
TION	BY DATE
PRELIMINARY NOT FOR CONSTRUCTION 3/26/21	REVISION
	No.
FOR THE A	
ATER BAN CANAL CANAL McMULLIN GS SNO COUNTY GENERAL	TYPICAL CROSS SECTION
A CONTRACT C	
PAD DATE: 3/26/21 JOB NO: 256920002 PROJECT NO: PHASE: 0, , , 1"	BY:
ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE F	GR NS.
























1112+00	1120+00	1130+00
210		
	DP 206.00	
200		EG
200		
190	V 195.50	
_190		
180		







































gwb























Detection 1.2011. De PRODUCT & Ref (DELARD) DEMERRING (SOUP INC, ALL BICHTS, EEEROLD The more from controls and the Bichts EEEROLD The expressive sets and the expressive and the control of the other applicable preserves its common due controlled the plants are not to be reproduced, changed, or copied in any form remain whitever, for one rely to be assigned to a third porty without first outdring the existence of these plants of the event of the retring pressive and control of the event of the third porty shell hold the firm of Provids & Prictoric Engineering Occup, first, in the event of which the event of the third porty shell hold the firm of Provids & Prictoric Engineering Occup, first, more set and peer the cost of Provids & Prictoric Engineering Occup, first, more and and peer the cost of Provids & Prictoric Engineering and peer the cost of Provids & Prictoric Provids & Prictoric & Provids & Prictoric & Provids & Prictoric & Pric	whoup, mer s regar rees associated with deteriaing and enforcing these rights.
N	BY DATE
PRELIMINARY NOT FOR CONSTRUCTION 3/26/21	REVISION
	No.
FOR FURT	
	SIA 1336+00 IO SIA 1356+00
EXT - 3 911-36 EXT - 3 911-36 PRITCHARD BRITCHARD A FROME AROUP A FROME	_
	BY:
PROJECT NO: PHASE: 01"	
ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FI REDUCED OR ENLARGED PLAN SHEET <b>PP13</b>	DR NS.
OF	











1384	4+00	1390+00	1400+00	
220				
	-ТОР	210.20	EG	
200				
		99.70		
180				
160				

































Coprotect accords the RADIOLST is the RADIOL State RADIOL RADIO RADIOL RADIOR RADIO RA	DATE enforcing these rights.
	BY DATE
PRELIMINARY NOT FOR CONSTRUCTION 3/26/21	REVISION
	No.
FOR HIN A	
AQUATERRA WATER BANK – EAST SIDE CANAL McMULLIN GSA FRESNO COUNTY, CA PLAN & PROFILE	SIA 1496+00 IO SIA 1516+00
DESIGN ENGINEER: LICENSE TAUK DRAFTED BY: PAD DATE: 3/26/21 JOB NO: 256920002	
PROJECT NO: PHASE: ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FI REDUCED OR ENLARGED PLAN SHEET PP19	DR NS.




1516+00	1520+00	 1530+00	
220			
TOP 207.30			
200		 	
INV 196.80			
180			
160			














1572+00	1580+00	15	90+00	
220				
,─TOP 207.30				
		EG		
200				
200				<u> </u>
-INV 196.80				
180				<u> </u>
				<u> </u>
160				<u> </u>






















Representation of the set of the	<ul> <li>Group, Inc.'s legal fees associated with defending and enforcing these rights.</li> </ul>
	DATE
NOIL	ΒY
PRELIMINARY NOT FOR CONSTRUCTION 3/26/21	REVISION
	No.
FOR THE A	
ERRA WATER B CANA McMULLIN FRESNO COLU PLAN & P	STA 1656+00 TO STA 1665+02
DESIGN ENGINEER:	0 009/449-2/00 FAX 009/449-2/10 www.ppeng.com
	R BY:
PAD DATE: 3/26/21 JOB NO: 256920002	
PROJECT NO: PHASE: 01"	
ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE F REDUCED OR ENLARGED PLA	or NS.
SHEET PP25	




Corpetition 2010 Constrained and Constrained and Constrained and Property Spring and Constrained Const	enforcing these rights.
	DATE
PRELIMINARY NOT FOR CONSTRUCTION 3/26/21	BY
PRELIMINARY NOT FOR CONSTRUC 3/26/21	REVISION
	No.
FOR IN T	
AQUATERRA WATER BANK – EAST SIDE CANAL McMULLIN GSA FRESNO COUNTY, CA STRUCTURAL	PUMP STATION
ETTER STATE PROVOST& PRITCHARD CONSULTING STOLF SAFEDIOPE OF COMPACT SECON CONTRACTOR SECON CONT	www.bbeug.com
LYNN GROUNDWATEF LICENSE NO:  DRAFTED BY: CHECKED E	२ ३४:
PAD DATE: 3/26/21 JOB NO: 256920002	
	OR NS.
SHEET S1	


6/2021 6:16 PM G: \McMullin GSA-2659/2659 On-going/CAD/340 Sheet Sets/03\_Structural/East Side Canal/S1 PUMP STATION.dwg -PHillip Dansb;





AQUATERRA WATER BANK - EAST SIDE CANAL McMULLIN GSA FRESNO COUNTY, CA	DETAILS CONSTRUCTION DETAILS	
DESIGN ENGINEE LYNN GRO LICENSE NO: 	R: UNDWATER CHECKED BY 26/21 9920002 	




#### SECTION VIEW - ROADWAY ALL DIMENSIONS ALONG CENTERLINE OF PIPELINE









# D1

#### PLACEMENT OF SPACERS ON CARRIER PIPE

- GENERAL ONE SPACER SHALL BE PLACED NOT MORE THAN TWO FEET FROM EACH END OF CASING. SUBSEQUENT SPACERS SHALL BE PLACED AT 6' INTERVALS WITHIN THE CASING, OR IN ACCORDANCE WITH PIPE MANUFACTURERS RECOMMENDATIONS.
- FOR ALL CARRIER PIPE, ONE SPACER SHALL BE PLACED ON THE SPIGOT END OF EACH SEGMENT AT THE LINE MARKING THE LIMIT OF INSERTION INTO THE BELL WHEN THE JOINT IS COMPLETE, THE SPACER SHALL BE IN CONTACT WITH THE BELL OF THE JOINT SO THAT 2. THE SPACER PUSHES THE JOINT AND RELIEVES COMPRESSION WITHIN THE JOINT. SUBSEQUENT SPACERS SHALL BE PLACED AT 6'-10' INTERVALS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

#### CARRIER PIPE

1. CARRIER PIPE SHALL BE CENTERED WITHIN CASING BY USING OF ONE OF THESE METHODS:

WOOD SKIDS PRESSURE TREATED #2 DF 2XS, #3 REDWOOD 2XS

MANUFACTURED SPACERS

### CASING SPACERS AS MANUFACTURED BY ONE OF THE FOLLOWING ADVANCE PRODUCTS & SYSTEMS, INC.; CCI PIPELINE SYSTEMS; PUBLIC WORKS MARKETING, INC.; PIPELINE SEAL & INSULATOR, INC.; OR APPROVED EQUAL

#### BLOWN SAND

1. CASING SHALL BE FILLED WITH BLOWN SAND AFTER INSTALLATION OF CARRIER PIPE

CASING END SEALS

1. CASING END SEALS SHALL BE SEALED BY USING ONE OF THESE METHODS:

RUBBER SEALS WRAP AROUND, NEOPRENE RUBBER, MIN. THICKNESS:1/8"; TEMPERATURE RATING: -20°F TO 170°F.

STEEL BAND STAINLESS STEEL BANDING; MIN. 2 BANDS PER SEAL; T304 STAINLESS STEEL WITH 100% NON-MAGNETIC WORM GEAR, 1/2" MIN. WIDTH.

#### BORE AND RECEIVING PIT NOTES

- 1. THE [AGENCY] HAS OBTAINED IT'S PORTION OF A [AGENCY] ENCROACHMENT PERMIT. THE CONTRACTOR SHALL OBTAIN HIS PORTION OF THE [AGENCY'S] PERMIT (NO PERMIT FEE) PRIOR TO PERFORMING ANY WORK WITHIN THE IAGENCY'SI RIGHT OF WAY.
- 2. ALL WORK WITHIN THE [AGENCY'S] RIGHT OF WAY SHALL BE IN CONFORMANCE WITH [AGENCY'S] ENCROACHMENT PERMIT REQUIREMENTS.
- 3. BORE AND RECEIVING PITS SHALL BE LOCATED 5 FEET (MINIMUM) OUTSIDE OF [AGENCY'S] RIGHT OF WAY.
- 4 IF THE AGENCY IS CALTRANS: THE BORE AND RECEIVING PITS ARE LINDER STATE OF AND RECEIVING PITS ARE THE CONTRACTOR'S RESPONSIBILITY SUBJECT TO CALTRANS APPROVAL.
- 4. IF THE AGENCY IS NOT CALTRANS:SIZE AND LOCATION OF BORE AND RECEIVING PITS ARE THE CONTRACTOR'S RESPONSIBILITY SUBJECT TO [AGENCY'S] APPROVAL.
- 5. ACCESS TO THE BORE AND RECEIVING PITS SHALL ONLY BE FROM THE CONSTRUCTION EASEMENTS OBTAINED BY [AGENCY]. THE PARKING OF EQUIPMENT AND/OR MATERIALS SHALL NOT BE WITHIN 20' OF THE ROADWAY LANES.
- 6. BORE AND RECEIVING PITS SHALL BE ADEQUATELY FENCED AND/OR HAVE A TYPE-K BARRIER PLACED AROUND THEM.
- 7. BORE AND RECEIVING PITS SHALL BE ADEQUATELY SHORED IN ACCORDANCE WITH CAL OSHA REQUIREMENTS
- 8. SHORING PLANS, SIGNED BY A REGISTERED ENGINEER, SHALL BE SUBMITTED AND APPROVED BY [AGENCY] BEFORE EXCAVATING.
- 9. CASING PIPE MAY BE NEW OR USED STEEL PIPE WITH A MINIMUM YIELD STRENGTH OF 36,000 PSI. (ASTM A36). USED STEEL PIPE SHALL BE PRE-APPROVED BY [AGENCY'S] BEFORE INSTALLATION.
- 10. CASING PIPE MAY BE SPIRAL WELDED PIPE PROVIDED THE PIPE IS NEW AND THE WELD IS SMOOTH
- 11. ALL CASING LENGTHS SHALL BE EQUAL TO THE AUGER LENGTH.
- 12. ALL CASING JOINTS WELDED IN THE FIELD SHALL BE FULLY WELDED AROUND THE CIRCUMFERENCE OF THE PIPE WITH COMPLETE PENETRATION WELD.
- 13. [AGENCY] SHALL SET AND CHECK A SURVEY GRID PER [AGENCY'S] APPROVED ENCROACHMENT PERMIT. CONTRACTOR SHALL PRESERVE ALL MONUMENTS ASSOCIATED WITH SURVEY GRID.

PPNG							
	AQUATERRA WATER BANK – EAST SIDE	CANAL	McMULLIN GSA	FRESNO COUNTY, CA	DETAILS	CONSTRUCTION DETAILS	
	DR4	LYI ENSE PAFTEI PAI JOB JECT PH QUCE	NN NO D B D ATE: NO: ASE:		CHECK 26/21 59200 E SHO	ED BY:	

## Appendix G – Project Capital Costs



#### PRELIMINARY ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST



#### McMullin Area Groundwater Sustainability Agency Aquaterra Water Bank Planning/Conceptual Level Costs

Item				1		APF	RIL 2022 DRAFT
No.	Item Description	Quantity	Unit		Unit Price		Amount <sup>/3</sup>
ONST	RUCTION COSTS						
	400 cfs Jensen Canal						
1	Mendota Pump Station (200 cfs)	1	LS	\$	4,520,000	\$	4,520,00
	James Bypass Mendota Pump Station (150 cfs)	1	LS	\$	3,390,000		3,390,00
	MVWD Mendota Pump Station (150 cfs)	1	LS	\$	3,390,000		3,390,00
2	Intermediate Pump Stations (5-bay, 500 cfs, 400 hp pumps)	3	LS	\$	9,991,667		29,975,00
3	Land Clearing (150-ft wide easement, 13.5 miles)	245	AC	\$	2,500	\$	614,00
4	Earthwork	630,000	CY	\$	10		6,300,00
5	Farm Road Crossings (box culvert)	18	EA	\$	334,000		6,012,00
6	Paved County Road Crossing (James Rd; Bore and Jack 3, 96" RCP for 160')	480	LF	\$	3,200		1,536,00
7	Remove/Replace Grower Turnout	8	EA	\$	40,000		320,00
8	Relocation of Wells/Filter Stations	10	EA	\$	250,000		2,500,00
					Subtotal		58,557,00
	500 cfs East Side Canal						,,
9	Land Clearing (150-ft wide canal easement, 32.4 miles)	589	AC	\$	2,500	\$	1,473,00
10	Earthwork	1,500,000	CY	\$	10		15,000,00
11	Intermediate Pump Stations (10-bay, 500 cfs, 125 hp pumps)	5	LS	\$	9,991,667		49,959,00
11	Farm Road Crossings (box culvert)	25	EA	\$	334,000		8,350,00
	Paved County Road Crossings (Jensen, American, Bore and Jack, 3, 96" RCP for 100'						
12	each)	600	LF	\$	3,200	\$	1,920,00
13	Railroad Crossing (Bore and Jack, 3, 96" RCP for 130')	390	LF	\$	3,200	\$	1,248,00
14	Hwy 180 & Hwy 145 Crossing (Bore and Jack, 3, 96 RCP for 220')	1,320	LF	\$	3,200		4,224,00
15	Relocation of Wells	2	EA	\$	250,000		500,00
		-	27	Ŷ	Subtotal		82,674,00
	400 cfs American Canal				oubtotai	Ψ	02,014,00
16	Placer Rd Pump Station	1	LS	\$	9,040,000	\$	9,040,00
17	Intermediate Pump Stations (8-bay, 400 cfs, 125 hp pumps)	3	LS	\$	7,993,000		23.979.00
18	Land Clearing (150-ft wide easement, 10.8 miles)	196	AC	\$	2,500		491,00
19	Earthwork	500,000	CY	\$	10		5,000,00
20	Farm Road Crossings (box culvert)	41	EA	\$	334,000		13,694,00
20	Paved Road Crossing (open cut, 3, 72" RCP barrels, 100' length)	5	EA		250,000		1,250,00
21	Paved Road Crossing (open cut, 3, 72 RCP barrels, 100 length) Paved County Road Crossings (3 crossings, Bore and Jack, 3, 72" RCP for 120')	1,080	LF	\$ \$	2,400		2,592,00
22	Canal Crossing (Bore and Jack, 3, 72" RCP for 130')	390		э \$	2,400		2,592,00
23	Hwy 145 Crossing (Bore and Jack, 3, 72" RCP for 130)	660		\$	2,400		1,584,00
24	Hwy 145 Crossing (Bore and Jack, 3, 72 RCP tor 220)	000	LF	¢	Subtotal		58,566,00
-	300 cfs Siskiyou Ave Canal				Subtotal	φ	50,500,000
25	Land Clearing (150-ft wide canal easement, 4.9 miles)	89	AC	\$	2,500	¢	223,00
26	Earthwork	230,000	CY EA	\$	10		2,300,00
27 28	Farm Road Crossings (box culvert) Intermediate Pump Stations (6-bay, 300 cfs, 125 hp pumps)	9	LS	\$ \$	334,000		3,006,00
28	Intermediate Pump Stations (6-bay, 300 cis, 125 np pumps)	3	LS	\$	5,995,000		17,985,000
	M-Mullin Europeien				Subtotal	Þ	23,514,00
	McMullin Expansion		1.0	•	10 000 000	٠	40,000,00
29	McMullin Expansion Project Cost	1	LS	\$	40,000,000		40,000,00
	Desta Mart				Subtotal	Þ	40,000,00
	Basin Work	20		•			
20	75 cfs Canal Turnouts, Discharge Pipe, Metering Stand					¢	
30		32	EA	\$	317,000		10,144,00
30 31	40 Acre Basin	96	EA EA	\$ \$	655,000	\$	62,880,00
	40 Acre Basin					\$	
31	40 Acre Basin Extraction Facilities	96	EA	\$	655,000 Subtotal	<del>())</del>	62,880,00 <b>73,024,00</b>
	40 Acre Basin				655,000 Subtotal 1,000,000	69 <b>69</b> 69	62,880,00 <b>73,024,00</b> 87,000,00
31	40 Acre Basin Extraction Facilities Extraction Wells (5.5 cfs per extraction well)	96	EA	\$	655,000 Subtotal	69 <b>69</b> 69	62,880,00 <b>73,024,00</b> 87,000,00
31 32	40 Acre Basin Extraction Facilities Extraction Wells (5.5 cfs per extraction well) Monitoring Facilities	96	EA	\$	655,000 Subtotal 1,000,000 Subtotal	\$ \$	62,880,00 73,024,00 87,000,00 87,000,00
31 32 33	40 Acre Basin  Extraction Facilities Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well	96 87 50	EA EA EA	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000	\$\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00
31 32	40 Acre Basin Extraction Facilities Extraction Wells (5.5 cfs per extraction well) Monitoring Facilities	96	EA	\$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00 500,00
31 32 33	40 Acre Basin  Extraction Facilities Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well	96 87 50	EA EA EA	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00 500,00
31 32 33 34	40 Acre Basin Extraction Facilities Extraction Wells (5.5 cfs per extraction well) Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well General Conditions <sup>74</sup>	96 87 50 5	EA EA EA EA	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00 500,00 1,750,00
31 32 33	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>14</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits	96 87 50	EA EA EA EA LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00 1,750,00 21,250,00
31 32 33 33 34	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection	96 87 50 5	EA EA EA EA	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00 1,750,00 21,250,00
31 32 33 34 35	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>14</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits	96 87 50 5 5%	EA EA EA EA LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 1,250,00 500,00 1,750,00 21,250,00 2,130,00
31 32 33 34 35 36	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection	96 87 50 5 5 5% 0.5%	EA EA EA EA LS LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 1,250,00 500,00 1,750,00 21,250,00 2,130,00 12,750,00
31 32 33 34 35 36 37 38	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>/4</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation	96 87 50 5 5% 0.5% 3% 0.5%	EA EA EA EA EA LS LS LS LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	S     S       S     S	62,880,00 73,024,00 87,000,00 1,250,00 500,00 1,750,00 21,250,00 2,130,00 2,130,00 2,130,00
31 32 33 34 35 36 37	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions' <sup>4</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations	96 87 50 5 5% 0.5% 3%	EA EA EA EA EA LS LS LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00 21,250,00 2,130,00 2,130,00 2,130,00 8,500,00
31 32 33 34 35 36 37 38 39	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation	96 87 50 5 5% 0.5% 3% 0.5% 2%	EA EA EA EA EA LS LS LS LS LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal	(4)     (4)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (6)     (5)       (7)     (5)	62,880,00 73,024,00 87,000,00 1,250,00 1,750,00 21,250,00 2,130,00 12,750,00 2,130,00 2,130,00 2,130,00 2,130,00 2,130,00
31 32 33 34 35 36 37 38 39	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation	96 87 50 5 5% 0.5% 3% 0.5% 2%	EA EA EA EA EA LS LS LS LS LS	\$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000	S     S       S <td>62,880,00 73,024,00 87,000,00 1,250,00 1,750,00 21,250,00 2,130,00 12,750,00 2,130,00 2,130,00 2,130,00 2,130,00 2,130,00</td>	62,880,00 73,024,00 87,000,00 1,250,00 1,750,00 21,250,00 2,130,00 12,750,00 2,130,00 2,130,00 2,130,00 2,130,00 2,130,00
31 32 33 34 35 36 37 38 39	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation	96 87 50 5 5% 0.5% 3% 0.5% 2% 0.5%	EA EA EA EA EA LS LS LS LS LS LS LS	\$ \$ \$ \$ }	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal Subtotal	\$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$	62,880,00 73,024,00 87,000,00 1,250,00 1,250,00 2,1250,00 2,130,00 2,130,00 2,130,00 2,130,00 8,500,00 2,130,00 48,890,00
31 32 33 34 35 36 37 38 39	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation	96 87 50 5 5% 0.5% 3% 0.5% 2% 0.5%	EA EA EA EA EA LS LS LS LS LS LS LS	\$ \$ \$ \$ }	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal	(4)     (4)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (5)     (5)       (6)     (5)       (7)     (5)	62,880,00 73,024,00 87,000,00 1,250,00 1,250,00 2,1250,00 2,130,00 2,130,00 2,130,00 2,130,00 8,500,00 2,130,00 48,890,00
31 32 33 34 35 36 37 38 39 40	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation Traffic Control	96 87 50 5 5% 0.5% 3% 0.5% 2% 0.5%	EA EA EA EA EA LS LS LS LS LS LS LS	\$ \$ \$ \$ }	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal Subtotal	\$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$	62,880,00 73,024,00 87,000,00 1,250,00 1,250,00 2,1250,00 2,130,00 2,130,00 2,130,00 2,130,00 8,500,00 2,130,00 48,890,00
31 32 33 34 35 36 37 38 39 40	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation Traffic Control  DNSTRUCTION COSTS	96 87 50 5 5% 0.5% 0.5% 2% 0.5%	EA EA EA EA LS LS LS LS LS LS LS CONSTRUC	\$ \$ \$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal Subtotal	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 1,250,00 21,250,00 2,130,00 2,130,00 2,130,00 2,130,00 2,130,00 2,130,00 48,890,00 48,890,00
31 32 33 34 35 36 37 38 39 40	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well  Deep Monitoring Well  General Conditions <sup>14</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits  Worker and Public Protection  Miscellaneous Facilities and Operations  Dust Control Plan & Implementation SWPPP Plan & Implementation Traffic Control  NSTRUCTION COSTS Land Acquisition (Cost per 40 acre Basin)	96 87 50 5 5% 0.5% 2% 0.5% 2% 0.5%	EA EA EA EA LS LS LS LS LS CONSTRUC	\$ \$ \$ \$ U	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal Subtotal OSTS SUBTOTAL 800,000	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	62,880,00 73,024,00 87,000,00 1,250,00 1,250,00 2,130,00 2,130,00 2,130,00 2,130,00 2,130,00 8,500,00 2,130,00 48,890,00 425,085,00 76,800,00
31 32 33 34 35 36 37 38 39 40	40 Acre Basin  Extraction Facilities  Extraction Wells (5.5 cfs per extraction well)  Monitoring Facilities Shallow Monitoring Well Deep Monitoring Well  General Conditions <sup>74</sup> Mobilization/Demobilization, Bonds and Insurance and Construction Permits Worker and Public Protection Miscellaneous Facilities and Operations Dust Control Plan & Implementation SWPPP Plan & Implementation Traffic Control  DNSTRUCTION COSTS	96 87 50 5 5% 0.5% 0.5% 2% 0.5%	EA EA EA EA LS LS LS LS LS LS LS CONSTRUC	\$ \$ \$ \$ \$	655,000 Subtotal 1,000,000 Subtotal 25,000 100,000 Subtotal Subtotal	\$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$       \$     \$	62,880,00 73,024,00 87,000,00 87,000,00 1,250,00



#### PRELIMINARY ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST

#### McMullin Area Groundwater Sustainability Agency Aquaterra Water Bank

#### Planning/Conceptual Level Costs

PRELIMINARY
-------------

					A	PRIL 2022 DRAFT
ltem No.	Item Description	Quantity	Unit	Unit Price		Amount <sup>/3</sup>
44	Construction Easement Jensen Alignment (35-foot wide, both sides for 9 miles)	76	AC	\$ 5,000	) \$	382,000
45	Construction Easement East Side Canal (35-foot wide, both sides for 12.6 miles)	107	AC	\$ 5,000	) \$	535,000
46	Construction Easement James/American Alignment (35-foot wide, both sides for 10.8 miles)	92	AC	\$ 5,000	) \$	458,000
46	Data Collection & Design <sup>/5,8</sup>	8%	LS		\$	34,006,800
47	Permitting & Compliance <sup>/5,9</sup>	4%	LS		\$	17,003,400
48	Construction Management <sup>/5,10</sup>	8%	LS		\$	34,006,800
			NON-CONTSTRUCTION SUBTOTAL			172,727,000
				PROJECT TOTA	L \$	597,812,000
	Preliminary Level Overall Project Contigency /11	30	%	\$ 597,812,000	) \$	179,344,000
	Preliminary Level Overall Project Contigency /12	-20	%	\$ 597,812,000	) \$	(119,562,000)
		PREL	RELIMINARY COST W/ 30% CONTIGENCY			777,156,000
		PRELIMINARY COST W/ -20% CONTIGENCY				478,250,000

Notes & Assumptions:

<sup>/1</sup> This preliminary level estimate represents the opinion of probable cost based on the engineer's experience with prior projects and cost sources such as RS Means.

<sup>/2</sup> Costs presume work will be publically bid as a public works project.

<sup>/3</sup> Amount totals rounded up to the nearest one-thousand dollars.

<sup>/4</sup> Percentages are of the subtotal of the Construction Costs.

<sup>/5</sup> Percentages are sum of Field Costs & General Conditions.

<sup>/6</sup> Construction schedule may impact construction cost.

<sup>/7</sup> Based on the estimated number of landowners with realty actions.

<sup>18</sup> Data Collection & Design includes: survey, field investigations, geotechnical investigation, reporting & legal review, design, specifications and bidding.

<sup>19</sup> Permitting & Compliance includes: NEPA, CEQA, federal & state ESA, Air Pollution Control District, cultural resources, land clearances, mitigation measures & legal review.

Construction Mangement includes: construction admin & staking, bid award, field inspections, geotechnical, water quality monitoring, qa/qc & legal review, record documents and close out.
 Preliminary level contingency typically ranages from 20 to 50%.

<sup>/12</sup> Landowner turnouts were NOT included, but presumed to be put in by landowners at their expense at a later date.

<sup>/13</sup> District does not hold right-of-way on existing canal

<sup>/14</sup> Cost estimate assumes there will not be any export of dirt

## Appendix H – Special Status Plant and Animal Species List

Species	Status	Habitat		
American badger (Taxidea taxus)	CSC	Grasslands, savannas, and mountain meadows near timberline are preferred. Most abundant in drier open spaces of shrub and grassland. Burrows in soil.		
bank swallow (Riparia riparia)	CT	These aerial insectivores nest colonially in burrows constructed along vertical banks and bluffs near waterbodies. This disturbance tolerant species is also known to nest in man-made sites, such as quarries, mounds of gravel or dirt, and road cuts.		
lizard (Gambelia sila) CE, floors, large loamy subs there are a grass. Can on kangard shrubs, in si excavate s		Inhabits semi-arid grasslands, alkali flats, low foothills, canyon floors, large washes, and arroyos, usually on sandy, gravelly, or loamy substrate, sometimes on hardpan. Often found where there are abundant rodent burrows in dense vegetation or tall grass. Cannot survive on lands under cultivation. Known to bask on kangaroo rat mounds and often seeks shelter at the base of shrubs, in small mammal burrows, or in rock piles. Adults may excavate shallow burrows but rely on deeper pre-existing rodent burrows for hibernation and reproduction.		
burrowing owl (Athene cunicularia)	CSC	Resides in open, dry annual or perennial grasslands, deserts, and scrublands with low growing vegetation. Nests underground in existing burrows created by mammals, most often ground squirrels.		
California glossy snake (Arizona elegans occidentalis)	CSC	Inhabits arid scrub, rocky washes, grasslands, and chaparral. Prefers open areas with loose soil for easy burrowing.		
California horned lark (Eremophila alpestris actia)	CWL	Frequents open habitats, including short-grass prairie, mountain meadows, open coastal plains, fallow grain fields, and alkali flats. Found primarily in coastal regions, including Sonoma and San Diego Counties.		
California tiger salamander (Ambystoma californiense)	FT, CT, CWL	Requires vernal pools or seasonal ponds for breeding and small mammal burrows for aestivation. Generally found in grassland and oak savannah plant communities in central California from sea level to 1500 feet in elevation.		
coast horned lizard (Phrynosoma blainvillii)	CSC	Found in grasslands, coniferous forests, woodlands, and chaparral, primarily in open areas with patches of loose, sandy soil and low-lying vegetation in valleys, foothills, and semi-arid mountains. Frequently found near ant hills and along dirt roads in lowlands along sandy washes with scattered shrubs.		
(Bombus crotchii)		Occurs throughout coastal California, as well as east to the Sierra-Cascade crest, and south in to Mexico. Food plant genera include Antirrhinum, Phacelia, Clarkia, Dendromecon, Eschscholzia, and Eriogonum.		
Fresno kangaroo rat (Dipodomys nitratoides exilis)	FE, CE	An inhabitant of alkali sink open grassland environments in western Fresno County. Prefers bare, alkaline, clay-based soils subject to seasonal inundation with more friable soil mounds around shrubs and grasses.		

Table 1 Special Status Animals with Potential to Occur Onsite and/or in the Vicinity

Species	Status	Habitat	
giant gartersnake (Thamnophis gigas)	FT, CT	Occurs in marshes, sloughs, drainage canals, irrigation ditches, rice fields, and adjacent uplands. Prefers locations with emergent vegetation for cover and open areas for basking. This species uses small mammal burrows adjacent to aquatic habitats for hibernation in the winter and to escape from excessive heat in the summer.	
giant kangaroo rat (Dipodomys ingens)	FE, CE	Inhabits annual grassland communities with few or no shrubs and well-drained, sandy-loam soils on gentle slopes.	
longhorn fairy shrimp (Branchinecta longiantenna)	FE	Inhabits clear to turbid vernal pools or seasonally ponded areas.	
merlin (Falco columbarius)	CWL	Found throughout North America in habitats ranging from tidal estuaries to open woodlands and valley grasslands. Generally roosts in clumps of trees or windbreaks.	
mountain plover (Charadrius montanus)	CSC	Breeds on open plains at moderate elevations. Winters in short- grass plains and fields, plowed or fallow fields, and sandy deserts. Prefers flat, bare ground with burrowing rodents.	
Nelson's antelope squirrel (Ammospermophilus nelsoni)	CT	Found in the western San Joaquin Valley on dry, sparsely vegetated loamy soils. Relies heavily on existing small mammal burrows.	
northern California CSG legless lizard (Anniella pulchra)		Found primarily underground, burrowing in loose, sandy soil. Forages in loose soil and leaf litter during the day. Occasionally observed on the surface at dusk and night.	
pallid bat (Antrozous pallidus)	CSC	Found in grasslands, chaparral, and woodlands, where it feeds on ground- and vegetation-dwelling arthropods, and occasionally takes insects in flight. Prefers to roost in rock crevices, but may also use tree cavities, caves, bridges, and other man-made structures.	
San Joaquin coachwhip (Masticophis flagellum ruddocki)	CSC	Found in open dry habitats with little or no tree cover in valley grassland and saltbush scrub communities in the San Joaquin Valley. Relies on mammal burrows for refuge and oviposition sites.	
San Joaquin kit fox FE, ( (Vulpes macrotis mutica)		Underground dens with multiple entrances in alkali sink, valley grassland, and woodland in valleys and adjacent foothills.	
<pre>short-eared owl CSC (Asio flammeus)</pre>		Found in wet and lowland habitats, including swamps, fresh and salt marshes, as well as irrigated alfalfa fields in the San Joaquin valley, portions of the San Francisco Bay area, the eastern Sierra Nevada range, and the northeast corner of California during the breeding season(Roberson, 2008). Numbers are highly dependent on drought conditions. Nests on dry ground, concealed in vegetation, and found in tule patches and tall grasses during the day.	

Species	Status	Habitat
Steelhead – Central Valley DPS (Oncorhynchus mykiss irideus pop.11)	FT	This winter-run fish begins migration to fresh water during peak flows during December and February. Spawning season is typically from February to April. After hatching, fry move to deeper, mid-channel habitats in late summer and fall. In general, both juveniles and adults prefer complex habitat boulders, submerged clay and undercut banks, and large woody debris.
Swainson's hawk (Buteo swainsoni)	CT	Nests in large trees in open areas adjacent to grasslands, grain or alfalfa fields, or livestock pastures suitable for supporting rodent populations.
tricolored blackbird (Agelaius tricolor)	CT, CSC	Nests colonially near fresh water in dense cattails or tules, or in thickets of riparian shrubs. Forages in grassland and cropland. Large colonies are often found on dairy farm forage fields.
Tulare grasshopper mouse (Onychomys torridus tularensis)	CSC	Typically inhabit arid shrubland communities in hot, arid grassland and shrubland associations. Diet consists almost exclusively of arthropods.
two-stripedCSCgartersnake(Thamnophishammondii)		Highly aquatic, found in or near permanent fresh water. Often along streams with rocky beds and riparian growth.
valley elderberry longhorn beetle (Desmocerus californicus dimorphus)	FT	Lives in mature elderberry shrubs of the Central Valley and foothills. Adults are active March to June.
vernal pool fairy FT shrimp (Branchinecta lynchi)		Occupies vernal pools, clear to tea-colored water, in grass or mud-bottomed swales, and basalt depression pools.
western mastiff bat (Eumops perotis californicus)		Found in open, arid to semi-arid habitats, including dry desert washes, flood plains, chaparral, oak woodland, open ponderosa pine forest, grassland, and agricultural areas, where it feeds on insects in flight. Roosts most commonly in crevices in cliff faces but may also use high buildings and tunnels.
(Emys marmorata) and irrigation ditches with riparian vegetation. Req		An aquatic turtle of ponds, marshes, slow-moving rivers, streams, and irrigation ditches with riparian vegetation. Requires adequate basking sites and sandy banks or grassy open fields to deposit eggs.
western red bat (Lasiurus blossevillii)	CSC	Roosts primarily in trees, 2–40 ft above ground, from sea level up through mixed conifer forests. Prefers habitat edges and mosaics with trees that are protected from above and open below with open areas for foraging.

Species	Status	Habitat
western spadefoot (Spea hammondii)	CSC	Prefers open areas with sandy or gravelly soils, in a variety of habitats including mixed woodlands, grasslands, coastal sage scrub, chaparral, sandy washes, lowlands, river floodplains, alluvial fans, playas, alkali flats, foothills, and mountains. Vernal pools or temporary wetlands, lasting a minimum of three weeks, which do not contain bullfrogs, fish, or crayfish are necessary for breeding.
western yellow- billed cuckoo (Coccyzus americanus occidentalis)	FT, CE	Suitable nesting habitat in California includes dense riparian willow-cottonwood and mesquite habitats along a perennial river. Once a common breeding species in riparian habitats of lowland California, this species currently breeds consistently in only two locations in the State: along the Sacramento and South Fork Kern Rivers.
white-faced ibis (Plegadis chihi)	CWL	Found in shallow freshwater marshes, using tule thickets for nesting and nearby areas of shallow water for foraging.

Species	Status	Habitat			
brittlescale CNPS (Atriplex 1B depressa)		Found in the San Joaquin Valley and Sacramento Valley in alkaline or clay soils, typically in meadows or annual grassland in at elevations below 1050 feet. Sometimes associated with vernal pools. Blooms June–October.			
grass 1B saline flats and mineral springs within valley g		Found in the San Joaquin Valley and other parts of California in saline flats and mineral springs within valley grassland and wetland- riparian communities at elevations below 3000 feet. Blooms March- May.			
jewelflower CE, sandy soils. Occurs on flats and s		Found in the San Joaquin Valley and Western Transverse Ranges in sandy soils. Occurs on flats and slopes, generally in non-alkaline grassland at elevations between 230 feet and 6100 feet. Blooms February–April.			
CaliforniaCNPSsatintail2B(Imperatabrevifolia)		Although this facultative species is equally likely to occur in wetlands and non-wetlands, it is often found in wet springs, meadows, streambanks, and floodplains at elevations below 1600 feet. Blooms September – May.			
caper-fruitedCNPStropidocarpum1B(Tropidocarpumcapparideum)		Found in alkaline soils in low hills and valleys, often within Valley Grassland communities, at elevations below 1300 feet. Blooms March – April.			
grass (Orcuttia CE, comm		Found in vernal pools in valley grassland, wetland, and riparian communities at elevations below 650 feet. Blooms May – September.			
(Atriplex 1B or alkaline soils within shadescale scrub, valley grassle		Found in the San Joaquin Valley and Sacramento Valley in saline or alkaline soils within shadescale scrub, valley grassland, and wetland-riparian communities at elevations below 230 feet. Blooms June–July.			

Species	Status	Habitat
Indian Valley bush-mallow (Malacothamnus aboriginum)	CNPS 1B	Occurs through central California in chaparral and woodland habitats at elevations between 490 and 3710 feet. Grows on granitic outcrops in sandy, bare soils. Blooms May – July.
lesser saltscale (Atriplex minuscula)	CNPS 1B	Found in the San Joaquin Valley in sandy, alkaline soils in alkali scrub, valley and foothill grassland, and alkali sink communities at elevations below 750 feet. Blooms April–October.
Lost Hills crownscale (Atriplex coronata var. vallicola)	CNPS 1B	Found in the San Joaquin Valley in dried ponds and alkaline soils in alkali scrub, valley and foothill grassland, and vernal pools at elevations below 2900 feet. Blooms April–September.
Madera leptosiphon (Leptosiphon serrulatus)	CNPS 1B	Found in openings in foothill woodland, often yellow-pine forest, and chaparral at elevations between 1000 feet and 4300 feet. Blooms April – May.
Munz's tidy-tips (Layia munzii)	CNPS 1B	Found in the San Joaquin Valley in alkaline clay soils; often along hillsides in alkali scrub and sometimes valley and foothill grassland. Occurs at elevations between 145 feet and 2625 feet Blooms March–April.
palmate- bracted bird's beak (Chloropyron palmatum)	FE, CE, CNPS 1B	Found in the San Joaquin Valley and Sacramento Valley in alkaline soils (usually Pescadero silty clay) in chenopod scrub, valley and foothill grassland at elevations below 500 feet. Blooms June– August.
Panoche pepper-grass (Lepidium jaredii ssp. album)	CNPS 1B	Found on steep slopes, washes, alluvial-fans, and clay, sometimes alkaline, within Valley and Foothill Grassland communities in western Fresno County at elevations between 600–2400 feet. Blooms February–June.
recurved larkspur (Delphinium recurvatum)	CNPS 1B	Occurs in poorly drained, fine, alkaline soils in grassland and alakli scrub communities at elevations between 100 feet and 2600 feet. Blooms March–June.
San Joaquin Valley Orcutt grass (Orcuttia inaequalis)	ft, Ce, CNPS 1B	Found in the eastern San Joaquin Valley and the Sierra Nevada foothills in vernal pools within valley grassland, freshwater wetland, and wetland-riparian communities at elevations below 2600 feet. Blooms April – September.
San Joaquin woollythreads (Monolopia congdonii)	fe, CNPS 1B	Occurs in the San Joaquin Valley in sandy soils on alkaline or loamy plains in valley and foothill grassland and alkali scrub communities at elevations between 180 feet and 2750 feet. Blooms February– May.
arrowhead 1B fr		Found in the San Joaquin Valley and other parts of California in freshwater-marsh, primarily ponds and ditches, at elevations below 1000 feet. Blooms May–October.

Species	Status	Habitat
spiny-sepaled button-celery (Eryngium spinosepalum)	CNPS 1B	Found in the Sierra Nevada Foothills and the San Joaquin Valley. Occurs in vernal pools, swales, and roadside ditches. Often associated with clay soils in vernal pools within grassland communities. Occurs at elevations between 50 feet and 4160 feet. Blooms April–July.
		Found in the San Joaquin Valley in saline depressions in alkaline soils within valley and foothill grassland communities at elevations below 330 feet. Blooms June–October.
succulent owl's- clover (Castilleja campestris var. succulenta)FT, CE, CNPS 1BFound in vernal pools, often in acid feet. Blooms April – July.		Found in vernal pools, often in acidic soils at elevations below 2500 feet. Blooms April – July.
vernal pool smallscale (Atriplex persistens)	CNPS 1B	Occurs in the San Joaquin Valley and Sacramento Valley in alkaline vernal pools at elevations below 375 feet. Blooms June– September.

#### **EXPLANATION OF DESIGNATIONS AND STATUS CODES**

#### STATUS CODES

FE	Federally Endangered	CE	California Endangered
FT	Federally Threatened	CT	California Threatened
CFP	California Fully Protected	CSC	California Species of Concern
CWL	California Watch List	CCE	California Endangered (Candidate)

#### **CNPS RARE PLANT RANK**

- 1B Plants Rare, Threatened, or Endangered in California and elsewhere
- 2B Plants Rare, Threatened, or Endangered in California but more common elsewhere

# Appendix I – California Natural Diversity Database Data



### Attachment 3 - MAGSA CNDDB Results Selected Elements by Common Name

### California Department of Fish and Wildlife



#### California Natural Diversity Database

Query Criteria: Quad<span style='color:Red'> IS </span>(Mendota Dam (3612073)<span style='color:Red'> OR </span>Gravelly Ford (3612072)<span style='color:Red'> OR </span>Tranquillity (3612063)<span style='color:Red'> OR </span>Jamesan (3612062)<span style='color:Red'> OR </span>Kerman (3612061)<span style='color:Red'> OR </span>Kerman (3612061)<span style='color:Red'> OR </span>Kerman (3612061)<span style='color:Red'> OR </span>Kerman (3612061)<span style='color:Red'> OR </span>Kerman (3612052)<span style='color:Red'> OR </span>Helm (3612051)<span style='color:Red'> OR </span>Raisin (3611958)<span style='color:Red'> OR </span>Caruthers (3611957)<span style='color:Red'> OR </span>Firebaugh (3612074)<span style='color:Red'> OR </span>Bonita Ranch (3612082)<span style='color:Red'> OR </span>Firebaugh NE (3612083)<span style='color:Red'> OR </span>Bonita Ranch (3612082)<span style='color:Red'> OR </span>Madera (3612081)<span style='color:Red'> OR </span>Bonita Ranch (3612082)<span style='color:Red'> OR </span>Madera (3612081)<span style='color:Red'> OR </span>Bonita (3611087)<span style='color:Red'> OR </span>Fresno South (3611967)<span style='color:Red'> OR </span>Caruthers (3611977)<span style='color:Red'> OR </span>Fresno South (3611967)<span style='color:Red'> OR </span>Caruthan style='color:Red'> OR </span>Fresno South (3611967)<span style='color:Red'> OR </span>Caruthan style='color:Red'> OR </span>Fresno South (3611977)<span style='color:Red'> OR </span>Fresno South (3611977)<span style='color:Red'> OR </span>Fresno South (3611977)<span style='color:Red'> OR </span>Eventor:Red'> OR </

Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
American badger	AMAJF04010	None	None	G5	S3	SSC
Taxidea taxus						
Antioch efferian robberfly	IIDIP07010	None	None	G1G2	S1S2	
Efferia antiochi						
bank swallow	ABPAU08010	None	Threatened	G5	S2	
Riparia riparia						
black-crowned night heron	ABNGA11010	None	None	G5	S4	
Nycticorax nycticorax						
blunt-nosed leopard lizard	ARACF07010	Endangered	Endangered	G1	S1	FP
Gambelia sila						
brittlescale	PDCHE042L0	None	None	G2	S2	1B.2
Atriplex depressa						
burrowing owl	ABNSB10010	None	None	G4	S3	SSC
Athene cunicularia						
California alkali grass	PMPOA53110	None	None	G3	S2	1B.2
Puccinellia simplex						
California glossy snake	ARADB01017	None	None	G5T2	S2	SSC
Arizona elegans occidentalis						
California horned lark	ABPAT02011	None	None	G5T4Q	S4	WL
Eremophila alpestris actia						
California jewelflower	PDBRA31010	Endangered	Endangered	G1	S1	1B.1
Caulanthus californicus						
California satintail	PMPOA3D020	None	None	G4	S3	2B.1
Imperata brevifolia						
California tiger salamander	AAAAA01180	Threatened	Threatened	G2G3	S2S3	WL
Ambystoma californiense						
caper-fruited tropidocarpum	PDBRA2R010	None	None	G1	S1	1B.1
Tropidocarpum capparideum						
coast horned lizard	ARACF12100	None	None	G3G4	S3S4	SSC
Phrynosoma blainvillii				_	_	
Coastal and Valley Freshwater Marsh	CTT52410CA	None	None	G3	S2.1	
Coastal and Valley Freshwater Marsh						



### Attachment 3 - MAGSA CNDDB Results Selected Elements by Common Name

California Department of Fish and Wildlife

**California Natural Diversity Database** 



Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
Crotch bumble bee	IIHYM24480	None	Candidate	G3G4	S1S2	
Bombus crotchii			Endangered			
Fresno kangaroo rat	AMAFD03151	Endangered	Endangered	G3TH	SH	
Dipodomys nitratoides exilis						
giant gartersnake	ARADB36150	Threatened	Threatened	G2	S2	
Thamnophis gigas						
giant kangaroo rat	AMAFD03080	Endangered	Endangered	G1G2	S1S2	
Dipodomys ingens						
great egret	ABNGA04040	None	None	G5	S4	
Ardea alba						
hairy Orcutt grass	PMPOA4G040	Endangered	Endangered	G1	S1	1B.1
Orcuttia pilosa						
heartscale	PDCHE040B0	None	None	G3T2	S2	1B.2
Atriplex cordulata var. cordulata						
hoary bat	AMACC05030	None	None	G5	S4	
Lasiurus cinereus						
Hoover's eriastrum	PDPLM03070	Delisted	None	G3	S3	4.2
Eriastrum hooveri						
Hurd's metapogon robberfly	IIDIP08010	None	None	G1G2	S1S2	
Metapogon hurdi						
Indian Valley bush-mallow	PDMAL0Q020	None	None	G3	S3	1B.2
Malacothamnus aboriginum						
lesser saltscale	PDCHE042M0	None	None	G2	S2	1B.1
Atriplex minuscula						
longhorn fairy shrimp	ICBRA03020	Endangered	None	G1	S1S2	
Branchinecta longiantenna						
Lost Hills crownscale	PDCHE04371	None	None	G4T2	S2	1B.2
Atriplex coronata var. vallicola						
Madera leptosiphon	PDPLM09130	None	None	G3	S3	1B.2
Leptosiphon serrulatus						
merlin	ABNKD06030	None	None	G5	S3S4	WL
Falco columbarius						
midvalley fairy shrimp	ICBRA03150	None	None	G2	S2S3	
Branchinecta mesovallensis						
molestan blister beetle	IICOL4C030	None	None	G2	S2	
Lytta molesta						
mountain plover	ABNNB03100	None	None	G3	S2S3	SSC
Charadrius montanus						
Munz's tidy-tips	PDAST5N0B0	None	None	G2	S2	1B.2
Layia munzii						
Nelson's antelope squirrel	AMAFB04040	None	Threatened	G2	S2S3	
Ammospermophilus nelsoni						



# Attachment 3 - MAGSA CNDDB Results

Selected Elements by Common Name

California Department of Fish and Wildlife California Natural Diversity Database



Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
northern California legless lizard	ARACC01020	None	None	G3	S3	SSC
Anniella pulchra						
Northern Claypan Vernal Pool	CTT44120CA	None	None	G1	S1.1	
Northern Claypan Vernal Pool						
Northern Hardpan Vernal Pool Northern Hardpan Vernal Pool	CTT44110CA	None	None	G3	S3.1	
pallid bat	AMACC10010	None	None	G5	S3	SSC
Antrozous pallidus						
palmate-bracted bird's-beak	PDSCR0J0J0	Endangered	Endangered	G1	S1	1B.1
Chloropyron palmatum						
Panoche pepper-grass	PDBRA1M0G2	None	None	G2G3T2T3	S2S3	1B.2
Lepidium jaredii ssp. album						
recurved larkspur	PDRAN0B1J0	None	None	G2?	S2?	1B.2
Delphinium recurvatum						
San Joaquin coachwhip Masticophis flagellum ruddocki	ARADB21021	None	None	G5T2T3	S2?	SSC
San Joaquin dune beetle	IICOL4A020	None	None	G1	S1	
Coelus gracilis						
San Joaquin kit fox	AMAJA03041	Endangered	Threatened	G4T2	S2	
Vulpes macrotis mutica						
San Joaquin Pocket Mouse	AMAFD01060	None	None	G2G3	S2S3	
Perognathus inornatus						
San Joaquin Valley Orcutt grass	PMPOA4G060	Threatened	Endangered	G1	S1	1B.1
Orcuttia inaequalis						
San Joaquin woollythreads	PDASTA8010	Endangered	None	G2	S2	1B.2
Monolopia congdonii						
Sanford's arrowhead	PMALI040Q0	None	None	G3	S3	1B.2
Sagittaria sanfordii						
short-eared owl	ABNSB13040	None	None	G5	S3	SSC
Asio flammeus						
snowy egret	ABNGA06030	None	None	G5	S4	
Egretta thula						
spiny-sepaled button-celery	PDAPI0Z0Y0	None	None	G2	S2	1B.2
Eryngium spinosepalum						
steelhead - Central Valley DPS	AFCHA0209K	Threatened	None	G5T2Q	S2	
Oncorhynchus mykiss irideus pop. 11				_	_	_
subtle orache	PDCHE042T0	None	None	G1	S1	1B.2
Atriplex subtilis						
succulent owl's-clover	PDSCR0D3Z1	Threatened	Endangered	G4?T2T3	S2S3	1B.2
Castilleja campestris var. succulenta				_	_	
Swainson's hawk Buteo swainsoni	ABNKC19070	None	Threatened	G5	S3	



## Attachment 3 - MAGSA CNDDB Results Selected Elements by Common Name

California Department of Fish and Wildlife

California Natural Diversity Database



-

Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
tricolored blackbird	ABPBXB0020	None	Threatened	G2G3	S1S2	SSC
Agelaius tricolor						
Tulare grasshopper mouse	AMAFF06021	None	None	G5T1T2	S1S2	SSC
Onychomys torridus tularensis						
two-striped gartersnake	ARADB36160	None	None	G4	S3S4	SSC
Thamnophis hammondii						
valley elderberry longhorn beetle	IICOL48011	Threatened	None	G3T2	S2	
Desmocerus californicus dimorphus						
Valley Sacaton Grassland	CTT42120CA	None	None	G1	S1.1	
Valley Sacaton Grassland						
Valley Sink Scrub	CTT36210CA	None	None	G1	S1.1	
Valley Sink Scrub						
vernal pool fairy shrimp	ICBRA03030	Threatened	None	G3	S3	
Branchinecta lynchi						
vernal pool smallscale	PDCHE042P0	None	None	G2	S2	1B.2
Atriplex persistens						
western mastiff bat	AMACD02011	None	None	G5T4	S3S4	SSC
Eumops perotis californicus						
western pond turtle	ARAAD02030	None	None	G3G4	S3	SSC
Emys marmorata						
western red bat	AMACC05060	None	None	G5	S3	SSC
Lasiurus blossevillii						
western spadefoot	AAABF02020	None	None	G3	S3	SSC
Spea hammondii						
western yellow-billed cuckoo	ABNRB02022	Threatened	Endangered	G5T2T3	S1	
Coccyzus americanus occidentalis						
white-faced ibis	ABNGE02020	None	None	G5	S3S4	WL
Plegadis chihi						
Yuma myotis	AMACC01020	None	None	G5	S4	
Myotis yumanensis						

Record Count: 73

# Appendix J – California Historical Resources Information System Search 20-139

	ical e	Fresno Kern Kings Madera Tulare	Southern San Joaquin Valley Information Center California State University, Bakersfield Mail Stop: 72 DOB 9001 Stockdale Highway Bakersfield, California 93311-1022 (661) 654-2289 E-mail: ssjvic@csub.edu Website: www.csub.edu/ssjvic						
То:	Jacqueline Lancaster Provost & Pritchard Consulting Gro 130 N. Garden Street Visalia, CA 93291	up, Inc.	Record Search 20-139						
Date:	April 14, 2020								
Re:	McMullin GSA Groundwater Banking Reconnaissance Study Project								
County:	Fresno								
Map(s):	Gravelly Ford, Helm, Jamesan, Kear Tranquillity 7.5's	rney Park, Kerman, N	/lendota Dam, Raisin, San Joaquin, &						

Concerna and

### CULTURAL RESOURCES RECORDS SEARCH

The California Office of Historic Preservation (OHP) contracts with the California Historical Resources Information System's (CHRIS) regional Information Centers (ICs) to maintain information in the CHRIS inventory and make it available to local, state, and federal agencies, cultural resource professionals, Native American tribes, researchers, and the public. Recommendations made by IC coordinators or their staff regarding the interpretation and application of this information are advisory only. Such recommendations do not necessarily represent the evaluation or opinion of the State Historic Preservation Officer in carrying out the OHP's regulatory authority under federal and state law.

The following are the results of a search of the cultural resource files at the Southern San Joaquin Valley Information Center. These files include known and recorded cultural resources sites, inventory and excavation reports filed with this office, and resources listed on the National Register of Historic Places, the OHP Built Environment Resources Directory, California State Historical Landmarks, California Register of Historical Resources, California Inventory of Historic Resources, and California Points of Historical Interest. Due to processing delays and other factors, not all of the historical resource reports and resource records that have been submitted to the OHP are available via this records search. Additional information may be available through the federal, state, and local agencies that produced or paid for historical resource management work in the search area.

### PRIOR CULTURAL RESOURCE STUDIES CONDUCTED WITHIN THE PROJECT AREA

According to the information in our files, there have been 30 previous cultural resource studies conducted within portions of the project area. A list is enclosed.

### KNOWN/RECORDED CULTURAL RESOURCES WITHIN THE PROJECT AREA

There are 30 recorded resource within the project area. A list is enclosed. These resources include prehistoric era lithic scatters, bedrock milling features, beads, groundstones, mounds, firecracked rocks, and burials. They also include historic era railroads, canals, trash scatters transmission lines, a farming community, and various types of buildings.

Resource P-10-006617, the Fresno Slough Bypass, has been given a National Register status code of 2D2, indicating it is a contributor to a district that has been determined eligible for listing in the National Register of Historic Places by a consensus through the Section 106 process. It is also listed in the California Register of Historical Resources. There are no other recorded cultural resources within the project area that are listed in the National Register of Historical Register of Historic Places, the California Register of Historical Resources, the California Points of Historical Interest, California Inventory of Historic Resources, or the California State Historic Landmarks.

### COMMENTS AND RECOMMENDATIONS

We understand the purpose of this project is to identify areas that would be best suited for a groundwater bank and look at fatal flaws analysis at a programmatic level with the 120,000 acre MAGSA boundary. Further, we understand, because specific project areas have not yet been identified, no ground disturbance activities are currently planned. Because no ground disturbance activities are currently planned. Because no ground disturbance activities are currently planned, no further cultural resource investigation is recommended at this time. However, prior to any future ground disturbance activities related to this project, we recommend that a new record search be conducted for each ground disturbance project area identified so specific recommendations can be made. A list of qualified consultants can be found at www.chrisinfo.org.

We also recommend that you contact the Native American Heritage Commission in Sacramento. They will provide you with a current list of Native American individuals/organizations that can assist you with information regarding cultural resources that may not be included in the CHRIS Inventory and that may be of concern to the Native groups in the area. The Commission can consult their "Sacred Lands Inventory" file in order to determine what sacred resources, if any, exist within this project area and the way in which these resources might be managed. Finally, please consult with the lead agency on this project to determine if any other cultural resource investigation is required. If you need any additional information or have any questions or concerns, please contact our office at (661) 654-2289.

By:

Celeste M. Thomson, Coordinator

Date: April 14, 2020

Please note that invoices for Information Center services will be sent under separate cover from the California State University, Bakersfield Accounting Office.

Reports in Project Area:	Resources in Project Area:
FR-00147	P-10-000074
FR-00148	P-10-000314
FR-00169	P-10-000398
FR-00185	P-10-000495
FR-00245	P-10-000562
FR-00246	P-10-000565
FR-00247	P-10-000566
FR-00255	P-10-000567
FR-00277	P-10-000784
FR-00433	P-10-002312
FR-00576	P-10-003930
FR-00589	P-10-004303
FR-00998	P-10-005175
FR-01783	P-10-005714
FR-01868	P-10-005715
FR-02316	P-10-005719
FR-02404	P-10-005793
FR-02412	P-10-006134
FR-02414	P-10-006202
FR-02416	P-10-006604
FR-02480	P-10-006614
FR-02501	P-10-006617
FR-02505	P-10-006628
FR-02506	P-10-006629
FR-02562	P-10-006630
FR-02723	P-10-006633
FR-02769	P-10-006634
FR-02791	P-10-006636
FR-02889	P-10-007057
FR-02905	P-10-007058

# Appendix K – Detailed Preliminary Schedule

	N	ask Name	Duration	Start	Finish
	M				
1					/- /
		· · · ·	480 days 6 mons	Mon 10/5/20 Mon 10/5/20	Fri 8/5/22 Fri 3/19/21
2	-		24 mons	Mon 10/5/20	Fri 8/5/22
4			1200 days	Mon 10/5/20	Fri 5/9/25
5		Coordination with SJREC	24 mons	Mon 10/5/20	Fri 8/5/22
6		Coordination with SLDMWA	24 mons	Mon 10/5/20	Fri 8/5/22
7		Coordination with Neighboring Agencie	24 mons	Mon 10/5/20	Fri 8/5/22
8		MAGSA Constituent Updates	60 mons	Mon 10/5/20	Fri 5/9/25
9		-	480 days	Mon 7/12/21	Fri 5/12/23
10		Subscription Agreements	12 mons 12 mons	Mon 7/12/21	Fri 6/10/22
11 12	Π.	Banking Agreements Environmental Documentation	12 mons 267 days	Mon 6/13/22 Thu 9/30/21	Fri 5/12/23 Fri 10/7/22
12			1 day	Thu 9/30/21	Thu 9/30/21
14			165 days	Mon 10/4/21	Fri 5/20/22
15		Biological Surveys	6 wks	Mon 10/4/21	Fri 11/12/21
16		Cultural Surveys	6 wks	Mon 10/4/21	Fri 11/12/21
17	•	Groundwater Analysis	6 wks	Mon 10/4/21	Fri 11/12/21
18		Prepare Administrative Draft EA/IS		Mon 10/4/21	Fri 1/21/22
19		Internal Team Review	1 wk	Mon 1/24/22	Fri 1/28/22
20			2 wks 8 wks	Mon 1/31/22	Fri 2/11/22
21		USBR Review Internal Team Review	8 wks 2 wks	Mon 2/14/22 Mon 4/11/22	Fri 4/8/22 Fri 4/22/22
22			2 wks 4 wks	Mon 4/25/22	Fri 5/20/22
24		Mitigated Neg. Dec. / Finding of No Sig		Mon 5/23/22	Fri 10/7/22
25			8 wks	Mon 5/23/22	Fri 7/15/22
26		Public Review Process	4 wks	Mon 7/18/22	Fri 8/12/22
27	•	Address Public Comments	4 wks	Mon 8/15/22	Fri 9/9/22
28	•	Adopt MND / Final FONSI	4 wks	Mon 9/12/22	Fri 10/7/22
29			315 days	Mon 10/10/22	Fri 12/22/23
0	-	CDFW LSAA	6 mons	Mon 10/10/22	Fri 3/24/23
1		Fresno County Encroachment Permits Fresno County Export Exemption	2 mons 3 mons	Mon 10/9/23 Mon 10/10/22	Fri 12/1/23 Fri 12/30/22
33		PG&E Service	12 mons	Mon 1/23/23	Fri 12/22/23
34			1 mon	Mon 10/9/23	Fri 11/3/23
5		RWQCB Stormwater Pollution Preventi	1 mon	Mon 10/9/23	Fri 11/3/23
36		Engineering	1225 days	Mon 3/22/21	Fri 11/28/25
7	•	Conceptual Design	440 days	Mon 3/22/21	Fri 11/25/22
38		Identify Alignments	2 mons	Mon 3/22/21	Fri 5/14/21
9	•	Identify Recharge Sites	40 days	Mon 3/22/21	Fri 5/14/21
0	•	Collect/Analyze GW Quality Samp		Mon 3/22/21	Fri 5/14/21
1			2 mons 6 mons	Mon 3/22/21 Mon 6/13/22	Fri 5/14/21 Fri 11/25/22
42 43	-	Surveys	170 days	Mon 6/13/22	Fri 2/3/23
43 44		Set Project Control Points	1 wk	Mon 6/13/22	Fri 6/17/22
			25 days	Mon 6/20/22	Fri 7/22/22
15	-	Field Surveys - Conveyance Alignr			
				Mon 6/20/22	Fri 7/15/22
46	-	Field Surveys - Survey Recharge S		Mon 6/20/22 Mon 6/20/22	Fri 7/15/22 Fri 7/15/22
46 47	-	Utility Research	4 wks 1 wk	Mon 6/20/22 Mon 6/20/22	Fri 7/15/22 Fri 6/24/22
6 7 8 9	-	Utility Research Develop CAD Basemaps	4 wks 1 wk 4 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22
6 7 8 9	-	Utility Research Develop CAD Basemaps Boundary Surveys	4 wks 1 wk 4 wks 50 days	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23
5 7 3 9		Utility Research Develop CAD Basemaps <b>Boundary Surveys</b> Research existing maps and recor	4 wks 1 wk 4 wks 50 days 2 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 11/28/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22
6 7 8 9 0 1 2	-	Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports	4 wks 1 wk 4 wks <b>50 days</b> 2 wks 6 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 11/28/22 Mon 12/12/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23
6 7 8 9 0 1 2 3	-	Utility Research Develop CAD Basemaps <b>Boundary Surveys</b> Research existing maps and recor	4 wks 1 wk 4 wks 50 days 2 wks 6 wks 4 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 11/28/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22
46 47 48 49 50 51 52 53 54	-	Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bo Reconcile and Develop CAD Baser	4 wks 1 wk 4 wks 50 days 2 wks 6 wks 4 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 11/28/22 Mon 12/12/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23
16 17 18 19 19 10 11 11 12 13 13 14 15		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bo Reconcile and Develop CAD Baser Conveyance Design	4 wks 1 wk 4 wks 50 days 2 wks 6 wks 4 wks 4 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 11/28/22 Mon 12/12/22 Mon 12/12/22 Mon 1/9/23	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 2/3/23
46 47 48 49 50 51 52 53 54 55 56		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bo Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents	4 wks 1 wk 4 wks 50 days 2 wks 6 wks 4 wks 4 wks 670 days	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 11/28/22 Mon 12/12/22 Mon 12/12/22 Mon 1/9/23	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 2/3/23 Fri 1/3/25
16 17 18 19 50 51 52 53 54 55 56 56 57 58		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bo Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling)	4 wks 1 wk 50 days 50 days 6 wks 4 wks 670 days 160 days 70 days 6 wks	Mon 6/20/22 Mon 6/20/22 Mon 6/27/22 Mon 11/28/22 Mon 12/12/22 Mon 12/12/22 Mon 1/9/23 Mon 6/13/22 Mon 6/13/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 2/3/23 Fri 1/3/25 Fri 1/20/23 Fri 9/16/22 Fri 7/22/22
6 7 8 9 9 60 11 22 3 3 44 5 5 66 7 7 8 8 9		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bc Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing	4 wks 1 wk 4 wks 50 days 2 wks 6 wks 4 wks 670 days 160 days 70 days 6 wks 4 wks	Mon 6/20/22           Mon 6/20/22           Mon 1/28/22           Mon 11/28/22           Mon 12/12/22           Mon 12/12/22           Mon 13/12           Mon 14/28/22           Mon 13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 12/0/23 Fri 1/6/23 Fri 1/6/23 Fri 2/3/23 Fri 1/20/23 Fri 9/16/22 Fri 7/22/22 Fri 8/5/22
46 47 48 49 50 51 52 53 54 55 56 57 58 59 50		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BR Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report	4 wks 1 wk 4 wks 50 days 2 wks 6 wks 4 wks 670 days 160 days 70 days 6 wks 4 wks 4 wks 4 wks	Non 6/20/22           Mon 6/20/22           Mon 6/27/22           Mon 11/28/22           Mon 12/12/22           Mon 12/12/22           Mon 1/2/12/22           Mon 13/12           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/11/25           Mon 8/8/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 12/0/23 Fri 1/6/23 Fri 2/3/23 Fri 2/3/23 Fri 2/3/23 Fri 9/16/22 Fri 7/22/22 Fri 8/5/22 Fri 9/2/22
46 47 48 49 50 51 52 53 55 55 55 55 55 55 55 55 55 55 55 55		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BR Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 670 days 670 days 6 wks 4 wks 4 wks 2 wks 2 wks	Non 6/20/22           Non 6/20/22           Mon 6/27/22           Mon 11/28/22           Mon 12/12/22           Mon 12/12/22           Mon 1/128/27           Mon 6/13/28           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 8/13/22           Mon 8/122	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/3/25 Fri 1/2/23 Fri 1/2/23 Fri 9/16/22 Fri 8/5/22 Fri 9/16/22 Fri 9/16/22
46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 52		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BR Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Initial Project Calculations	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 670 days 160 days 6 wks 4 wks 4 wks 2 wks 2 wks 2 mons	Non 6/20/22           Non 6/20/22           Mon 6/27/22           Mon 11/28/22           Mon 12/12/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 6/13/22           Mon 9/5/22           Mon 11/28/24	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/20/23 Fri 2/3/23 Fri 1/3/25 Fri 1/20/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 1/20/23
46           47           48           49           50           51           52           53           54           55           56           57           58           59           50           51           52           53           53		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BC Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Initial Project Calculations Prepare Plans	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 4 wks 160 days 160 days 160 days 4 wks 4 wks 2 wks 2 wks 2 wks 2 mons 3 mons	Non 6/20/22           Non 6/20/22           Mon 1/28/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/11/22           Mon 9/5/22           Mon 9/5/22           Mon 1/128/24	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 1/6/23 Fri 1/2/23 Fri 1/20/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 1/20/23 Fri 1/20/23 Fri 1/20/23
46         47         48         49         50         51         52         53         54         55         56         57         58         59         50         51         52         53         54         55         54         52         53         54		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BC Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Initial Project Calculations Prepare Plans Prepare Opinion of Construction	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 4 wks 160 days 160 days 160 days 4 wks 4 wks 2 wks 2 wks 2 wks 2 mons 3 mons	Non 6/20/22           Non 6/20/22           Mon 6/27/22           Mon 11/28/22           Mon 12/12/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 6/13/22           Mon 9/5/22           Mon 11/28/24	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/20/23 Fri 2/3/23 Fri 1/3/25 Fri 1/20/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 1/20/23
46         47         48         49         50         51         52         53         54         55         56         57         58         59         50         51         52         53         54         55         54         55         54         55		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BC Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Initial Project Calculations Prepare Plans Prepare Opinion of Construction	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 4 wks 160 days 160 days 6 wks 4 wks 2 wks 2 wks 2 mons 3 mons 1 mon	Non 6/20/22           Non 6/20/22           Mon 1/28/22           Mon 11/28/22           Mon 12/12/22           Mon 1/2/12/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/11/22           Mon 9/5/22           Mon 1/28/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 2/3/23 Fri 2/3/23 Fri 1/20/23 Fri 9/222 Fri 9/222 Fri 9/16/22 Fri 9/30/22 Fri 9/30/22 Fri 9/30/22
46 47 48 50 51 52 53 55 55 55 55 55 55 55 55 55 55 55 55		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W BG Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Initial Project Calculations Prepare Plans Prepare Opinion of Construction of Internal QA/QC Review MAGSA Review	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 4 wks 670 days 70 days 160 days 6 wks 4 wks 4 wks 2 wks 2 wks 2 mons 1 mon 3 wks	Non 6/20/22           Non 6/20/22           Mon 1/28/22           Mon 1/28/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/1/22	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 2/3/23 Fri 2/3/23 Fri 1/3/25 Fri 1/20/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/30/22 Fri 9/30/22 Fri 9/30/22 Fri 9/30/22 Fri 9/30/22
45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 66 66 67 68		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bc Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Final Report Final Report Initial Project Calculations Prepare Opinion of Construction of Internal QA/QC Review MAGSA Review Phase 1 Conveyance Design	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 4 wks 70 days 6 wks 160 days 70 days 2 wks 2 wks 2 mons 3 mons 2 mo	Non 6/20/22           Mon 6/20/22           Mon 1/28/22           Mon 1/28/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/11/22           Mon 9/5/22           Mon 1/28/22           Mon 9/5/22           Mon 1/2/2/2           Mon 7/1/22           Mon 9/5/22           Mon 1/2/2/2           Mon 1/2/2	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 1/6/23 Fri 1/20/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/10/22 Fri 9/10/22 Fri 10/21/22 Fri 11/4/22 Fri 11/4/22 Fri 1/2/24 Fri 1/2/24
46           47           48           49           50           51           52           53           54           55           56           57           58           59           60           51           52           53           56           57           58           59           60           51           52           53           56           57           58           59           60           51           52           53           54           55           56           57           58           59           60           57           58           57           58           57           58           59           50           57           58           57		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bc Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Final Report Initial Project Calculations Prepare Opinion of Construction of Internal QA/QC Review MAGSA Review Phase 1 Conveyance Design 60% Design Documents	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 6 70 days 70 days 70 days 70 days 2 wks 2 wks 2 wks 2 mons 3 mons 3 mons 2 wks 2	Non 6/20/22           Non 6/20/22           Mon 6/27/22           Mon 11/28/22           Mon 12/12/22           Mon 12/12/22           Mon 12/12/22           Mon 12/12/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/11/22           Mon 9/5/22           Mon 7/11/22           Mon 9/5/22           Mon 7/11/22           Mon 10/24/22           Mon 10/24/22           Mon 1/23/23	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 1/2/23 Fri 12/9/22 Fri 1/2/23 Fri 1/6/23 Fri 1/6/23 Fri 1/2/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/12/22 Fri 1/2/23 Fri 1/2/23 Fri 1/2/23
5 7 3 3 9 0 1 2 3 3 4 5 7 3 9 0 1 2 2 3 3 9 0 1 2 2 3 3 4 5 7 3 9 0 0 1 2 3 3 4 5 7 7 3 9 9 0 0 1 2 3 3 3 7 7 7 8 9 9 7 7 8 9 9 9 7 7 9 9 9 9 9 9		Utility Research Develop CAD Basemaps Boundary Surveys Research existing maps and recor Order Preliminary Title Reports Field Surveys - Property & R/W Bc Reconcile and Develop CAD Baser Conveyance Design 30% Design Documents Geotechnical Investigations Field Work (Drilling/Sampling) Lab Testing Draft Report Final Report Final Report Final Report Initial Project Calculations Prepare Opinion of Construction of Internal QA/QC Review MAGSA Review Phase 1 Conveyance Design	4 wks 1 wk 2 wks 50 days 2 wks 6 wks 4 wks 4 wks 70 days 6 wks 160 days 70 days 2 wks 2 wks 2 mons 3 mons 2 mo	Non 6/20/22           Mon 6/20/22           Mon 1/28/22           Mon 1/28/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2/22           Mon 1/2/2           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 6/13/22           Mon 7/11/22           Mon 9/5/22           Mon 1/28/22           Mon 9/5/22           Mon 1/2/2/2           Mon 7/1/22           Mon 9/5/22           Mon 1/2/2/2           Mon 1/2/2	Fri 7/15/22 Fri 6/24/22 Fri 7/22/22 Fri 2/3/23 Fri 12/9/22 Fri 1/20/23 Fri 1/6/23 Fri 1/6/23 Fri 1/20/23 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/16/22 Fri 9/10/22 Fri 9/10/22 Fri 10/21/22 Fri 11/4/22 Fri 11/4/22 Fri 1/12/24 Fri 1/2/23


Milestone

Summary

٠

-

Project: 2022-0302 AquaTerra S Date: Tue 4/26/22 Split



	Q3	Q4 20	026 Q1			Q3			
			]						
It Manual Progres									
it Manul Progres									
it Manual Progres									
it Manual Progres									
It Manual Progress									
It Manual Progress									
It Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
It Manual Progress									
lit Manual Progress									
it Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
lit Manual Progress									
	blit		Manual Progre	ess					

ID T Ta	ask Name Duration	Start Finish		
M				
		Q3	2021 2022 2023 2024 2025 Q4 Q1 Q2 Q3 Q4	2026 2027 Q4 Q1 Q2 Q3 Q4 Q1 Q2 Q3
72 <b>•</b> 73 <b>•</b>	Prepare Technical Specification 2 mons	Mon 2/27/23 Fri 4/21/23		
73 •	Prepare Opinion of Constructic1 mon Internal QA/QC Review 3 wks	Mon 3/27/23 Fri 4/21/23 Mon 4/24/23 Fri 5/12/23		
74	MAGSA Review 2 wks	Mon 5/15/23 Fri 5/26/23		
76	Value Engineering Workshop 1 wk	Mon 5/29/23 Fri 6/2/23		
77	90% Design Documents 90 days	Mon 6/5/23 Fri 10/6/23		
78 🔍	Review and reconcile commen 1 wk	Mon 6/5/23 Fri 6/9/23		
79 🗖	Update Project Calculations 1 mon	Mon 6/12/23 Fri 7/7/23		
80	Prepare Plans 3 mons	Mon 6/12/23 Fri 9/1/23		
81 🔍	Prepare Contract Specification 3 mons	Mon 6/12/23 Fri 9/1/23		
82	Prepare Opinion of Constructic2 mons	Mon 7/10/23 Fri 9/1/23		
83	Internal QA/QC Review 3 wks	Mon 9/4/23 Fri 9/22/23		
84	MAGSA Review 2 wks	Mon 9/25/23 Fri 10/6/23		
85	100% Design Documents 70 days	Mon 10/9/23 Fri 1/12/24		
86 87	Review and reconcile commen 1 wk	Mon 10/9/23 Fri 10/13/23		
87 -	Update Project Calculations 1 mon Prepare Plans 2 mons	Mon 10/16/23 Fri 11/10/23 Mon 10/16/23 Fri 12/8/23		
89	Prepare Contract Specification 2 mons	Mon 10/16/23 Fri 12/8/23		
90	Prepare Opinion of Constructic1 mon	Mon 11/13/23 Fri 12/8/23		
91	Internal QA/QC Review 3 wks	Mon 12/11/23 Fri 12/29/23		
92	MAGSA Review 2 wks	Mon 1/1/24 Fri 1/12/24		
93	Phase 2 Conveyance Design 255 days			
94	60% Design Documents 95 days	Mon 1/15/24 Fri 5/24/24		
95	Review and reconcile commen 1 wk	Mon 1/15/24 Fri 1/19/24		
96 🖷	Update Project Calculations 1 mon	Mon 1/22/24 Fri 2/16/24		
97 🗖	Prepare Plans 3 mons	Mon 1/22/24 Fri 4/12/24		
98	Prepare Technical Specificatior 2 mons	Mon 2/19/24 Fri 4/12/24		
99	Prepare Opinion of Constructic 1 mon	Mon 3/18/24 Fri 4/12/24		
100	Internal QA/QC Review 3 wks	Mon 4/15/24 Fri 5/3/24		
101 🗖	MAGSA Review 2 wks	Mon 5/6/24 Fri 5/17/24		
102	Value Engineering Workshop 1 wk	Mon 5/20/24 Fri 5/24/24		
103	90% Design Documents 90 days	Mon 5/27/24 Fri 9/27/24		
104 105	Review and reconcile commen 1 wk	Mon 5/27/24 Fri 5/31/24		
105	Update Project Calculations 1 mon Prepare Plans 3 mons	Mon 6/3/24 Fri 6/28/24 Mon 6/3/24 Fri 8/23/24		
107	Prepare Contract Specification 3 mons	Mon 6/3/24 Fri 8/23/24		
107	Prepare Opinion of Constructic2 mons	Mon 7/1/24 Fri 8/23/24		
109	Internal QA/QC Review 3 wks	Mon 8/26/24 Fri 9/13/24		
110	MAGSA Review 2 wks	Mon 9/16/24 Fri 9/27/24		
111 🔍	100% Design Documents 70 days	Mon 9/30/24 Fri 1/3/25		
112 🗖	Review and reconcile commen 1 wk	Mon 9/30/24 Fri 10/4/24		
113	Update Project Calculations 1 mon	Mon 10/7/24 Fri 11/1/24		
114	Prepare Plans 2 mons	Mon 10/7/24 Fri 11/29/24		
115 <b>•</b> 116 <b>•</b>	Prepare Contract Specification 2 mons	Mon 10/7/24 Fri 11/29/24		
116	Prepare Opinion of Constructic1 mon Internal QA/QC Review 3 wks	Mon 11/4/24 Fri 11/29/24 Mon 12/2/24 Fri 12/20/24		
117	MAGSA Review 2 wks	Mon 12/23/24 Fri 1/3/25		
119	Recharge Design 680 days			
120	30% Design Documents 170 days			
121	Geotechnical Investigations 70 days	Mon 11/28/22 Fri 3/3/23		
122	Field Work (Drilling/Sampling) 6 wks	Mon 11/28/22 Fri 1/6/23		
123	Lab Testing 4 wks	Mon 12/26/22 Fri 1/20/23		
124	Draft Report 4 wks	Mon 1/23/23 Fri 2/17/23		
125	Final Report 2 wks	Mon 2/20/23 Fri 3/3/23		
126	Initial Project Calculations 2 mons	Mon 11/28/22 Fri 1/20/23		
127	Prepare Plans 3 mons	Mon 7/11/22 Fri 9/30/22		
128	Prepare Opinion of Construction (1 mon	Mon 9/5/22 Fri 9/30/22		
129 130	Internal QA/QC Review 3 wks MAGSA Review 2 wks	Mon 10/3/22 Fri 10/21/22 Mon 10/24/22 Fri 11/4/22		
130	MAGSA Review 2 wks Phase 1 Recharge Design 255 days			
131	60% Design Documents 95 days	Mon 3/6/23 Fri 7/14/23		
132	Review and reconcile commen 1 wk	Mon 3/6/23 Fri 3/10/23		
134	Update Project Calculations 1 mon	Mon 3/13/23 Fri 4/7/23		
135	Prepare Plans 3 mons	Mon 3/13/23 Fri 6/2/23		
136	Prepare Technical Specificatior 2 mons	Mon 4/10/23 Fri 6/2/23		
137 -	Prepare Opinion of Constructic1 mon	Mon 5/8/23 Fri 6/2/23		
138	Internal QA/QC Review 3 wks	Mon 6/5/23 Fri 6/23/23		
139	MAGSA Review 2 wks	Mon 6/26/23 Fri 7/7/23		
140	Value Engineering Workshop 1 wk	Mon 7/10/23 Fri 7/14/23		
141	90% Design Documents 90 days	Mon 7/17/23 Fri 11/17/23		
142	Review and reconcile commen 1 wk	Mon 7/17/23 Fri 7/21/23		
		Milestone 🔶		Manual Progress
Date: Tue	4/26/22 Split	Summary	Inactive Task Inactive Summary Duration-only Manual Summary Finish-only External Milestone Ocritical Progress	
			Page 2	

TT	ask Name Duration	Start Finish	
M			
			2021 2022 2023 2024 2025 2025 2026 2027 Q3 Q4 Q1 Q2 Q3 Q4 Q1 Q1 Q2 Q3 Q4 Q1 Q1 Q2 Q3 Q4 Q1 Q1 Q2 Q3 Q4 Q1 Q2 Q3 Q
13	Update Project Calculations 1 mon	Mon 7/24/23 Fri 8/18/23	
4	Prepare Plans 3 mons	Mon 7/24/23 Fri 10/13/23	
5	Prepare Contract Specification 3 mons	Mon 7/24/23 Fri 10/13/23	
5 • 7 •	Prepare Opinion of Constructic2 mons Internal QA/QC Review 3 wks	Mon 8/21/23 Fri 10/13/23 Mon 10/16/23 Fri 11/3/23	
8	MAGSA Review 2 wks	Mon 11/6/23 Fri 11/17/23	
9	100% Design Documents 70 days	Mon 11/20/23 Fri 2/23/24	
0	Review and reconcile commen 1 wk	Mon 11/20/23 Fri 11/24/23	
51 🔳	Update Project Calculations 1 mon	Mon 11/27/23 Fri 12/22/23	
52	Prepare Plans 2 mons	Mon 11/27/23 Fri 1/19/24	
53 🔍	Prepare Contract Specification 2 mons	Mon 11/27/23 Fri 1/19/24	
54 🔳	Prepare Opinion of Constructic1 mon	Mon 12/25/23 Fri 1/19/24	
5	Internal QA/QC Review 3 wks	Mon 1/22/24 Fri 2/9/24	
6	MAGSA Review 2 wks	Mon 2/12/24 Fri 2/23/24	
7	Phase 2 Recharge Design 255 days	Mon 2/26/24 Fri 2/14/25	
8	60% Design Documents 95 days	Mon 2/26/24 Fri 7/5/24	
9	Review and reconcile commen 1 wk	Mon 2/26/24 Fri 3/1/24	
0	Update Project Calculations 1 mon Prepare Plans 3 mons	Mon 3/4/24 Fri 3/29/24 Mon 3/4/24 Fri 5/24/24	
2	Prepare Plans 3 mons Prepare Technical Specificatior 2 mons	Mon 4/1/24 Fri 5/24/24	
3	Prepare Opinion of Constructic1 mon	Mon 4/29/24 Fri 5/24/24	
4	Internal QA/QC Review 3 wks	Mon 5/27/24 Fri 6/14/24	
5	MAGSA Review 2 wks	Mon 6/17/24 Fri 6/28/24	
6	Value Engineering Workshop 1 wk	Mon 7/1/24 Fri 7/5/24	
7 •	90% Design Documents 90 days	Mon 7/8/24 Fri 11/8/24	
8	Review and reconcile commen 1 wk	Mon 7/8/24 Fri 7/12/24	
9	Update Project Calculations 1 mon	Mon 7/15/24 Fri 8/9/24	
0	Prepare Plans 3 mons	Mon 7/15/24 Fri 10/4/24	
1	Prepare Contract Specification 3 mons	Mon 7/15/24 Fri 10/4/24	
2	Prepare Opinion of Constructic2 mons	Mon 8/12/24 Fri 10/4/24	
3	Internal QA/QC Review 3 wks	Mon 10/7/24 Fri 10/25/24	
4 • 5 •	MAGSA Review 2 wks 100% Design Documents 70 days	Mon 10/28/24 Fri 11/8/24 Mon 11/11/24 Fri 2/14/25	
6 •	Review and reconcile commen 1 wk	Mon 11/11/24 Fri 11/15/24	
7	Update Project Calculations 1 mon	Mon 11/18/24 Fri 12/13/24	
8	Prepare Plans 2 mons	Mon 11/18/24 Fri 1/10/25	
79	Prepare Contract Specification 2 mons	Mon 11/18/24 Fri 1/10/25	
80	Prepare Opinion of Constructic 1 mon	Mon 12/16/24 Fri 1/10/25	
81	Internal QA/QC Review 3 wks	Mon 1/13/25 Fri 1/31/25	
32	MAGSA Review 2 wks	Mon 2/3/25 Fri 2/14/25	
33 <b>•</b> 34 •	Recovery System Design 595 days	Mon 8/21/23 Fri 11/28/25	
5	30% Design Documents         85 days           Update Project Calculations         3 mons	Mon 8/21/23 Fri 12/15/23 Mon 8/21/23 Fri 11/10/23	
6	Prepare Plans 3 mons	Mon 8/21/23 Fri 11/10/23	
7 🔳	Prepare Opinion of Construction (1 mon	Mon 10/16/23 Fri 11/10/23	
в -	Internal QA/QC Review 3 wks	Mon 11/13/23 Fri 12/1/23	
9 -	MAGSA Review 2 wks	Mon 12/4/23 Fri 12/15/23	
0	Phase 1 Recovery 255 days	Mon 12/18/23 Fri 12/6/24	
1	60% Design Documents 95 days	Mon 12/18/23 Fri 4/26/24	
2	Review and reconcile commen 1 wk	Mon 12/18/23 Fri 12/22/23	
3	Update Project Calculations 1 mon	Mon 12/25/23 Fri 1/19/24	
4	Prepare Plans 3 mons	Mon 12/25/23 Fri 3/15/24	
5	Prepare Technical Specification 2 mons	Mon 1/22/24 Fri 3/15/24	
-	Prepare Opinion of Constructic1 mon Internal QA/QC Review 3 wks	Mon 2/19/24 Fri 3/15/24 Mon 3/18/24 Fri 4/5/24	
	MAGSA Review 2 wks	Mon 4/8/24 Fri 4/19/24	
, ,	Value Engineering Workshop 1 wk	Mon 4/22/24 Fri 4/26/24	
- ) -	90% Design Documents 90 days	Mon 4/29/24 Fri 8/30/24	
-	Review and reconcile commen 1 wk	Mon 4/29/24 Fri 5/3/24	
2	Update Project Calculations 1 mon	Mon 5/6/24 Fri 5/31/24	
3	Prepare Plans 3 mons	Mon 5/6/24 Fri 7/26/24	
1	Prepare Contract Specification 3 mons	Mon 5/6/24 Fri 7/26/24	
5	Prepare Opinion of Constructic2 mons	Mon 6/3/24 Fri 7/26/24	
5	Internal QA/QC Review 3 wks	Mon 7/29/24 Fri 8/16/24	
	MAGSA Review 2 wks	Mon 8/19/24 Fri 8/30/24	
3	100% Design Documents 70 days	Mon 9/2/24 Fri 12/6/24	
0	Review and reconcile commen 1 wk	Mon 9/2/24 Fri 9/6/24	
0	Update Project Calculations 1 mon Prepare Plans 2 mons	Mon 9/9/24 Fri 10/4/24 Mon 9/9/24 Fri 11/1/24	
2	Prepare Contract Specification 2 mons	Mon 9/9/24 Fri 11/1/24	
13	Prepare Opinion of Constructic1 mon	Mon 10/7/24 Fri 11/1/24	
			Project Summary Inactive Milestone Manual Task Manual Summary Rollup Start-only E External Tasks Deadline + Critical Split Manual Progress
ect. 20		inite scolie	
		Summary	Inactive Task Inactive Summary Duration-only Manual Summary Finish-only Critical Progress

T Task Name	Duration	Start	Finish														
N																	
				Q3	Q4 2021	1 Q1 Q2	Q3	Q4 2022	Q1 Q2	Q3	Q4 2023	Q1 Q2	Q3 Q4	2024 Q1	Q2 Q3	Q4 2025	<u>01 02</u>
Internal QA/QC Review	3 wks	Mon 11/4/24		. 7													
MAGSA Review	2 wks	Mon 11/25/24															
Phase 2 Recovery 60% Design Documents	255 days 95 days	Mon 12/9/24 Mon 12/9/24															
Review and reconcile com		Mon 12/9/24 Mon 12/9/24															
<ul> <li>Update Project Calculation</li> </ul>		Mon 12/16/24														₽	
Prepare Plans	3 mons	Mon 12/16/24														-	
<ul> <li>Prepare Technical Specific</li> </ul>		Mon 1/13/25															
<ul> <li>Prepare Opinion of Constr</li> </ul>		Mon 2/10/25															
Internal QA/QC Review	3 wks	Mon 3/10/25	Fri 3/28/25														
MAGSA Review	2 wks	Mon 3/31/25	Fri 4/11/25														1 <b>t</b>
<ul> <li>Value Engineering Worksh</li> </ul>	op 1 wk	Mon 4/14/25	Fri 4/18/25														<b>†</b>
90% Design Documents	90 days	Mon 4/21/25	Fri 8/22/25														<b> </b>
Review and reconcile com	men 1 wk	Mon 4/21/25	Fri 4/25/25														1 <b>*</b>
Update Project Calculation	ns 1 mon	Mon 4/28/25	Fri 5/23/25														1 <b>t</b>
Prepare Plans	3 mons	Mon 4/28/25	Fri 7/18/25														<b>1</b>
Prepare Contract Specifica	tion 3 mons	Mon 4/28/25	Fri 7/18/25														
<ul> <li>Prepare Opinion of Constr</li> </ul>	uctic2 mons	Mon 5/26/25	Fri 7/18/25														
Internal QA/QC Review	3 wks	Mon 7/21/25	Fri 8/8/25														
MAGSA Review	2 wks	Mon 8/11/25															
100% Design Documents	70 days	Mon 8/25/25															
Review and reconcile com	men 1 wk	Mon 8/25/25															
Update Project Calculation	ns 1 mon	Mon 9/1/25	Fri 9/26/25														
Prepare Plans	2 mons	Mon 9/1/25	Fri 10/24/25														
Prepare Contract Specifica		Mon 9/1/25	Fri 10/24/25														
Prepare Opinion of Constr		Mon 9/29/25															
Internal QA/QC Review	3 wks	Mon 10/27/25															
MAGSA Review	2 wks	Mon 11/17/25															
Land / Easement Acquisition	210 days	Mon 1/23/23									Ļ						
Conveyance Easements	180 days	Mon 1/23/23									ř-						
Identify Easement Needs	1 mon	Mon 1/23/23															
Meet with Landowners Appraisals	1 mon	Mon 2/20/23															
	1 mon	Mon 3/20/23															
Negotiations     Execute Agreements	3 mons	Mon 4/17/23															
	3 mons											-					1
Recharge Easements Identify Recharge Sites	180 days	Mon 3/6/23 Mon 3/6/23	Fri 11/10/23 Fri 3/31/23														
Meet with Landowners	1 mon 1 mon	Mon 3/6/23 Mon 4/3/23	Fri 4/28/23														
Appraisals	1 mon	Mon 4/3/23 Mon 5/1/23	Fri 5/26/23														
Negotiations	3 mons	Mon 5/29/23															
Execute Agreements	3 mons	Mon 8/21/23															
Construction	900 days	Mon 1/15/24															
Conveyance	545 days	Mon 1/15/24														<b>_</b>	
Phase 1 Conveyance	290 days	Mon 1/15/24															-∔
Bidding and Award	6 wks	Mon 1/15/24												╈ <u></u>			
Construction	12 mons	Mon 2/26/24												₩			
Start-Up and Initial Recharge	Ope1 mon	Mon 1/27/25	Fri 2/21/25													🖕	🛶
Phase 2 Conveyance	290 days	Mon 1/6/25	Fri 2/13/26													┢──	+
Bidding and Award	6 wks	Mon 1/6/25	Fri 2/14/25													📥	▲
Construction	12 mons	Mon 2/17/25	Fri 1/16/26													.	♥
Start-Up and Initial Recharge	Ope1 mon	Mon 1/19/26	Fri 2/13/26														
Recharge Basins	545 days	Mon 2/26/24	Fri 3/27/26											∎ <del>     </del>			+
Phase 1 Recharge	290 days	Mon 2/26/24	Fri 4/4/25													—	+++
Bidding and Award	6 wks	Mon 2/26/24	Fri 4/5/24											<b>*</b>			
Construction	12 mons	Mon 4/8/24	Fri 3/7/25											*		_	📥
Start-Up and Initial Recharge	Ope1 mon	Mon 3/10/25	Fri 4/4/25														
Phase 2 Recharge	290 days	Mon 2/17/25															<u>∎</u> +
Bidding and Award Construction	6 wks	Mon 2/17/25															
Construction	12 mons	Mon 3/31/25															
Start-Up and Initial Recharge		Mon 3/2/26															
Recovery System	665 days	Mon 12/9/24														-	
Phase 1 Recovery	410 days	Mon 12/9/24															
Bidding and Award	6 wks	Mon 12/9/24															
Construction	18 mons	Mon 1/20/25														<b>1</b>	
Start-Up and Initial Recovery		Mon 6/8/26															
Phase 2 Recovery	410 days	Mon 12/1/25															
Bidding and Award	6 wks	Mon 12/1/25															
Construction	18 mons	Mon 1/12/26															
Start-Up and Initial Recovery	ope 1 mon	Mon 5/31/27	FTI 6/25/27		<u> </u>												
2022-0302 Agustorra 5			lestone	•	Project Common		Inactive Mileston	0	Manual Tack		Manual Common Deller	10 Chart	nhy F	Extornal Tasks		line a	4
2022-0302 AquaTerra S te 4/26/22 Task Split		Mil		* I	Project Summary Inactive Task	0	Inactive Milestone	\$ 	Manual Task Duration-only		Manual Summary Rollu Manual Summary	Start-or Finish-o		External Tasks External Milestone	Dead Critic		¢

